



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

JAMES H. TROGDON, III  
SECRETARY

October 3, 2018

**Addendum No. 1**

RE: **Pipe Replacements**  
**Wayne County**

To Whom It May Concern:


Reference is made to the above-mentioned project. The following changes/additions/deletions have been made:

1. We have received the shop drawings for the replacement pipes. One of the proposed pipe sizes have changed. Please replace the site information on page 44 of the proposal with the attached page. Line item 17 has also been corrected; please replace page 86 of the proposal with the attached page 86.

***This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.***

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:  
  
BD9FE36C1AA642B...  
10/3/2018

Vickie P. Gardner  
Division Four Proposals Engineer

VPG/  
Attachment

County	Site/ WBS	Road No.	Road Name	Latitude	Longitude	Proposed Pipe	Pipe Length	Inlet Headwall Length	Outlet headwall Length
Wayne	DF15404.2096128	SR 1209	Brock Road	35.31155	-78.18378	1 @ 95" x 67" CMPA w/ HW	47'	18'	18'
Wayne	DF15404.2096101	SR 1006	Falling Creek	35.32003	-78.15586	1 @ 81" x 59" CMPA w/ HW	54'	27'	27'
Wayne	DF15404.2096156	SR 1746	Mark Herring	35.19082	-77.87044	1 @ 112" x 75" CMPA w/ HW	44'	31.5'	31.5'
Wayne	DF15404.2096208	SR 1960	Spring bank road	35.30353	-77.92433	1 @ 81" x 59" CMPA w/ HW	48'	22.5'	22.5'
Wayne	DF15404.2096828	SR 1948	Camp Jubilee rd	35.22047	-77.92112	1 @ 95" x 67" CMPA w/ HW	48'	22.5'	22.5'
Wayne	DF15404.2096812	SR 1746	Mark Herring	35.21337	-77.86418	1 @ 10'-9" x 6'-10" CASPPA w/ HW	45'	27'	27'

**North Carolina Dept. of Transportation Bid Form**

ITEM	SECT	DESCRIPTION	QTY.	UNIT	UNIT PRICE	AMOUNT BID
1	SP	MOBILIZATION	6	EA		
2	SP	EXPLORATORY EXCAVATION	30	HR		
3	SP	BACK HOE	15	HR		
4	SP	EXCAVATOR	35	HR		
5	SP	PIPE TRANSPORT	15	HR		
6	200	CLEARING AND GRUBBING	0.15	ACR		
7	230	BORROW EXCAVATION	120	CY		
8	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	750	SY		
9	SP	EXCAVATION	2000	CY		
10	SP	BACKFILL	1000	CY		
11	270	GEOTEXTILE FOR SOIL STABILIZATION	120	SY		
12	300	FOUNDATION CONDITIONING MATERIAL, MINOR STURCTURES	360	TON		
13	300	FOUNDATION CONDITIONING GEOTEXTILE	360	SY		
14	520	CLASS IV SELECT MATERIAL	3000	TON		
15	SP	DF15404.2096128 - INSTALLATION OF NCDOT PROVIDED 47 LF OF 95" x 67" CMPA w/ 36 LF OF HEADWALLS	1	EA		
16	SP	DF15404.2096101 - INSTALLATION OF NCDOT PROVIDED 54 LF OF 81" x 59" CMPA w/ 54 LF OF HEADWALLS	1	EA		
17	SP	DF15404.2096156 - INSTALLATION OF NCDOT PROVIDED 44 LF OF 112" x 75" CMPA w/ 63 LF OF HEADWALLS	1	EA		