



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

October 29, 2020

Addendum No. 1

RE: **DD00330**
Edgecombe County

To Whom It May Concern:

Reference is made to the above-mentioned project. The following changes have been made:

1. The Incidental Milling Quantity, Line Item #3, was overlooked on Map 4. Please replace the Summary of Quantities page and the Itemized Proposal sheets in the proposal with the attached sheets.

This sheet and attachments shall be made a part of the plans and bid documents and shall be submitted with the bid. Bids submitted without the addenda and attachments will be considered non-responsive.

If there are any questions, please contact me at (252) 640-6433.

Sincerely,

DocuSigned by:
Vickie P. Gardner
BD9FE36C1AA642B...

10/29/2020

Vickie P. Gardner
Division Four Proposals Engineer

VPG/
Attachments

PROJECT NO.	SHEET NO.	TOTAL NO.
2021CPT.04.08.10331, 2021CPT.04.08.20331	1	2

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	1297000000-E	1330000000-E	1491000000-E	1519000000-E	1523000000-E	1575000000-E	1704000000-E	2845000000-N	7444000000-E		
												1.5" MILLING	INCIDENTAL MILLING	BASE COURSE, B25.0C	SURFACE COURSE, S9.5B	SURFACE COURSE, S9.5C	ASPHALT BINDER FOR PLANT MIX	PATCHING EXISTING PAVEMENT	ADJ. OF METER OR VALVE BOX	INDUCTIVE LOOP		
												MI	FT	SY	SY	TONS	TONS	TONS	TONS	EA	LF	
2021CPT.04.08.10331	Edgecombe	1	NC 43	FROM NC 43 BUS TO US 64 ALT	1, 2	2	2WU	NO	NO	1.99	24	44,973	2,400			3,990	239			1,050		
2021CPT.04.08.10331	Edgecombe	2	NC 43	FROM SR 1126 TO SR 1126	1	2	2WU	NO	NO	5.902	32	112,192	2,500			9,736	584					
2021CPT.04.08.10331	Edgecombe	3	NC 97	FROM HALIFAX CO. LINE TO US 258	3	2	2WU	NO	NO	3.13	26.5	48,661	1,430			4,232	254					
TOTAL FOR PROJ NO. 2021CPT.04.08.10331												11.022		205,826	6,330		17,958	1,077			1,050	
2021CPT.04.08.20331	Edgecombe	4	SR 1002	FROM SR 1006 TO ROCKY MOUNT CITY LIMITS	4	2	2WU	NO	NO	2.75	22.5		400		3,386		227		1			
2021CPT.04.08.20331	Edgecombe	5	SR 1220	FROM SR 1006 TO SR 1218	4	2	2WU	NO	NO	1.89	21				1,942		130					
2021CPT.04.08.20331	Edgecombe	6	SR 1253	FROM NC 97 TO NC 33	4	2	2WU	NO	NO	3.38	25		300		4,190		281	200				
2021CPT.04.08.20331	Edgecombe	7	SR 1426	FROM NC 33 TO SR 1429	4	2	2WU	NO	NO	2.93	19				2,712		182					
2021CPT.04.08.20331	Edgecombe	8	SR 1427	NC 33 TO SR 1429	5	2	2WU	NO	NO	2.81	23			1,629	3,145		284					
TOTAL FOR PROJ NO. 2021CPT.04.08.20331												13.76		700	1,629	15,375		1,104	200	1		
GRAND TOTAL												24.782		205,826	7,030	1,629	15,375	17,958	2,181	200	1	1,050

County : Edgemcombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH 1.5"	205,826 SY		
0003	1330000000-E	607	INCIDENTAL MILLING	7,030 SY		
0004	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,629 TON		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	15,375 TON		
0006	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	17,958 TON		
0007	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	2,181 TON		
0008	1704000000-E	SP	PATCHING EXISTING PAVEMENT	200 TON		
0009	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		
0010	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	1,420 SF		
0011	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0012	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	150,009 LF		
0013	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	58,469 LF		
0014	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	573 LF		
0015	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	200 LF		
0016	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	52 EA		
0017	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") TYPE 2	3,040 LF		

County : Edgecombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,040	LF	
0019	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM 24", 90 MILS - THERMO PM LINES	327	LF	
0020	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM 4" HOT SPRAY THERMO PM LINES (50 MILS)	257,038	LF	
0021	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM NON-CAST IRON SNOWPLOWABLE PAVEMENT MARKERS	950	EA	
0022	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM THERMO PM CHARACTER - 90 MIL	12	EA	
0023	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,050	LF	

0921/Oct29/Q726382.0/D82281100000/E23

Total Amount Of Bid For Entire Project :