

**STATE OF NORTH CAROLINA**  
**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**

**STRUCTURE**  
**SUBSURFACE INVESTIGATION**

PROJ. REFERENCE NO. 45350.1.13 (BD-5104L) F.A. PROJ. NA  
COUNTY NASH  
PROJECT DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW

**CONTENTS**

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE
5, 6	CROSS SECTIONS
7-9	BORE LOGS

**CAUTION NOTICE**

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT 1909 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU UN-PLACED TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

**PROJECT: 45350.1.13 ID: BD-5104L**

**PERSONNEL**

N.D. MOHS

O.B. OIT


TERRACON

INVESTIGATED BY N.D. MOHS

CHECKED BY N.T. ROBERSON

SUBMITTED BY N.T. ROBERSON

DATE MAY 2013



DRAWN BY: I.T. WALKER

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**

PROJECT REFERENCE NO.  
45350.113 (BD-5104L)

SHEET NO.  
2

**SUBSURFACE INVESTIGATION**

**SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION		GRADATION		ROCK DESCRIPTION		TERMS AND DEFINITIONS																																																																																																																																																																														
<p>SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 300 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE:</p> <p align="center"><i>VERY STIFF, NON-SILT CLAY, MOST WITH INTERMEDIATE FINE SAND UNIFORM PLASTIC, A-7-6</i></p>		<p><b>WELL GRADED</b> - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. <b>UNIFORM</b> - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. ALSO <b>POORLY GRADED</b>.</p> <p><b>GAP-GRADED</b> - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.</p> <p align="center"><b>ANGULARITY OF GRAINS</b></p> <p>THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS: <b>ANGULAR</b>, <b>SUBANGULAR</b>, <b>SUBROUNDED</b>, OR <b>ROUNDED</b>.</p>		<p><b>HARD ROCK</b> IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 63 FOOT PER 60 BLOWS, IN NON-COASTAL PLAIN MATERIAL. THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK.</p> <p>ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>		<p><b>ALLUVIUM (ALUV.)</b> - SOILS THAT HAVE BEEN TRANSPORTED BY WATER.</p> <p><b>AQUIFER</b> - A WATER BEARING FORMATION OR STRATA.</p> <p><b>ARENACEOUS</b> - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND.</p> <p><b>ARGILLACEOUS</b> - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC.</p> <p><b>ARTESIAN</b> - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE.</p> <p><b>CALCAREOUS (CALC.)</b> - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE.</p> <p><b>COLLUVIUM</b> - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE.</p> <p><b>CORE RECOVERY (REC.)</b> - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.</p> <p><b>DIKE</b> - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK.</p> <p><b>DIP</b> - THE ANGLE AT WHICH A STRATUM OR ANY PLANNED FEATURE IS INCLINED FROM THE HORIZONTAL.</p> <p><b>DIP DIRECTION (DIP AZIMUTH)</b> - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH.</p> <p><b>FAULT</b> - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE.</p> <p><b>FISSILE</b> - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES.</p> <p><b>FLOAT</b> - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL.</p> <p><b>FLOOD PLAIN (FP)</b> - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM.</p> <p><b>FORMATION (FOL)</b> - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD.</p> <p><b>JOINT</b> - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED.</p> <p><b>LEDGE</b> - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT.</p> <p><b>LENS</b> - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS.</p> <p><b>MOTTLED (MOT.)</b> - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE.</p> <p><b>PENCHED WATER</b> - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM.</p> <p><b>RESIDUAL (RES.) SOIL</b> - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK.</p> <p><b>ROCK QUALITY DESIGNATION (RQD)</b> - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE.</p> <p><b>SAPROLITE (SAP.)</b> - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK.</p> <p><b>SHAL</b> - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS.</p> <p><b>SLICKENSIDE</b> - POLISHED AND STRATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE.</p> <p><b>STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT)</b> - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 63 FOOT PER 60 BLOWS.</p> <p><b>STRATA CORE RECOVERY (SREC)</b> - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.</p> <p><b>STRATA ROCK QUALITY DESIGNATION (SRQD)</b> - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE.</p> <p><b>TOPSOIL (TS)</b> - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>																																																																																																																																																																														
<p align="center"><b>SOIL LEGEND AND AASHTO CLASSIFICATION</b></p> <table border="1"> <tr> <th rowspan="2">GENERAL CLASS.</th> <th colspan="7">GRANULAR MATERIALS (&lt; 36% PASSING #200)</th> <th colspan="7">SILT-CLAY MATERIALS (&gt; 36% PASSING #200)</th> <th colspan="3">ORGANIC MATERIALS</th> </tr> <tr> <th>A-1</th> <th>A-3</th> <th>A-2</th> <th>A-4</th> <th>A-5</th> <th>A-6</th> <th>A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> <th>A-6, A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> <th>A-6, A-7</th> <th>A-1, A-2</th> <th>A-3</th> <th>A-4, A-5</th> </tr> <tr> <th>GROUP CLASS.</th> <td colspan="2">A-1-a</td> <td colspan="2">A-1-b</td> <td colspan="2">A-2-1</td> <td colspan="2">A-2-2</td> <td colspan="2">A-2-3</td> <td colspan="2">A-2-4</td> <td colspan="2">A-2-5</td> <td colspan="2">A-2-6</td> <td colspan="2">A-2-7</td> </tr> <tr> <th>SYMBOL</th> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> <td colspan="2"></td> </tr> <tr> <th>% PASSING</th> <td colspan="2">30 MM</td> <td colspan="2">4.75</td> <td colspan="2">75</td> <td colspan="2">200</td> <td colspan="2">40</td> <td colspan="2">60</td> <td colspan="2">200</td> <td colspan="2">200</td> <td colspan="2">200</td> </tr> <tr> <th>LIQUID LIMIT PLASTIC INDEX</th> <td colspan="2">0-5</td> <td colspan="2">6-15</td> <td colspan="2">16-25</td> <td colspan="2">26 OR MORE</td> <td colspan="2">0-5</td> <td colspan="2">6-15</td> <td colspan="2">16-25</td> <td colspan="2">26 OR MORE</td> <td colspan="2">0-5</td> </tr> <tr> <th>GROUP INDEX</th> <td colspan="2">0</td> <td colspan="2">0</td> <td colspan="2">4</td> <td colspan="2">10</td> <td colspan="2">10</td> <td colspan="2">10</td> <td colspan="2">10</td> <td colspan="2">10</td> <td colspan="2">10</td> </tr> <tr> <th>USUAL TYPES OF MAJOR MATERIALS</th> <td colspan="2">SAND</td> <td colspan="2">FINE SAND</td> <td colspan="2">SANDY SILT</td> <td colspan="2">SILT</td> <td colspan="2">SILT</td> <td colspan="2">SILT</td> <td colspan="2">SILT</td> <td colspan="2">SILT</td> <td colspan="2">SILT</td> </tr> <tr> <th>GENERAL RATING AS A SUBGRADE</th> <td colspan="2">EXCELLENT TO GOOD</td> <td colspan="2">FAIR TO POOR</td> <td colspan="2">FAIR TO POOR</td> <td colspan="2">POOR</td> <td colspan="2">POOR</td> <td colspan="2">POOR</td> <td colspan="2">POOR</td> <td colspan="2">POOR</td> <td colspan="2">POOR</td> </tr> </table> <p align="center">PI OF A-7-5 SUBGROUP IS ≤ LL - 30; PI OF A-7-6 SUBGROUP IS ≥ LL - 30</p>		GENERAL CLASS.	GRANULAR MATERIALS (< 36% PASSING #200)							SILT-CLAY MATERIALS (> 36% PASSING #200)							ORGANIC MATERIALS			A-1	A-3	A-2	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7	A-1, A-2	A-3	A-4, A-5	GROUP CLASS.	A-1-a		A-1-b		A-2-1		A-2-2		A-2-3		A-2-4		A-2-5		A-2-6		A-2-7		SYMBOL																			% PASSING	30 MM		4.75		75		200		40		60		200		200		200		LIQUID LIMIT PLASTIC INDEX	0-5		6-15		16-25		26 OR MORE		0-5		6-15		16-25		26 OR MORE		0-5		GROUP INDEX	0		0		4		10		10		10		10		10		10		USUAL TYPES OF MAJOR MATERIALS	SAND		FINE SAND		SANDY SILT		SILT		SILT		SILT		SILT		SILT		SILT		GENERAL RATING AS A SUBGRADE	EXCELLENT TO GOOD		FAIR TO POOR		FAIR TO POOR		POOR		POOR		POOR		POOR		POOR		POOR		<p align="center"><b>MINERALOGICAL COMPOSITION</b></p> <p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.</p>		<p align="center"><b>COMPRESSIBILITY</b></p> <p>SLIGHTLY COMPRESSIBLE MODERATELY COMPRESSIBLE HIGHLY COMPRESSIBLE</p> <p>LIQUID LIMIT LESS THAN 30 LIQUID LIMIT EQUAL TO 30-50 LIQUID LIMIT GREATER THAN 50</p>		<p align="center"><b>WEATHERING</b></p> <p><b>FRESH</b> - ROCK FRESH, CRYSTALLINE BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING, ROCK RINGS UNDER HAMMER IF CRYSTALLINE.</p> <p><b>VERY SLIGHT (V SLJ)</b> - ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY, ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.</p> <p><b>SLIGHT (SLJ)</b> - ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED, CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.</p> <p><b>MODERATE (MOD.)</b> - SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.</p> <p><b>MODERATELY SEVERE (MOD. SEV.)</b> - ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE ENCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLINK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL.</i></p> <p><b>SEVERE (SEV.)</b> - ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED, ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUE &gt; 100 BPF.</i></p> <p><b>VERY SEVERE (V SEV.)</b> - ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED, ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &lt; 100 BPF.</i></p> <p><b>COMPLETE</b> - ROCK REDUCED TO SOIL, ROCK FABRIC NOT DISCERNIBLE OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.</p>		<p align="center"><b>GROUND WATER</b></p> <p> WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING</p> <p> STATIC WATER LEVEL AFTER 24 HOURS</p> <p> PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA</p> <p> SPRING OR SEEP</p>		<p align="center"><b>MISCELLANEOUS SYMBOLS</b></p> <p> ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</p> <p> SOIL SYMBOL</p> <p> ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</p> <p> INFERRED SOIL BOUNDARY</p> <p> INFERRED ROCK LINE</p> <p> ALLUVIAL SOIL BOUNDARY</p> <p> DIP &amp; DIP DIRECTION OF ROCK STRUCTURES</p> <p> SPT TEST BORING</p> <p> AUGER BORING</p> <p> CORE BORING</p> <p> MONITORING WELL</p> <p> PIEZOMETER INSTALLATION</p> <p> SLOPE INDICATOR INSTALLATION</p> <p> CONE PENETROMETER TEST</p> <p> SOUNDING ROD</p>	
GENERAL CLASS.	GRANULAR MATERIALS (< 36% PASSING #200)							SILT-CLAY MATERIALS (> 36% PASSING #200)							ORGANIC MATERIALS																																																																																																																																																																					
	A-1	A-3	A-2	A-4	A-5	A-6	A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7	A-1, A-2	A-3	A-4, A-5	A-6, A-7	A-1, A-2	A-3	A-4, A-5																																																																																																																																																																		
GROUP CLASS.	A-1-a		A-1-b		A-2-1		A-2-2		A-2-3		A-2-4		A-2-5		A-2-6		A-2-7																																																																																																																																																																			
SYMBOL																																																																																																																																																																																				
% PASSING	30 MM		4.75		75		200		40		60		200		200		200																																																																																																																																																																			
LIQUID LIMIT PLASTIC INDEX	0-5		6-15		16-25		26 OR MORE		0-5		6-15		16-25		26 OR MORE		0-5																																																																																																																																																																			
GROUP INDEX	0		0		4		10		10		10		10		10		10																																																																																																																																																																			
USUAL TYPES OF MAJOR MATERIALS	SAND		FINE SAND		SANDY SILT		SILT		SILT		SILT		SILT		SILT		SILT																																																																																																																																																																			
GENERAL RATING AS A SUBGRADE	EXCELLENT TO GOOD		FAIR TO POOR		FAIR TO POOR		POOR		POOR		POOR		POOR		POOR		POOR																																																																																																																																																																			
<p align="center"><b>CONSISTENCY OR DENSENESS</b></p> <table border="1"> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT<sup>2</sup>)</th> </tr> <tr> <td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE</td> <td>&lt; 4 4 TO 10 10 TO 30 30 TO 50 &gt; 50</td> <td>N/A</td> </tr> <tr> <td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD</td> <td>&lt; 2 2 TO 4 4 TO 8 8 TO 15 10 TO 30 &gt; 30</td> <td>&lt; 0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 &gt; 4</td> </tr> </table>		PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 10 TO 30 > 30	< 0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 > 4	<p align="center"><b>TEXTURE OR GRAIN SIZE</b></p> <table border="1"> <tr> <th>U.S. STD. SIEVE SIZE (OPENING IN IN)</th> <th>4</th> <th>10</th> <th>40</th> <th>60</th> <th>200</th> <th>270</th> </tr> <tr> <td></td> <td>4.75</td> <td>2.00</td> <td>0.42</td> <td>0.25</td> <td>0.075</td> <td>0.053</td> </tr> <tr> <th>BOULDER (BLDR.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>COBBLE (COB.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>GRAVEL (GRV.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>COARSE SAND (CSE. SD.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>FINE SAND (F. SD.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>SILT (SL.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>CLAY (CL.)</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>		U.S. STD. SIEVE SIZE (OPENING IN IN)	4	10	40	60	200	270		4.75	2.00	0.42	0.25	0.075	0.053	BOULDER (BLDR.)							COBBLE (COB.)							GRAVEL (GRV.)							COARSE SAND (CSE. SD.)							FINE SAND (F. SD.)							SILT (SL.)							CLAY (CL.)																																																																																																												
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )																																																																																																																																																																																	
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 4 4 TO 10 10 TO 30 30 TO 50 > 50	N/A																																																																																																																																																																																	
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	< 2 2 TO 4 4 TO 8 8 TO 15 10 TO 30 > 30	< 0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 > 4																																																																																																																																																																																	
U.S. STD. SIEVE SIZE (OPENING IN IN)	4	10	40	60	200	270																																																																																																																																																																														
	4.75	2.00	0.42	0.25	0.075	0.053																																																																																																																																																																														
BOULDER (BLDR.)																																																																																																																																																																																				
COBBLE (COB.)																																																																																																																																																																																				
GRAVEL (GRV.)																																																																																																																																																																																				
COARSE SAND (CSE. SD.)																																																																																																																																																																																				
FINE SAND (F. SD.)																																																																																																																																																																																				
SILT (SL.)																																																																																																																																																																																				
CLAY (CL.)																																																																																																																																																																																				
<p align="center"><b>SOIL MOISTURE - CORRELATION OF TERMS</b></p> <table border="1"> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE</td> <td>- MOIST - (M)</td> <td>SOLID AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td>SL - SHRINKAGE LIMIT</td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </table>		SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID AT OR NEAR OPTIMUM MOISTURE	SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<p align="center"><b>ABBREVIATIONS</b></p> <p>AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CORE PENETRATION TEST CSE - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS - FOSSILIFEROUS FRAC - FRACTURED, FRACTURES FRAG. - FRAGMENTS H. - HIGHLY</p> <p>MED. - MEDIUM MICA - MICACEOUS MOD. - MODERATELY NP - NON PLASTIC ORG. - ORGANIC PMT - PRESSUREMETER TEST SAP. - SAPROLITIC SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL w - MOISTURE CONTENT v - VERY</p> <p>VST - VANE SHEAR TEST WEA. - WEATHERED W - UNIT WEIGHT W<sub>d</sub> - DRY UNIT WEIGHT</p> <p align="center"><b>SAMPLE ABBREVIATIONS</b></p> <p>S - BULK SS - SPLIT SPOON ST - SHELBY TUBE RS - ROCK RT - RECOMPACTED TRIAXIAL CBR - CALIFORNIA BEARING RATIO</p>																																																																																																																																																																			
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																																																																		
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																																																																		
PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																		
OM - OPTIMUM MOISTURE	- MOIST - (M)	SOLID AT OR NEAR OPTIMUM MOISTURE																																																																																																																																																																																		
SL - SHRINKAGE LIMIT	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																																																																		
<p align="center"><b>PLASTICITY</b></p> <table border="1"> <tr> <th>NONPLASTIC</th> <th>PLASTICITY INDEX (PI)</th> <th>DRY STRENGTH</th> </tr> <tr> <td>LOW PLASTICITY</td> <td>0-5</td> <td>VERY LOW</td> </tr> <tr> <td>MED. PLASTICITY</td> <td>6-15</td> <td>SLIGHT</td> </tr> <tr> <td>HIGH PLASTICITY</td> <td>16-25</td> <td>MEDIUM</td> </tr> <tr> <td></td> <td>26 OR MORE</td> <td>HIGH</td> </tr> </table>		NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH	LOW PLASTICITY	0-5	VERY LOW	MED. PLASTICITY	6-15	SLIGHT	HIGH PLASTICITY	16-25	MEDIUM		26 OR MORE	HIGH	<p align="center"><b>EQUIPMENT USED ON SUBJECT PROJECT</b></p> <p>DRILL UNITS:</p> <p><input type="checkbox"/> MOBILE B-_____</p> <p><input type="checkbox"/> BK-51</p> <p><input type="checkbox"/> CHE-45C</p> <p><input type="checkbox"/> CHE-550</p> <p><input type="checkbox"/> PORTABLE HOIST</p> <p><input checked="" type="checkbox"/> CME-75</p> <p>ADVANCING TOOLS:</p> <p><input type="checkbox"/> CLAY BITS</p> <p><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</p> <p><input checked="" type="checkbox"/> 6" HOLLOW AUGERS</p> <p><input checked="" type="checkbox"/> HARD FACED FINGER BITS</p> <p><input type="checkbox"/> TUNG-CARBIDE INSERTS</p> <p><input checked="" type="checkbox"/> CASING _____ w/ ADVANCER</p> <p><input checked="" type="checkbox"/> TRICONE _____ STEEL TEETH</p> <p><input type="checkbox"/> TRICONE _____ TUNG-CARB.</p> <p><input type="checkbox"/> CORE BIT</p> <p>HAMMER TYPE:</p> <p><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</p> <p>CORE SIZE:</p> <p><input type="checkbox"/> 4</p> <p><input type="checkbox"/> 6</p> <p><input type="checkbox"/> 8</p> <p>HAND TOOLS:</p> <p><input type="checkbox"/> POST HOLE DIGGER</p> <p><input type="checkbox"/> HAND AUGER</p> <p><input type="checkbox"/> SOUNDING ROD</p> <p><input type="checkbox"/> VANE SHEAR TEST</p>																																																																																																																																																																			
NONPLASTIC	PLASTICITY INDEX (PI)	DRY STRENGTH																																																																																																																																																																																		
LOW PLASTICITY	0-5	VERY LOW																																																																																																																																																																																		
MED. PLASTICITY	6-15	SLIGHT																																																																																																																																																																																		
HIGH PLASTICITY	16-25	MEDIUM																																																																																																																																																																																		
	26 OR MORE	HIGH																																																																																																																																																																																		
<p align="center"><b>INDURATION</b></p> <p>FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.</p> <p>FRIABLE - RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.</p> <p>MODERATELY INDURATED - GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.</p> <p>INDURATED - GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.</p> <p>EXTREMELY INDURATED - SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.</p>		<p align="center"><b>ROCK HARDNESS</b></p> <p>VERY HARD - CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.</p> <p>HARD - CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.</p> <p>MODERATELY HARD - CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE ENCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.</p> <p>MEDIUM HARD - CAN BE GROOVED OR GOUGED 0.625 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE ENCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.</p> <p>SOFT - CAN BE GROOVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE ENCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.</p> <p>VERY SOFT - CAN BE CARVED WITH KNIFE. CAN BE ENCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGERNAIL.</p>																																																																																																																																																																																		
<p align="center"><b>FRACTURE SPACING</b></p> <table border="1"> <tr> <th>TERM</th> <th>SPACING</th> </tr> <tr> <td>VERY WIDE</td> <td>MORE THAN 30 FEET</td> </tr> <tr> <td>WIDE</td> <td>3 TO 10 FEET</td> </tr> <tr> <td>MODERATELY CLOSE</td> <td>1 TO 3 FEET</td> </tr> <tr> <td>CLOSE</td> <td>0.16 TO 1 FEET</td> </tr> <tr> <td>VERY CLOSE</td> <td>LESS THAN 0.16 FEET</td> </tr> </table>		TERM	SPACING	VERY WIDE	MORE THAN 30 FEET	WIDE	3 TO 10 FEET	MODERATELY CLOSE	1 TO 3 FEET	CLOSE	0.16 TO 1 FEET	VERY CLOSE	LESS THAN 0.16 FEET	<p align="center"><b>BEDDING</b></p> <table border="1"> <tr> <th>TERM</th> <th>THICKNESS</th> </tr> <tr> <td>VERY THICKLY BEDDED</td> <td>&gt; 4 FEET</td> </tr> <tr> <td>THICKLY BEDDED</td> <td>1.5 - 4 FEET</td> </tr> <tr> <td>THINLY BEDDED</td> <td>0.16 - 1.5 FEET</td> </tr> <tr> <td>VERY THINLY BEDDED</td> <td>0.03 - 0.16 FEET</td> </tr> <tr> <td>THICKLY LAMINATED</td> <td>0.008 - 0.03 FEET</td> </tr> <tr> <td>THINLY LAMINATED</td> <td>&lt; 0.008 FEET</td> </tr> </table>		TERM	THICKNESS	VERY THICKLY BEDDED	> 4 FEET	THICKLY BEDDED	1.5 - 4 FEET	THINLY BEDDED	0.16 - 1.5 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET	THINLY LAMINATED	< 0.008 FEET																																																																																																																																																							
TERM	SPACING																																																																																																																																																																																			
VERY WIDE	MORE THAN 30 FEET																																																																																																																																																																																			
WIDE	3 TO 10 FEET																																																																																																																																																																																			
MODERATELY CLOSE	1 TO 3 FEET																																																																																																																																																																																			
CLOSE	0.16 TO 1 FEET																																																																																																																																																																																			
VERY CLOSE	LESS THAN 0.16 FEET																																																																																																																																																																																			
TERM	THICKNESS																																																																																																																																																																																			
VERY THICKLY BEDDED	> 4 FEET																																																																																																																																																																																			
THICKLY BEDDED	1.5 - 4 FEET																																																																																																																																																																																			
THINLY BEDDED	0.16 - 1.5 FEET																																																																																																																																																																																			
VERY THINLY BEDDED	0.03 - 0.16 FEET																																																																																																																																																																																			
THICKLY LAMINATED	0.008 - 0.03 FEET																																																																																																																																																																																			
THINLY LAMINATED	< 0.008 FEET																																																																																																																																																																																			
<p align="center"><b>COLOR</b></p> <p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>		<p align="center"><b>NOTES:</b></p> <p>BENCH MARK: BL-100; BL- STATION 18+69.34</p> <p align="right">ELEVATION: 175.57 FT.</p>																																																																																																																																																																																		

PROJECT REFERENCE NO.	SHEET
45350.1.13 (BD-5104L)	3
<b>SITE PLAN</b>	
 0                      40                      80 FEET	

25+00

27+00



WOODS

WOODS

STONEY HILL CHURCH RD. (SR-1109)

63-0

BL-100

4-SPAN CONC.&WOOD  
W/4 WOODEN WW


WOODS


WOODS

TURKEY CREEK


WOODS

TURKEY CREEK OVERFLOW








PROJECT REFERENCE NO.	SHEET
43350.113 (BD-5104L)	4
PROFILE OF BORINGS PROJECTED ALONG -L-	



NOTE: GROUNDLINE PROFILE TAKEN FROM HYDRAULIC REPORT DATED 04/12/2013




CROSS SECTION THROUGH END BENT 1



CROSS SECTION THROUGH BENT 1

(A) ALLUVIAL GRAY-BROWN, WET, LOOSE, SILTY SAND AND MEDIUM STIFF, SILTY CLAY



VE = 1:1

CROSS SECTION THROUGH END BENT 2



**NCDOT GEOTECHNICAL ENGINEERING UNIT**  
**BORELOG REPORT**

WBS 45350.1.13	TIP BD-5104L	COUNTY NASH	GEOLOGIST Oti, O. B.	
SITE DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW				GROUND WTR (ft)
BORING NO. EB1-A	STATION 25+03	OFFSET 12 ft LT	ALIGNMENT -L-	0 HR. 19.0
COLLAR ELEV. 176.4 ft	TOTAL DEPTH 38.7 ft	NORTHING 748,225	EASTING 2,244,127	24 HR. 7.5
DRILL RIG/HAMMER EFF./DATE TER6847 CME-75 91% 02/02/2012		DRILL METHOD H.S. Augers		HAMMER TYPE Automatic
DRILLER Contract Driller	START DATE 05/08/13	COMP. DATE 05/08/13	SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
180													GROUND SURFACE	176.4	0.0
175	173.3	3.1	1	2	3							M	ROADWAY EMBANKMENT TAN-BROWN, SANDY SILT		
170	168.3	8.1	1	1	3							M	RESIDUAL GRAY-BROWN, SILTY CLAY	169.4	7.0
165	163.3	13.1	1	2	5							M	TAN-BROWN, SAPROLITIC, SANDY SILT	162.9	13.5
160	158.3	18.1	3	4	22							M	GRAY-BROWN, SAPROLITIC, SILTY CLAY	157.4	19.0
155	153.3	23.1	4	8	20							M			
150	148.3	28.1	26	53	47/0.4							M			
145	143.3	33.1	20	45	55/0.4							M	WEATHERED ROCK (META-ARGILLITE)	147.8	28.6
140	138.3	38.1	70	30/0.1								M		137.7	38.7

Boring Terminated at Elevation 137.7 ft in WEATHERED ROCK (META-ARGILLITE)

WBS 45350.1.13	TIP BD-5104L	COUNTY NASH	GEOLOGIST Oti, O. B.	
SITE DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW				GROUND WTR (ft)
BORING NO. EB1-B	STATION 25+03	OFFSET 12 ft RT	ALIGNMENT -L-	0 HR. 18.0
COLLAR ELEV. 176.1 ft	TOTAL DEPTH 39.3 ft	NORTHING 748,204	EASTING 2,244,115	24 HR. 7.7
DRILL RIG/HAMMER EFF./DATE TER6847 CME-75 91% 02/02/2012		DRILL METHOD H.S. Augers		HAMMER TYPE Automatic
DRILLER Contract Driller	START DATE 05/08/13	COMP. DATE 05/08/13	SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION	ELEV. (ft)	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
180													GROUND SURFACE	176.1	0.0
175	173.0	3.1	1	2	2							M	ROADWAY EMBANKMENT TAN-BROWN, SANDY SILT		
170	168.0	8.1	2	4	5							M	RESIDUAL TAN, BROWN, AND GRAY, SAPROLITIC, SILTY CLAY	171.1	5.0
165	163.0	13.1	4	8	9							M			
160	158.0	18.1	8	8	15							M			
155	153.0	23.1	2	8	11							M			
150	148.0	28.1	25	40	50							M			
145	143.0	33.1	19	33	51							M			
140	138.0	38.1	23	51	49/0.2							M		137.5	38.6


Boring Terminated at Elevation 138.8 ft in WEATHERED ROCK (META-ARGILLITE)



# NCDOT GEOTECHNICAL ENGINEERING UNIT


## BORELOG REPORT

WBS 45350.1.13	TIP BD-5104L	COUNTY NASH	GEOLOGIST Oti, O. B.
SITE DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW			GROUND WTR (ft)
BORING NO. B1-A	STATION 25+40	OFFSET 7 ft LT	ALIGNMENT -L-
COLLAR ELEV. 167.2 ft	TOTAL DEPTH 40.5 ft	NORTHING 748,202	EASTING 2,244,157
DRILL RIG/HAMMER EFF./DATE TER6847 CME-75 91% 02/02/2012		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Contract Driller	START DATE 05/07/13	COMP. DATE 05/07/13	SURFACE WATER DEPTH 0.6ft



Boring Terminated at Elevation 128.7 ft in SILTY CLAY

WBS 45350.1.13	TIP BD-5104L	COUNTY NASH	GEOLOGIST Oti, O. B.
SITE DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW			GROUND WTR (ft)
BORING NO. B1-B	STATION 25+40	OFFSET 7 ft RT	ALIGNMENT -L-
COLLAR ELEV. 167.9 ft	TOTAL DEPTH 45.3 ft	NORTHING 748,190	EASTING 2,244,150
DRILL RIG/HAMMER EFF./DATE TER6847 CME-75 91% 02/02/2012		DRILL METHOD Mud Rotary	HAMMER TYPE Automatic
DRILLER Contract Driller	START DATE 05/06/13	COMP. DATE 05/07/13	SURFACE WATER DEPTH N/A



Boring Terminated at Elevation 122.6 ft in WEATHERED ROCK (META-ARGILLITE)

NCDOT BORE DOUBLE BD-5104L GEO BH BRDGG080.GPJ NC DOT.GDT 5/15/13





# NCDOT GEOTECHNICAL ENGINEERING UNIT

## BORELOG REPORT

WBS 45350.1.13	TIP BD-5104L	COUNTY NASH	GEOLOGIST Oti, O. B.	
SITE DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW				GROUND WTR (ft)
BORING NO. EB2-A	STATION 25+86	OFFSET 8 ft LT	ALIGNMENT -L-	0 HR. 10.2
COLLAR ELEV. 176.3 ft	TOTAL DEPTH 28.9 ft	NORTHING 748,180	EASTING 2,244,197	24 HR. FIAD
DRILL RIG/HAMMER EFF./DATE TER6847 CME-75 91% 02/02/2012		DRILL METHOD H.S. Augers		HAMMER TYPE Automatic
DRILLER Contract Driller	START DATE 05/08/13	COMP. DATE 05/08/13	SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
180													GROUND SURFACE	0.0
175	173.1	3.2	2	2	3							M	ROADWAY EMBANKMENT TAN-BROWN, SANDY SILT	6.0
170	168.1	8.2	12	13	9							M	RESIDUAL TAN-BROWN, SANDY SILT	11.7
165	163.1	13.2	8	20	24							M	TAN-BROWN, SAPROLITIC, SILTY CLAY	17.0
160	158.1	18.2	100/0.3							100/0.3		M	WEATHERED ROCK (META-ARGILLITE)	26.9
155	153.1	23.2	88	42/0.2						100/0.7				
150	148.1	28.2	40	60/0.2						100/0.7				
														Boring Terminated at Elevation 147.4 ft in WEATHERED ROCK (META-ARGILLITE)

WBS 45350.1.13	TIP BD-5104L	COUNTY NASH	GEOLOGIST Oti, O. B.	
SITE DESCRIPTION BRIDGE NO. 60 ON SR 1109 (STONE HILL CHURCH ROAD) OVER TURKEY CREEK OVERFLOW				GROUND WTR (ft)
BORING NO. EB2-B	STATION 25+86	OFFSET 13 ft RT	ALIGNMENT -L-	0 HR. 4.2
COLLAR ELEV. 176.3 ft	TOTAL DEPTH 34.5 ft	NORTHING 748,182	EASTING 2,244,186	24 HR. 5.5
DRILL RIG/HAMMER EFF./DATE TER6847 CME-75 91% 02/02/2012		DRILL METHOD H.S. Augers		HAMMER TYPE Automatic
DRILLER Contract Driller	START DATE 05/08/13	COMP. DATE 05/08/13	SURFACE WATER DEPTH N/A	

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				
180													GROUND SURFACE	0.0
175	173.3	3.0	2	3	2							M	ROADWAY EMBANKMENT TAN-BROWN, SANDY SILT	7.0
170	168.3	8.0	2	3	3							M	RESIDUAL TAN-BROWN, SAPROLITIC, SANDY SILT	15.0
165	163.3	13.0	1	3	4							M	TAN-BROWN, SAPROLITIC, SILTY CLAY	23.5
160	158.3	18.0	8	14	20							M	WEATHERED ROCK (META-VOLCANIC)	29.5
155	153.3	23.0	15	50	50/0.2					100/0.7				
150	148.3	28.0	29	48	52/0.4					100/0.9				
145	143.3	33.0	18	28	34									
														Boring Terminated at Elevation 141.8 ft in SANDY SILT

NCDOT BORE DOUBLE BD-5104L GEO BH BRD0080.GPJ NC\_DOT\_GDT 5/15/13