PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.05.03.10921.1, 2017CPT.05.03.20921.1		

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4685000000-E 4" X 90 M WHITE THERMO LF	4685000000-E 4" X 90 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4700000000-E 12" X 90 M YELLOW THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG ONLY 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO STR & LT ARROW 90 M EA	4770000000-E 4" WHITE COLD APPLIED PLASTIC, TYPE II LF	4770000000-E 4" YELLOW COLD APPLIED PLASTIC, TYPE II LF	4810000000-E 4" WHITE PAINT LF	4845000000-N PAINT STR ARROW EA	4850000000-E 4" LINE REMOVAL LF	4900000000-N YELLOW& YELLOW MARKERS EA	4900000000-N CRYSTAL & RED MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS EA	4940000000-N FLEXIBLE DELINEATORS (YELLOW) EA
2017CPT.05.03.10921.1	Wake	1	US 64 WESTBOUND	PAVEMENT JOINT .2 MI WEST OF SR 1163 TO CHATHAM CO	1	2	MD	2.73	40-50	306	0.26	40	29,375	13,930	6,427	48					140		18	5	24					18,018	12				275	
		"	"	JOINT .2 MILES WEST OF NC 55 TO JOINT 95' EAST OF CREEKSIDE LANDING DR	1	2	MD	0.265	40-50	30	0.03	10	1,505	1,400	505	276	150				18			2	4					1,750	2				24	16
TOTAL FOR MAP NO. 1								**2.995**		**336**	**0.29**	**50**	**30,880**	**15,330**	**6,932**	**324**	**150**				**158**		**18**	**7**	**28**					**19,768**	**14**				**299**	**16**
2017CPT.05.03.10921.1	Wake	2	US 64 EASTBOUND	CHATHAM COUNTY LINE TO PAVEMENT JOINT .2 MI WEST OF SR 1163	1	2	MD	2.75	40-50	308	0.26	40	29,590	14,508	5,882								18	1	24					18,150	12				260	
		"	"	JOINT 150' EAST OF CREEKSIDE LANDING TO PAVEMENT JOINT .2 MI WEST OF NC 55	1	2	MD	0.317	40-50	36	0.03	10	1,675	1,675	489			228							4					2,094	2				33	
TOTAL FOR MAP NO. 2								**3.067**		**344**	**0.29**	**50**	**31,265**	**16,183**	**6,371**			**228**					**18**	**1**	**28**					**20,244**	**14**				**293**	
TOTAL FOR PROJ NO. 2017CPT.05.03.10921.1								**6.062**		**680**	**0.58**	**100**	**62,145**	**31,513**	**13,303**	**324**	**150**	**228**			**158**		**36**	**8**	**56**					**40,012**	**28**				**592**	**16**
													93,658		**13,627**		**378**						**100**													
2017CPT.05.03.20921.1	Wake	3	SR 1756 - ELECTRA DR/BRANDYWINE RD	SR 1797 - MEDFIELD DR TO SR 1655 - TRINITY RD	3	2	2WU	0.55	20-25	62	0.02					5,733					36												36			
TOTAL FOR MAP NO. 3								**0.55**		**62**	**0.02**					**5,733**					**36**												**36**			
2017CPT.05.03.20921.1	Wake	4	SR 3002 - ELECTRA DR	SR 1797 - MEDFIELD DR TO SR 3055 - TROPICAL DR	3	2	2WU	0.46	21-25	52	0.02					4,704					14												30			
TOTAL FOR MAP NO. 4								**0.46**		**52**	**0.02**					**4,704**					**14**												**30**			
2017CPT.05.03.20921.1	Wake	5	SR 3014 - MORRISVILLE CARPENTER RD	SR 1613 - DAVIS DR TO .12 MI. E OF SR 1635 - HAMILTON HEDGE PL	3	3	MU	0.85	27-40	126	0.05		4,125		2,405	9,341	130		132	120	36	8	23	9	2	9							141		56	
TOTAL FOR MAP NO. 5								**0.85**		**126**	**0.05**		**4,125**		**2,405**	**9,341**	**130**		**132**	**120**	**36**	**8**	**23**	**9**	**2**	**9**							**141**		**56**	
2017CPT.05.03.20921.1	Wake	6	SR 3070 - WINDY WOODS DR	SR 1655 - TRENTON RD TO DEAD END	3	2	2WU	0.58	20	65	0.02																									
TOTAL FOR MAP NO. 6								**0.58**		**65**	**0.02**																									
2017CPT.05.03.20921.1	Wake	7	SR 3071 - FIELDVIEW CT	SR 3070 - WINDY WOODS DR TO DEAD END	2	2	2WU	0.04	18-20	4	0.01																									
TOTAL FOR MAP NO. 7								**0.04**		**4**	**0.01**																									
2017CPT.05.03.20921.1	Wake	8	SR 3086 - BYERS DR	CUL-DE-SAC - TO CUL-DE-SAC	2	2	2WU	0.12	20	13	0.01																									
TOTAL FOR MAP NO. 8								**0.12**		**13**	**0.01**																									
2017CPT.05.03.20921.1	Wake	9	SR 3087 - ABNEY PLACE	SR 3070 - WINDY WOODS DR TO CUL-DE-SAC	3	2	2WU	0.03	18	3	0.01																									
TOTAL FOR MAP NO. 9								**0.03**		**3**	**0.01**																									
2017CPT.05.03.20921.1	Wake	10	SR 3112 - NW CARY PKWY	FROM SR 1615 - HIGH HOUSE RD TO END OF RR BRIDGE AND FROM NC 54 TO SR 1653 - EVANS RD	4	4	MD	2.68	50	126	0.21				12,701				783		231	8	44	5	42	9	12	925	740			1,665		20	443	
TOTAL FOR MAP NO. 10								**2.68**		**126**	**0.21**				**12,701**				**783**		**231**	**8**	**44**	**5**	**42**	**9**	**12**	**925**	**740**			**1,665**		**20**	**443**	
2017CPT.05.03.20921.1	Wake	11	SR 1157 - JAMES ST	FROM SR 1158 - S HUGHES ST TO SR 1153 - TINGEN RD	3	2	2WU	0.26	19-20	29	0.01		2,746			2,746					60												18			
TOTAL FOR MAP NO. 11								**0.26**		**29**	**0.01**		**2,746**			**2,746**					**60**												**18**			
2017CPT.05.03.20921.1	Wake	12	SR 1171 - PERRY RD	SR 1158 - S HUGHES ST TO END OF PAVEMENT	3	2	2WU	0.55	30-32	62	0.03		788			5,728					40												36			
TOTAL FOR MAP NO. 12								**0.55**		**62**	**0.03**		**788**			**5,728**					**40**												**36**			
2017CPT.05.03.20921.1	Wake	13	SR 1307 - W CHATHAM ST	HUNTER ST TO SR 1011 - S SALEM ST	3	2	2WU	0.67	28-32	75	0.03		4,553	56	28	6,988	54		141		72												45			
TOTAL FOR MAP NO. 13								**0.67**		**75**	**0.03**		**4,553**	**56**	**28**	**6,988**	**54**		**141**		**72**												**45**			
TOTAL FOR PROJ NO. 2017CPT.05.03.20921.1								**6.79**		**617**	**0.42**		**12,212**	**56**	**15,134**	**35,240**	**184**		**1,056**	**120**	**489**	**16**	**67**	**14**	**44**	**18**	**12**	**925**	**740**			**1,665**	**306**	**20**	**499**	
													12,268		**50,374**		**184**						**155**					**1,665**					**326**			
GRAND TOTAL								**12.852**		**1,297**	**1.00**	**100**	**74,357**	**31,569**	**28,437**	**35,564**	**334**	**228**	**1,056**	**120**	**647**	**16**	**103**	**22**	**100**	**18**	**12**	**925**	**740**	**40,012**	**28**	**1,665**	**306**	**20**	**1,091**	**16**
													105,926		**64,001**		**562**						**255**					**1,665**					**326**			