PROJECT REFERENCE NO.	SHEET NO.
2017CPT.05.03.10921.1, etc.	5

PAVEMENT SCHEDULE

C1	1¼" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 137.5 LBS. PER SQ. YD.
C2	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C3	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
D	2½" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0C, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
S	PROP. SHOULDER GRADING
U	EXISTING PAVEMENT
V1	2½" MILLING
V2	0" - 1½" MILLING NEW ASPHALT TO BE PAVED BACK FLUSH
V3	1½" MILLING



INCIDENTAL MILLING



PATCHING EXISTING PAVEMENT

MILLING (IF REQUIRED BY TYPICAL) TO BE PERFORMED PRIOR TO PATCHING



TYPICAL SECTION NO. 2



TYPICAL SECTION NO. 3