

**PROJECT SPECIAL PROVISIONS****ROADWAY****BURNING RESTRICTIONS:**

(7-1-95)

200, 210, 215

SP2 R05

Open burning is not permitted on any portion of the right-of-way limits established for this project. Do not burn the clearing, grubbing or demolition debris designated for disposal and generated from the project at locations within the project limits, off the project limits or at any waste or borrow sites in this county. Dispose of the clearing, grubbing and demolition debris by means other than burning, according to state or local rules and regulations.

**EQUIPMENT**

(2-28-2022)

The Contractor should own or be able to lease the following equipment or equivalent sign truck each equipped with a lift (sign crane or bucket), sign puller and post driver. The truck shall be a minimum of 17,500 GWV with a lift capable of lifting 3200 pounds, fitted with a receiver mount p hook, a puller with 10,000 pounds of pulling force and a minimum 91.5-inch reach, a trigger lever post driver with an impact rate of at least 30 blows per minute and an impact energy of at least 8 I-foot pounds. The equipment shall be in good operating condition with all manufacture's safety devices in place. The equipment shall be equipped with safety flashers adequate for visibility in all directions.

Misc. Equipment: The contractor shall have available various hand tools i.e. pole saw, loppers, hammer and or impact drill, mechanical trimmer, squeegee, fuel and other supporting tools for installation, clearing for visibility and sight distance of new and or existing signs.

The Contractor shall be responsible for all costs or charges incurred in the operation and maintenance of the equipment during the contract period.

**SIGN ERECTOR**

Sign erection shall be in accordance with Section 904 of the *Standard Specifications* as modified herein.

The Department will furnish all signs, mounting hardware, and associated supports for this project in accordance with Section 901 of the *Standard Specifications*. The Contractor will be responsible for picking up all signs from the Traffic Services facility located on Guess Road in Durham. Direct payment for items associated with "Department Furnished Signs" per Section 901 will not be covered under this contract and will be considered incidental to the sign erection.

- The sign erector shall be a trained and qualified with at least 2 years of field experience trained with MUTCD and NCDOT standard specifications, standard drawings, and advance work zone training with up to two qualified sign assistant(s).