PROJECT REFERENCE NO.	SHEET NO.
2017CPT.05.06J0391J, etc.	6

PAVEMENT SCHEDULE

C	1 ½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
D	PROP. APPROX. 2 ½" ASPH. CONC. INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
S	SHOULDER GRADING ASB REQUIRED (EXCEPT AT RESIDENTIAL AREAS)
P	PRIME COAT AT THE RATE OF 0.20-0.50 GALLONS PER SQUARE YARD, AS DIRECTED BY THE ENGINEER
U1	EXISTING PAVEMENT
U2	EXISTING ABC TO BE CONDITIONED AND SHAPED
V	1 ½" MILLING

DETAIL OF PROJECT LIMITS AT SIGNALIZED Y LINES

DETAIL OF PROJECT LIMITS AT UNSIGNALIZED Y LINES

INCIDENTAL MILLING

*SHOULDER RECONSTRUCTION TO BE DONE BY STATE FORCES

TYPICAL SECTION 3

5/14/99
$$$$SYSTIME$$$$
$$$$SYSLOG$$$$
$$$$SYSLOG$$$$
$$$$SYSLOG