PROJECT REFERENCE NO.	SHEET NO.
2017CPT.05.06.J0391.J, etc.	5

PAVEMENT SCHEDULE

C	1 ½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
D	PROP. APPROX. 2 ½" ASPH. CONC. INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
S	SHOULDER GRADING ASB REQUIRED (EXCEPT AT RESIDENTIAL AREAS)
P	PRIME COAT AT THE RATE OF 0.20-0.50 GALLONS PER SQUARE YARD, AS DIRECTED BY THE ENGINEER
U1	EXISTING PAVEMENT
U2	EXISTING ABC TO BE CONDITIONED AND SHAPED
V	1 ½" MILLING

PATCHING EXISTING PAVEMENT

MILLING TO BE PERFORMED PRIOR TO PATCHING

NOTES

ALL UNPAVED S.R. ROADS TO BE RESURFACED 50' FROM EDGE OF PAVEMENT OF MAIN PROJECT
ALL PAVED S.R. ROADS TO BE RESURFACED TO THE ENDS OF THE RADII, OR AS DIRECTED BY THE ENGINEER.
EDGES, PAVEMENT WIDENING, INTERSECTIONS AND BRIDGE FLARES ARE INCLUDED IN THE TABLE OF QUANTITIES.
BRIDGES TO BE RESURFACED AT LOCATIONS AND TO DEPTH AS DIRECTED BY THE ENGINEER.

TYPICAL SECTION 1

TYPICAL SECTION 2

* USE ON MAP 13 FROM SR 1209 TO .12 OF A MILE SOUTH OF THE I-85 BRIDGE
* USE ON MAP 13 FROM US 15 FOR A DISTANCE OF 460'
* USE ON MAP 13 AT THE RR CROSSING