PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.05.06.10391.1, etc.	8	

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4685000000-E 4" X 90 M WHITE THERMO LF	4686000000-E 4" X 120 M YELLOW THERMO LF	4686000000-E 4" X 120 M WHITE THERMO LF	4695000000-E 8" X 90 M WHITE THERMO LF	4695000000-E 8" X 90 M YELLOW THERMO LF	4697000000-E 8" X 120 M WHITE THERMO LF	4700000000-E 12" X 90 M YELLOW THERMO LF	4705000000-E 16" X 120 M WHITE THERMO LF	4710000000-E 24" X 120 M WHITE THERMO LF	4721000000-E THERMO MSG SCHOOL 120 M EA	4721000000-E THERMO RXR 120 M EA	4725000000-E THERMO LT ARROW 90 M EA	4725000000-E THERMO RT ARROW 90 M EA	4725000000-E THERMO STR & RT ARROW 90 M EA	4725000000-E THERMO STR ARROW 90 M EA	4770000000-E 4" WHITE COLD APPLIED PLASTIC, TYPE III LF	4770000000-E 4" YELLOW COLD APPLIED PLASTIC, TYPE II LF	4810000000-E 4" WHITE PAINT LF	4810000000-E 4" YELLOW PAINT LF	4820000000-E 8" WHITE PAINT LF	4825000000-E 12" YELLOW PAINT LF	4835000000-E 24" WHITE PAINT LF	4845000000-N PAINT LT ARROW EA	4845000000-N PAINT STR & RT ARROW EA	4845000000-N PAINT RT ARROW EA	4850000000-E 4" LINE REMOVAL LF	4900000000-N CRYSTAL & RED MARKERS EA	4900000000-N YELLOW & YELLOW MARKERS EA	4905000000-N SNOW PLOWABLE MARKERS EA
2017CPT.05.06.10391.1	Granville	1	NC 49	PERSON CL TO STATE LINE	1	2	2WU	1.93	20	216	0.06	20,500	19,890	76																									128
TOTAL FOR MAP NO. 1								**1.93**		**216**	**0.06**	**20,500**	**19,890**	**76**																									**128**
TOTAL FOR PROJ NO. 2017CPT.05.06.10391.1								**1.93**		**216**	**0.06**	**20,500**	**19,890**	**76**																									**128**
													19,966																										
2017CPT.05.06.20391.1	Granville	2	SR 1100 - E B ST	SR 1103 - CENTRAL AVE TO NC 56 - E C ST	2	2	2WU	0.61	26	68	0.03	5,850	6,135	86						48			8						5,936	6,135			48	8						
TOTAL FOR MAP NO. 2								**0.61**		**68**	**0.03**	**5,850**	**6,135**	**86**						**48**			**8**						**5,936**	**6,135**			**48**	**8**						
2017CPT.05.06.20391.1	Granville	3	SR 1102 - WILL SUITT RD	US 15 TO SR 1103 - GATE TWO RD	1	2	2WU	2.61	22	292	0.09	27,415	25,555	98																									
TOTAL FOR MAP NO. 3								**2.61**		**292**	**0.09**	**27,415**	**25,555**	**98**																									
2017CPT.05.06.20391.1	Granville	4	SR 1106 - WILL SUITT RD	SR1103 - GATE TWO RD TO SR 1104 - E LYON STATION RD	1	2	2WU	1.51	20	169	0.05	15,900	13,100	40																									
TOTAL FOR MAP NO. 4								**1.51**		**169**	**0.05**	**15,900**	**13,100**	**40**																									
2017CPT.05.06.20391.1	Granville	5	SR 1121 - RANGE RD	SR 1004 - OLD NC 75 TO DURHAM CL	1	2	2WU	2.37	20	266	0.07	24,875	11,140	28																									
TOTAL FOR MAP NO. 5								**2.37**		**266**	**0.07**	**24,875**	**11,140**	**28**																									
2017CPT.05.06.20391.1	Granville	6	SR 1126 - RANGE RD	PERSON CL TO SR 1141 - MORIAH RD	1	2	2WU	2.22	20	235	0.07	23,570	18,905	36																									
TOTAL FOR MAP NO. 6								**2.22**		**235**	**0.07**	**23,570**	**18,905**	**36**																									
2017CPT.05.06.20391.1	Granville	7	SR 1126 - RANGE RD	SR 1139 - ENON RD TO SR 1004 - OLD NC 75	1	2	2WU	5.03	20	564	0.15	52,260	33,650	72																									
TOTAL FOR MAP NO. 7								**5.03**		**564**	**0.15**	**52,260**	**33,650**	**72**																									
2017CPT.05.06.20391.1	Granville	8	SR 1410 - OAK HILL RD	NC 96 TO SR 1300 - CORNWALL RD	1	2	2WU	4.88	20	547	0.13	51,100	48,882	140			40																						
TOTAL FOR MAP NO. 8								**4.88**		**547**	**0.13**	**51,100**	**48,882**	**140**			**40**																						
2017CPT.05.06.20391.1	Granville	9	SR 1413 - JOHN WATKINS RD	SR 1410 - OAK HILL RD TO SR 1300 - CORNWALL RD	1	2	2WU	0.67	20	75	0.02	7,200	7,000																										
TOTAL FOR MAP NO. 9								**0.67**		**75**	**0.02**	**7,200**	**7,000**																										
2017CPT.05.06.20391.1	Granville	10	SR 1600 - ANTIOCH RD	US 158 TO SR 1606 - W ANTIOCH DR	1	2	2WU	1.98	22	222	0.07	20,950	18,610	200																									
TOTAL FOR MAP NO. 10								**1.98**		**222**	**0.07**	**20,950**	**18,610**	**200**																									
2017CPT.05.06.20391.1	Granville	11	SR 1334 - 5TH ST	NC 96 TO SR 1335	1	2	2WU	0.09	18	9	0.01																												
TOTAL FOR MAP NO. 11								**0.09**		**9**	**0.01**																												
2017CPT.05.06.20391.1	Granville	12	SR 1335- CAROLINA AVE.	SR 1334 - 5TH ST TO STATE LINE	1	2	2WU	0.07	18	8	0.01																												
TOTAL FOR MAP NO. 12								**0.07**		**8**	**0.01**																												
2017CPT.05.06.20391.1	Granville	13	SR 1103- GATE 2 RD	US 15 TO PVTJT 570' NORTH OF SR 1201	1,2	2	2WU	2.613	26	288	0.07	26,000	30,400	1,575	780	240		635	100	250	12	4	11	3	1	2	550	550	4,230	3,590	780	40	48	3	1	2	1,100	75	300	
TOTAL FOR MAP NO. 13								**2.613**		**288**	**0.07**	**26,000**	**30,400**	**1,575**	**780**	**240**		**635**	**100**	**250**	**12**	**4**	**11**	**3**	**1**	**2**	**550**	**550**	**4,230**	**3,590**	**780**	**40**	**48**	**3**	**1**	**2**	**1,100**	**75**	**300**	
2017CPT.05.06.20391.1	Granville	14	SR 1402- SMART RD	NC 96 TO SR 1400 - GRASSY CREEK VIRGILINA RD	1	2	2WU	2.32	20	260	0.07	24,395	22,410																										
TOTAL FOR MAP NO. 14								**2.32**		**260**	**0.07**	**24,395**	**22,410**																										
TOTAL FOR PROJ NO. 2017CPT.05.06.20391.1								**26.973**		**3,003**	**0.84**	**279,515**	**235,787**	**2,275**	**780**	**240**	**40**	**635**	**100**	**298**	**12**	**4**	**19**	**3**	**1**	**2**	**550**	**550**	**10,166**	**9,725**	**780**	**40**	**96**	**11**	**1**	**2**	**1,100**	**75**	**300**	
													238,062		**1,020**						**16**			**25**			**1,100**		**19,891**					**14**				**375**		
5C.039060	Granville	15	SR 1407 - RUEBEN HART	SR 1410 TO SR 1408		2		2.01	20	225	0.10	21,210	21,210																										
TOTAL FOR MAP NO. 15								**2.01**		**225**	**0**	**21,210**	**21,210**																										
TOTAL FOR PROJ NO. 5C.039060								**2.01**		**225**	**0**	**21,210**	**21,210**																										
													21,210																										
GRAND TOTAL								**30.913**		**3,444**	**1**	**321,225**	**276,887**	**2,351**	**780**	**240**	**40**	**635**	**100**	**298**	**12**	**4**	**19**	**3**	**1**	**2**	**550**	**550**	**10,166**	**9,725**	**780**	**40**	**96**	**11**	**1**	**2**	**1,100**	**75**	**300**	**128**
													279,238		**1,020**						**16**			**25**			**1,100**		**19,891**					**14**				**375**		