PROJECT REFERENCE NO.	SHEET NO.
2017CPT.05.07.10731.1, etc.	6

PAVEMENT SCHEDULE

C1	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
C2	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
E	8" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, TO BE PLACED IN TWO LIFTS AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
S	SHOULDER GRADING ASB REQUIRED (EXCEPT RESIDENTIAL AREAS)
U	EXISTING PAVEMENT
V1	0" - 1½" MILLING
V2	1½" MILLING

INCIDENTAL MILLING

PATCHING EXISTING PAVEMENT

MILLING (IF REQUIRED BY TYPICAL) TO BE PERFORMED PRIOR TO PATCHING

TYPICAL SECTION NO. 4

TYPICAL TO BE USED ON MAP 1 (NC 157 - HURDLE MILLS ROAD)
FROM END OF C&G TO GUESS RD

TYPICAL SECTION NO. 5

TYPICAL TO BE USED ON MAP 1 (NC 157 - HURDLE MILLS ROAD)
FROM US 501 TO END OF C&G