PROJECT REFERENCE NO.	SHEET NO.
2017CPT.05.07.10731.1, etc.	4

PAVEMENT SCHEDULE

C1	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
C2	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
E	8" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, TO BE PLACED IN TWO LIFTS AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
S	SHOULDER GRADING ASB REQUIRED (EXCEPT RESIDENTIAL AREAS)
U	EXISTING PAVEMENT
V1	0" - 1½" MILLING
V2	1½" MILLING

TYPICAL SECTION NO. 3