PROJECT REFERENCE NO.	SHEET NO.
2017CPT.05.07.10731.1, etc.	3

PAVEMENT SCHEDULE

C1	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
C2	1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
E	8" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, TO BE PLACED IN TWO LIFTS AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
S	SHOULDER GRADING ASB REQUIRED (EXCEPT RESIDENTIAL AREAS)
U	EXISTING PAVEMENT
V1	0" - 1½" MILLING
V2	1½" MILLING

DETAIL OF PROJECT LIMITS AT SIGNALIZED Y LINES

DETAIL OF PROJECT LIMITS AT UNSIGNALIZED Y LINES

NOTES

ALL UNPAVED S.R. ROADS TO BE RESURFACED 50' FROM EDGE OF PAVEMENT OF MAIN PROJECT
ALL PAVED S.R. ROADS TO BE RESURFACED TO THE ENDS OF THE RADII, OR AS DIRECTED BY THE ENGINEER.
EDGES, PAVEMENT WIDENING, INTERSECTIONS AND BRIDGE FLARES ARE INCLUDED IN THE TABLE OF QUANTITIES.
BRIDGES TO BE RESURFACED AT LOCATIONS AND TO DEPTH AS DIRECTED BY THE ENGINEER.

TYPICAL SECTION NO. 1

TYPICAL SECTION NO. 2