PROJECT NO.	SHEET NO.	TOTAL NO.
2017CPT.05.07.10731.1, etc.	7	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	BORROW CY	REMOVAL OF EXISTING CONCRETE PAVEMENT SLABS SY	GEOTEXTILE FOR SOIL STABILIZATION SY	ASB TONS	SHOULDER GRADING SMI	SHALLOW UNDERCUT CY	CLASS IV SUBGRADE STABILIZATION TON	INCIDENTAL STONE BASE TONS	1½" MILLING SY	0" TO 1.5" MILLING SY	INCIDENTAL MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	ASPHALT BINDER FOR PLANT MIX TON	PATCHING EXISTING PAVEMENT TONS	ADJUST MANHOLES EA	ADJUST METER OR VALVE BOX EA	TEMPORARY SILT FENCE LF	WATTLE LF	SEED & MULCHING AC	INDUCTIVE LOOP LF
2017CPT.05.07.10731.1	Person	1	NC 157 HURDLE MILLS RD	GUESS RD TO US 501	4&5	2	2WU	NO	NO	9.6	24-44	948			911	18.96			237	2,581		4,376		12,474		748	850	1	1	698	1,730	6.98	1,050
TOTAL FOR MAP NO. 1										**9.6**		**948**			**911**	**18.96**			**237**	**2,581**		**4,376**		**12,474**		**748**	**850**	**1**	**1**	**698**	**1,730**	**6.98**	**1,050**
2017CPT.05.07.10731.1	Person	2	US 158 OLD DURHAM RD.	PVT JT AT US 501 TO OXFORD RD PVT JT (SKIP NEW 540' SECTION BETWEEN SR 1542 AND GREGORY ST)	3	2	2WU	NO	NO	0.55	20-40	32	450	450.00		0.32	300	580	8		808	445	205	696		51	100	2	4	24	60	0.24	
TOTAL FOR MAP NO. 2										**0.55**		**32**	**450**	**450.00**		**0.32**	**300**	**580**	**8**		**808**	**445**	**205**	**696**		**51**	**100**	**2**	**4**	**24**	**60**	**0.24**	
TOTAL FOR PROJ NO. 2017CPT.05.07.10731.1										**10.15**		**980**	**450**	**450.00**	**911**	**19.28**	**300**	**580**	**245**	**2,581**	**808**	**4,821**	**205**	**13,170**		**799**	**950**	**3**	**5**	**722**	**1,790**	**7.22**	**1,050**
2017CPT.05.07.20731.1	Person	3	SR 1102 RALPH WINSTEAD RD.	US 158 TO SR 1343 CONCORD CHURCH RD	2	2	2WU	NO	NO	4.1	20	410			394	8.20			103	30,507		1,359			5,185	347	100			298	750	2.98	
TOTAL FOR MAP NO. 3										**4.1**		**410**			**394**	**8.20**			**103**	**30,507**		**1,359**			**5,185**	**347**	**100**			**298**	**750**	**2.98**	
2017CPT.05.07.20731.1	Person	4	SR 1110 BRIGGS RD	SR 1109 TO SR 1111	1	2	2WU	NO	NO	0.9	20	45			130	0.18			11			165			920	62	250			33	90	0.33	
TOTAL FOR MAP NO. 4										**0.9**		**45**			**130**	**0.18**			**11**			**165**			**920**	**62**	**250**			**33**	**90**	**0.33**	
2017CPT.05.07.20731.1	Person	5	SR 1137 POINDEXTER RD/WHITFIELD ROGERS RD	NC 157 TO NC 49	1	2	2WU	NO	NO	2.9	20	290			279	5.80			73			303			2,994	201	500			211	530	2.11	
TOTAL FOR MAP NO. 5										**2.9**		**290**			**279**	**5.80**			**73**			**303**			**2,994**	**201**	**500**			**211**	**530**	**2.11**	
2017CPT.05.07.20731.1	Person	6	SR 1139 POINDEXTER RD.	SR 1137 TO SR 1142	1	2	2WU	NO	NO	0.7	20	70			67	1.40			18			85			716	48	100			51	130	0.51	
TOTAL FOR MAP NO. 6										**0.7**		**70**			**67**	**1.40**			**18**			**85**			**716**	**48**	**100**			**51**	**130**	**0.51**	
2017CPT.05.07.20731.1	Person	7	SR 1138 HASSEL HORTON RD	NC 49 TO SR 1137	1	2	2WU	NO	NO	1.5	20	150			144	3.00			38			85			1,534	103	200			109	280	1.09	
TOTAL FOR MAP NO. 7										**1.5**		**150**			**144**	**3.00**			**38**			**85**			**1,534**	**103**	**200**			**109**	**280**	**1.09**	
2017CPT.05.07.20731.1	Person	8	SR 1536 MOUNTAIN RD.	SR 1537 TO SR 1520	2	2	2WU	NO	NO	4.3	20	430			413	8.60			108	50,453		2,546			4,599	308	250			313	790	3.13	
TOTAL FOR MAP NO. 8										**4.3**		**430**			**413**	**8.60**			**108**	**50,453**		**2,546**			**4,599**	**308**	**250**			**313**	**790**	**3.13**	
2017CPT.05.07.20731.1	Person	9	SR 1520 MILL CREEK RD/SR 1520 GENTRY RIDGE RD	FROM SR 1519 TO SR 1536	2	2	2WU	NO	NO	4.1	20	410			394	8.20			103	48,107		741			4,258	285	350			298	750	2.98	
TOTAL FOR MAP NO. 9										**4.1**		**410**			**394**	**8.20**			**103**	**48,107**		**741**			**4,258**	**285**	**350**			**298**	**750**	**2.98**	
2017CPT.05.07.20731.1	Person	10	SR 1519 MILL CREEK RD	SR 1520 TO US 501	2	2	2WU	NO	NO	1	20	100			96	2.00			25	11,733					1,023	69	100			73	190	0.73	
TOTAL FOR MAP NO. 10										**1**		**100**			**96**	**2.00**			**25**	**11,733**					**1,023**	**69**	**100**			**73**	**190**	**0.73**	
2017CPT.05.07.20731.1	Person	11	SR 1705 HOUSTON BLALOCK RD	US 158 TO SR 1708	1	2	2WU	NO	NO	2.3	20	230			221	4.60			58			418			2,370	159	250			167	420	1.67	
TOTAL FOR MAP NO. 11										**2.3**		**230**			**221**	**4.60**			**58**			**418**			**2,370**	**159**	**250**			**167**	**420**	**1.67**	
2017CPT.05.07.20731.1	Person	12	SR 1706 OUTLAW RD	SR 1705 TO CUL-DE-SAC	1	2	2WU	NO	NO	0.55	20	55			53	1.10			14						563	38	100			40	100	0.40	
TOTAL FOR MAP NO. 12										**0.55**		**55**			**53**	**1.10**			**14**						**563**	**38**	**100**			**40**	**100**	**0.40**	
2017CPT.05.07.20731.1	Person	13	SR 1194 LAKE SHORE DR	NC 49 TO SR 1154	1	2	2WU	NO	NO	0.25	20	50				0.50			13			85			256	17	40			36	100	0.36	
TOTAL FOR MAP NO. 13										**0.25**		**50**				**0.50**			**13**			**85**			**256**	**17**	**40**			**36**	**100**	**0.36**	
2017CPT.05.07.20731.1	Person	14	SR 1154 ROSEWOOD DR	NC 49 TO SR 1154	1	2	2WU	NO	NO	0.45	20	90				0.90			23			85			460	31	50			65	170	0.66	
TOTAL FOR MAP NO. 14										**0.45**		**90**				**0.90**			**23**			**85**			**460**	**31**	**50**			**65**	**170**	**0.66**	
2017CPT.05.07.20731.1	Person	15	SR 1200 PARKVIEW	SR 1194 TO DEAD END	1	2	2WU	NO	NO	0.1	20	20				0.20			5						102	7	20			15	40	0.15	
TOTAL FOR MAP NO. 15										**0.1**		**20**				**0.20**			**5**						**102**	**7**	**20**			**15**	**40**	**0.15**	
2017CPT.05.07.20731.1	Person	16	SR 1201 WESTWOOD LN	SR 1200 TO DEAD END	1	2	2WU	NO	NO	0.05	20	10				0.10			3						51	3	10			7	20	0.07	
TOTAL FOR MAP NO. 16										**0.05**		**10**				**0.10**			**3**						**51**	**3**	**10**			**7**	**20**	**0.07**	
TOTAL FOR PROJ NO. 2017CPT.05.07.20731.1										**23.2**		**2,360**			**2,191**	**44.78**			**595**	**140,800**		**5,872**			**25,031**	**1,678**	**2,320**			**1,716**	**4,360**	**17.16**	
GRAND TOTAL										**33.35**		**3,340**	**450**	**450.00**	**3,102**	**64.06**	**300**	**580**	**840**	**143,381**	**808**	**10,693**	**205**	**13,170**	**25,031**	**2,477**	**3,270**	**3**	**5**	**2,438**	**6,150**	**24.38**	**1,050**