



PAVEMENT SCHEDULE								
С	PROP. LATEX MODIFIED MICRO-SURFACING, TYPE III AT AN AVERAGE RATE OF 22 TO 26 LBS. PER SQ. YD.							
U	EXISTING PAVEMENT							

Project Reference No	Sheet No
2022CPT.05.18.20392.1	2



TYPICAL SECTION 1



PATCHING EXISTING PAVEMENT MILLING (IF REQUIRED BY TYPICAL) TO BE PERFORMED PRIOR TO PATCHING

* MICROSURFACE OVER BRIDGE #0136 ON MAP 1

PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.18.20392.1	3	

SUMMARY OF QUANTITIES

											1704000000-E	189100000-E
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL	WARM MIX	LENGTH	WIDTH	PATCHING	LATEX
							SURFACE	ASPHALT			EXISTING	MODIFIED
							TESTING	REQUIRED			PAVEMENT	MICROSURFACI
							REQUIRED					NG, TYPE III
									MI	FT	TONS	SY
2022CPT.05.18.20392.1	Granville	1	SR 1300 - CORNWALL RD	US 158 TO VIRGINIA STATE LINE	1	2	NO	NO	15.919	21	100	196,122
TOTAL FOR PROJ NO. 2022CPT.05.18.20392.1								15.919		100	196,122	
GRAND TOTAL								15.919		100	196,122	


PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.18.20392.1	4	

THERMOPLASTIC AND PAINT QUANTITIES


						4413000000-E	4457000000-N	4685000000-E		4810000000-E		4850000000-E			
PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	WORK ZONE	TEMPORARY	4" X 90 M	4" X 90 M	4" WHITE	4" YELLOW	4" LINE
									ADVANCE/GE	TRAFFIC	WHITE	YELLOW	PAINT	PAINT	REMOVAL
									NERAL	CONTROL	THERMO	THERMO			
									WARNING						
									SIGNING						
							MI	FT	SF	LS	LF	LF	LF	LF	LF
2022CPT.05.18.20392.1	Granville	1	SR 1300 - CORNWALL RD	US 158 TO VIRGINIA STATE LINE	1	2	15.919	21	1,783	1.00	171,288	168,104	171,288	168,104	339,392
TOTAL FOR PROJ NO. 2022CPT.05.18.20392.1						15.919		1,783	1.00	171,288	168,104	171,288	168,104	339,392	
101AL FOR PROJ NO. 2022CF1.05.18.20592.1											339,392 339,392				
GRAND TOTAL						15.919		1,783	1.00	171,288	168,104	171,288	168,104	339,392	
GRAND TOTAL											339,392 339,392				

TEE INTERSECTION





MAINLINE (-L-) SIGNING



MAPS LESS THAN 2 MILES START OF CONTRACT WORK.

FOR RESURFACING MAPS WITH CONSTRUCTION LIMITS LESS THAN 2 MILES IN LENGTH, NO STATIONARY SIGNS ARE REQUIRED. USE PORTABLE "ROAD UNDER CONSTRUCTION" OR "ROAD WORK AHEAD" SIGNS IN LIEU OF STATIONARY ADVANCE WARNINGS SIGNS.

ADDITIONAL SIGNS REQUESTED BY NCDOT DIVISIONS SHALL BE INSTALLED WITHIN 7 BUSINESS DAYS OF THE



ADVANCE WARNING SIGNS FOR RURAL AND SUBURBAN 2-LANE ROADWAY RESURFACING