

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0003	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0004	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0005	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0006	0043000000-N	226	GRADING	Lump Sum	L.S.	
0007	0043000000-N	226	GRADING	Lump Sum	L.S.	
0008	0043000000-N	226	GRADING	Lump Sum	L.S.	
0009	0043000000-N	226	GRADING	Lump Sum	L.S.	
0010	0134000000-E	240	DRAINAGE DITCH EXCAVATION	3 CY		
0011	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	110 SY		
0012	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	840 SY		
0013	0255000000-E	SP	GENERIC GRADING ITEM HAULING & DISPOSAL OF PETROLEUM CONTAMINATED SOILS	50 TON		
0014	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	40 TON		
0015	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	80 SY		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	32 LF		
0017	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	128 LF		
0018	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	12 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0995000000-E	340	PIPE REMOVAL	80 LF		
0020	0996000000-N	350	PIPE CLEAN OUT	2 EA		
0021	1099500000-E	505	SHALLOW UNDERCUT	280 CY		
0022	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	560 TON		
0023	1121000000-E	520	AGGREGATE BASE COURSE	180 TON		
0024	1220000000-E	545	INCIDENTAL STONE BASE	170 TON		
0025	1275000000-E	600	PRIME COAT	150 GAL		
0026	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5")	3,100 SY		
0027	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	450 TON		
0028	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	380 TON		
0029	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	610 TON		
0030	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	85 TON		
0031	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0032	1704000000-E	SP	PATCHING EXISTING PAVEMENT	227 TON		
0033	2000000000-N	806	RIGHT-OF-WAY MARKERS	20 EA		
0034	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0035	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100 SY		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	17 CY		
0037	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0038	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0039	2077000000-E	815	6" OUTLET PIPE	6 LF		
0040	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	10 EA		
0041	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0042	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
0043	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0044	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0045	2535000000-E	846	*** X *** CONCRETE CURB (8"X12")	20 LF		
0046	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	930 LF		
0047	2591000000-E	848	4" CONCRETE SIDEWALK	430 SY		
0048	2605000000-N	848	CONCRETE CURB RAMPS	15 EA		
0049	2612000000-E	848	6" CONCRETE DRIVEWAY	123 SY		
0050	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	75 SY		
0051	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	255 SY		
0052	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	1 EA		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	1 EA		
0054	3649000000-E	876	RIP RAP, CLASS B	8 TON		
0055	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	19 SY		
0056	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	37.5 SF		
0057	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (F)	87 SF		
0058	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	418 LF		
0059	4102000000-N	904	SIGN ERECTION, TYPE E	9 EA		
0060	4108000000-N	904	SIGN ERECTION, TYPE F	5 EA		
0061	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (D)	3 EA		
0062	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10 EA		
0063	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	3 EA		
0064	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	10 EA		
0065	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	436 SF		
0066	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	736 SF		
0067	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	14 SF		
0068	4415000000-N	1115	FLASHING ARROW BOARD	6 EA		
0069	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	5 EA		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	4430000000-N	1130	DRUMS	99 EA		
0071	4435000000-N	1135	CONES	275 EA		
0072	4445000000-E	1145	BARRICADES (TYPE III)	40 LF		
0073	4455000000-N	1150	FLAGGER	90 DAY		
0074	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0075	4510000000-N	1190	LAW ENFORCEMENT	215 HR		
0076	4516000000-N	1180	SKINNY DRUM	47 EA		
0077	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,903 LF		
0078	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	589 LF		
0079	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	1,829 LF		
0080	4720000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MILS)	4 EA		
0081	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	35 EA		
0082	4726110000-E	1205	HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2 EA		
0083	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	700 LF		
0084	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,239 LF		
0085	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	976 LF		
0086	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	280 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	4 EA		
0088	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM 10 FT. WIDTH	300 LF		
0089	4898000000-N	1251	GENERIC PAVEMENT MARKING ITEM HEATED-IN-PLACE THERMOPLASTIC PAVEMENT MARKING CHARACTER (90 MIL)	4 EA		
0090	4915000000-E	1264	7' U-CHANNEL POSTS	3 EA		
0091	4957000000-N	1264	OBJECT MARKERS (TYPE **) (END OF ROAD, TYPE 4)	3 EA		
0092	6000000000-E	1605	TEMPORARY SILT FENCE	1,455 LF		
0093	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	235 TON		
0094	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	45 TON		
0095	6012000000-E	1610	SEDIMENT CONTROL STONE	35 TON		
0096	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0097	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	400 LB		
0098	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2 TON		
0099	6024000000-E	1622	TEMPORARY SLOPE DRAINS	600 LF		
0100	6029000000-E	SP	SAFETY FENCE	200 LF		
0101	6030000000-E	1630	SILT EXCAVATION	60 CY		
0102	6036000000-E	1631	MATTING FOR EROSION CONTROL	11,975 SY		
0103	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0104	6071010000-E	SP	WATTLE	130 LF		
0105	6084000000-E	1660	SEEDING & MULCHING	2 ACR		
0106	6087000000-E	1660	MOWING	2 ACR		
0107	6090000000-E	1661	SEED FOR REPAIR SEEDING	200 LB		
0108	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0109	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0110	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0111	6114500000-N	1667	SPECIALIZED HAND MOWING	40 MHR		
0112	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	21 EA		
0113	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	3 EA		
0114	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INLET PROTECTION DEVICE	6 EA		
0115	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INLET PROTECTION DEVICE CLEANOUT	12 EA		
0116	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION	6 EA		
0117	7048500000-E	1705	PEDESTRIAN SIGNAL HEAD (16", 1 SECTION W/COUNTDOWN)	15 EA		
0118	7060000000-E	1705	SIGNAL CABLE	6,720 LF		
0119	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	12 EA		
0120	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	9 EA		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	4 EA		
0122	7264000000-E	1710	MESSENGER CABLE (3/8")	500 LF		
0123	7288000000-E	1715	PAVED TRENCHING (*****) (1 CONDUIT, 2 INCH)	220 LF		
0124	7288000000-E	1715	PAVED TRENCHING (*****) (2 CONDUIT, 2 INCH)	150 LF		
0125	7300000000-E	1715	UNPAVED TRENCHING (*****) (1 CONDUIT, 2 INCH)	1,325 LF		
0126	7300000000-E	1715	UNPAVED TRENCHING (*****) (2 CONDUIT, 2 INCH)	25 LF		
0127	7300100000-E	1715	UNPAVED TRENCHING FOR TEMPORARY LEAD-IN	225 LF		
0128	7301000000-E	1715	DIRECTIONAL DRILL (*****) (1 CONDUIT, 2 INCH)	60 LF		
0129	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	11 EA		
0130	7360000000-N	1720	WOOD POLE	2 EA		
0131	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0132	7396000000-E	1722	1/2" RISER WITH WEATHERHEAD	8 EA		
0133	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0134	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2 EA		
0135	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,675 LF		
0136	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	7,650 LF		
0137	7481000000-N	SP	SITE SURVEY	1 EA		

County: WAKE, FRANKLIN

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0138	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	1 EA		
0139	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	1 EA		
0140	7541000000-N	1731	MODIFY SPLICE ENCLOSURE	1 EA		
0141	7636000000-N	1745	SIGN FOR SIGNALS	4 EA		
0142	7642100000-N	1743	TYPE I POST WITH FOUNDATION	1 EA		
0143	7642200000-N	1743	TYPE II PEDESTAL WITH FOUNDATION	15 EA		
0144	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0145	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (TYPE 2070 LX, BASE MOUNTED)	1 EA		
0146	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (TYPE 2070E, BASE MOUNTED)	1 EA		
0147	7744000000-N	1751	DETECTOR CARD (TYPE 170)	23 EA		
0148	7901000000-N	1753	CABINET BASE EXTENDER	2 EA		
0149	7980000000-N	SP	GENERIC SIGNAL ITEM 2070LX CONTROLLER	1 EA		

1319/Feb21/Q60663.5/D638246020000/E149

Total Amount Of Bid For Entire Project :