PROJ. REFERENCE NO.	SHEET NO.
SS-4905BI	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT.

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
13+50.00	16	1
14+00.00	35	2
14+50.00	37	2
15+22.00	57	5
15+50.00	26	5
16+00.00	43	7
16+50.00	27	9
17+00.00	15	7
17+50.00	15	0
18+00.00	17	6
18+50.00	18	6
19+00.00	29	0
19+50.00	32	0
20+00.00	19	0
20+50.00	10	0
SUBTOTAL=	396	50
CONTAMINATED SOIL DISPOSAL	-150	
TOTAL	**246**	**50**