PROJECT REFERENCE NO.	SHEET NO.
W-5601FB	PMP / SGN

NORTH CAROLINA PROFESSIONAL SEAL 039266 ENGINEER JOHN SAUNDERS

Docusigned by:
A8A3F36AF75A4F7...

Project Notes

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
2. Remove all markings noted with an "x", including lines that encroach the stopbars.
3. Install W3–3 "Signal Ahead" signs on all approaches. When existing terrain permits, locate these signs at least 250' in advance of the stop bar. Otherwise choose the best location available in the field. The supplemental "Street Name" plaques will be furnished by the City of Raleigh.



PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY
T2	WHITE STOPBAR	THERMOPLASTIC (24", 120 MIL)	125 LF
T3	WHITE CROSSWALK LINE	THERMOPLASTIC (24", 120 MIL)	170 LF
UA	LEFT TURN ARROW	THERMOPLASTIC (90 MIL)	1 EA
UB	RIGHT TURN ARROW	THERMOPLASTIC (90 MIL)	1 EA

TRYON RD (SR 1009)
AND LAKE DAM (SR 1427)
RALEIGH, WAKE COUNTY, NC
PAVEMENT MARKING /
SIGN PLACEMENT PLAN

DIVISION 05 WAKE COUNTY

REVISIONS	INIT.	DATE

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
DIVISION FIVE TRAFFIC ENGINEERING

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION TRAFFIC ENGINEERING

SCALE: 60' = 1" DATE: 12 OCT 2016
PREPARED BY: SJL
REVIEWED BY:
REVIEWED BY: