PROJECT NO.	SHEET NO.	TOTAL NO.
2022CPT.05.07.10351.1, etc.	8	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH	WIDTH	0106000000-E BORROW	0264000000-E SHOULDER GRADING	1220000000-E INCIDENTAL STONE BASE	1260000000-E AGGREGATE SHOULDER BORROW	1330000000-E INCIDENTAL MILLING	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2613000000-N REMOVE AND REPLACE CURB RAMPS	2830000000-N ADJUST MANHOLES	2845000000-N ADJUST METER OR VALVE BOX	4600000000-N GENERIC TRAFFIC CONTROL ITEM, PEDESTRIAN TRANSPORT SERVICE	4600000000-N GENERIC TRAFFIC CONTROL ITEM, AUDIBLE WARNING DEVICE	6000000000-E TEMPORARY SILT FENCE	6071010000-E WATTLE	6084000000-E SEED & MULCHING	6117000000-N RESPONSE FOR EROSION CONTROL	7444000000-E INDUCTIVE LOOP SAWCUT
									MI	FT	CY	SMI	TONS	TON	SY	TONS	TON	TONS	EA	EA	EA	EA	EA	LF	LF	AC	EA	LF
2022CPT.05.07.10351.1	Franklin	1	NC 96	WAKE CO. TO SR 1100 - EAST MAIN ST	1	2	NO	NO	3.35	26	201	6.70	168	247	1,218	4,974	298	127	1	2	1	2	2	292	740	3.00	1	208
TOTAL FOR PROJ NO. 2022CPT.05.07.10351.1									**3.35**		**201**	**6.70**	**168**	**247**	**1,218**	**4,974**	**298**	**127**	**1**	**2**	**1**	**2**	**2**	**292**	**740**	**3.00**	**1**	**208**
																						4						
2022CPT.05.07.10921.1	Wake	2	NC 96	NC 98 - WAIT AVE TO FRANKLIN CO.	1	2	NO	NO	1.62	26	81	3.00	81	149	1,225	2,283	137	59						117	300	1.00	1	
TOTAL FOR PROJ NO. 2022CPT.05.07.10921.1									**1.62**		**81**	**3.00**	**81**	**149**	**1,225**	**2,283**	**137**	**59**						**117**	**300**	**1.00**	**1**	
GRAND TOTAL									**4.97**		**282**	**9.70**	**249**	**396**	**2,443**	**7,257**	**435**	**186**	**1**	**2**	**1**	**2**	**2**	**409**	**1,040**	**4.00**	**2**	**208**
																						4						

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LENGTH	WIDTH	1300000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING	4700000000-E PEDESTRIAN CHANNELIZING DEVICES	4457000000-N TEMPORARY TRAFFIC CONTROL	4685000000-E 4" X 90 M WHITE THERMO	4685000000-E 4" X 90 M YELLOW THERMO	4700000000-E 12" X 90 M YELLOW THERMO	4725000000-E THERMO LT ARROW 90 M	4890000000-E GENERIC MARKING ITEM 24" X 90 M WHITE THERMO	4895000000-N GENERIC PAVEMENT MARKING ITEM NON-CAST IRON SNOW PLOWABLE MARKER
							MI	FT	SF	LF	LS	LF	LF	LF	EA	LF	EA
2022CPT.05.07.10351.1	Franklin	1	NC 96	WAKE CO. TO SR 1100 - EAST MAIN ST	1	2	3.35	26	126	20	0.20	36,046	36,556	190	5	26	250
TOTAL FOR PROJ NO. 2022CPT.05.07.10351.1							**3.35**		**126**	**20**	**0.20**	**36,046**	**36,556**	**190**	**5**	**26**	**250**
												72,602					
2022CPT.05.07.10921.1	Wake	2	NC 96	NC 98 - WAIT AVE TO FRANKLIN CO.	1	2	1.62	26	181		0.80	17,431	16,802				107
TOTAL FOR PROJ NO. 2022CPT.05.07.10921.1							**1.62**		**181**		**0.80**	**17,431**	**16,802**				**107**
												34,233					
GRAND TOTAL							**4.97**		**307**	**20**	**1.00**	**53,477**	**53,358**	**190**	**5**	**26**	**357**
												106,835					