PROJECT REFERENCE NO.	SHEET NO.
W-5705O	PMP / SGN

NORTH CAROLINA PROFESSIONAL SEAL 039266 ENGINEER JOHN E. SANDOR

Project Notes

1. Refer to "NCDOT January 2018 Roadway Standard Drawings " and "NCDOT Standard Specifications for Roads and Structures January 2018"

2. Remove all markings noted with an "x".

3. Install W3-3 "Signal Ahead" signs for both intersection approaches on US 401 (Fox Rd). When existing terrain permits, locate these signs at least 250' in advance of the stop bar. Otherwise choose the best location available in the field. The supplemental "Street Name" plaques will be furnished by the City of Raleigh.

4. Remove R1-1 "Stop" signs once signal is in operation.

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY
T2	WHITE STOPBAR	THERMOPLASTIC (24", 120 MIL)	110 LF
T3	WHITE CROSSWALK LINE	THERMOPLASTIC (8", 120 MIL)	620 LF
TD	3FT. - 9FT./SP WHITE MINISKIP	THERMOPLASTIC (4", 120 MIL)	15 LF
TE	WHITE LANE LINE	THERMOPLASTIC (4", 120 MIL)	60 LF
TI	YELLOW DOUBLE CENTER	THERMOPLASTIC (4", 120 MIL)	145 LF
UB	RIGHT TURN ARROW	THERMOPLASTIC (90 MIL)	1 EA
UD	COMBO LEFT/STRAIGHT ARROW	THERMOPLASTIC (90 MIL)	1 EA

US 401 (LOUISBURG RD) AND FOX RD
RALEIGH, WAKE COUNTY, NC

PAVEMENT MARKING /
SIGN PLACEMENT PLAN

DIVISION 05 WAKE COUNTY

REVISIONS	INIT.	DATE

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
DIVISION FIVE TRAFFIC ENGINEERING

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION TRAFFIC ENGINEERING

SCALE: 60' = 1" DATE: 18 MAR 2019
PREPARED BY: SJL
REVIEWED BY: JES
REVIEWED BY: