PROJECT REFERENCE NO.	SHEET NO.
W-5705R	PMP / SGN

NORTH CAROLINA PROFESSIONAL SEAL 039266 ENGINEER JOHN E. SANDOR

Project Notes

1. Refer to "NCDOT January 2018 Roadway Standard Drawings " and "NCDOT Standard Specifications for Roads and Structures January 2018"

2. Remove all markings noted with an "x".

3. Install W3-3 "Signal Ahead" signs for both intersection approaches on SR 2012 (Litchford Rd). When existing terrain permits, locate these signs at least 250' in advance of the stop bar. Otherwise choose the best location available in the field. The supplemental "Street Name" plaques will be furnished by the City of Raleigh.

4. Remove R1-1 "Stop" signs once signal is in operation.

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY
T2	WHITE STOPBAR	THERMOPLASTIC (24", 120 MIL)	110 LF
T3	WHITE CROSSWALK LINE	THERMOPLASTIC (8", 120 MIL)	150 LF
TE	WHITE LANE LINE	THERMOPLASTIC (4", 120 MIL)	15 LF

LITCHFORD RD (SR 2012)
AND HUNTING RIDGE RD / ROWLAND RD
RALEIGH, WAKE COUNTY, NC
PAVEMENT MARKING /
SIGN PLACEMENT PLAN

DIVISION 05 WAKE COUNTY

REVISIONS	INIT.	DATE

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION TRAFFIC ENGINEERING

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
DIVISION FIVE TRAFFIC ENGINEERING

SCALE: 60' = 1" DATE: 27 FEB 2019
PREPARED BY: SJL
REVIEWED BY: JES
REVIEWED BY: