PROJECT REFERENCE NO.	SHEET NO.
W-5601AX	SCP.3

NEW UNDERGROUND SPLICE ENCLOSURE
SR 3977 (CARY PARKWAY)
NEAR
WEST CHATHAM STREET

LEGEND
X = FUSION SPLICE

COLOR CODE
TIA/EIA 598-A

(1) BLUE
(2) ORANGE
(3) GREEN
(4) BROWN
(5) SLATE
(6) WHITE
(7) RED
(8) BLACK
(9) YELLOW
(10) VIOLET
(11) ROSE
(12) SLATE

NEW SPLICE TRAY
SR 3977 (CARY PARKWAY) AT
WEST CHATHAM STREET
SIG. INV. # 05-0711

Notes:
Unused fibers left coiled and stored in splice tray.
Unused Buffer Tubes left coiled and stored in splice tray.

LEGEND
X = FUSION SPLICE

COLOR CODE
TIA/EIA 598-A

(1) BLUE
(2) ORANGE
(3) GREEN
(4) BROWN
(5) SLATE
(6) WHITE
(7) RED
(8) BLACK
(9) YELLOW
(10) VIOLET
(11) ROSE
(12) SLATE

NOTES:

1) TRANSCEIVER TERMINATION CONFIGURATIONS ARE GENERIC. CONTRACTOR IS RESPONSIBLE FOR DETERMINING \ ENSURING PROPER TERMINATIONS.

2) NOTIFY THE TOWN OF CARY TRANSPORTATION ENGINEER, DAVID SPENCER, AT (919) 462-3833 5 DAYS PRIOR TO BEGINNING WORK ON SIGNAL SYSTEMS COMMUNICATION CABLE. NOTIFY THE TOWN TRANSPORTATION ENGINEER AFTER ALL WORK IS PERFORMED TO ENSURE THAT ALL FIBER CIRCUITS ARE FUNCTIONING PROPERLY.

3) INCLUDE ON THE COVER OF EACH SPLICE TRAY THE FOLLOWING:
REFERENCE SECTION 1731 "FIBER OPTIC SPLICE ENCLOSURE"

1) SPLICE LOCATION
2) DATE
3) COMPANY NAME
4) NAME OF INDIVIDUAL PERFORMING THE SPLICING

PRIOR TO INSTALLING THE COVER ON THE SPLICE TRAY TAKE A DIGITAL PHOTOGRAPH SHOWING THE SPLICE TRAY AND INFORMATION SHOWN ABOVE (1-4) AND SUBMIT PHOTOGRAPH ALONG WITH OTDR TEST RESULTS.

Prepared in the Offices of:
Transportation Mobility and Safety Division
750 N. Greenfield Pkwy., Garner, NC 27529

SPLICE DETAILS

DIVISION 05 WAKE COUNTY CARY

PLAN DATE: AUGUST 2015 REVIEWED BY: DocuSigned by: Neil Lowery
PREPARED BY: A. J. SKUCE REVIEWED BY: 09F3DB4CBED3443...

REVISIONS	INIT.	DATE

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 023919 ENGINEER GREGORY A. FULLER
DocuSigned by: Gregory A. Fuller 8/14/2015
7032CA0AEE874FF...
DATE

CADD Filename: