PROJECT REFERENCE NO.	SHEET NO.
W-5601AX	PMP / SGN

NORTH CAROLINA PROFESSIONAL SEAL 039266 ENGINEER JOHN E. SANDOR

DocuSigned by:
A8A3E36AE75A4E7...

Project Notes

1. Refer to "Roadway Standard Drawings NCDOT" dated January 2012 and "Standard Specifications for Roads and Structures" dated January 2012.
2. Remove all markings noted with an "x".
3. Remove R1-1 "Stop" signs once signal is in operation.
4. Stockpile R1-1 "Stop" sign, but retain all other existing signs on this system.
5. Replace W2-2 "Intersection Ahead" sign with W3-3 "Signal Ahead" sign where indicated, but retain the "W Chatham St" plaque below. Stockpile the removed W2-2 "Intersection Ahead" signs.

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY
T2	WHITE STOPBAR	THERMOPLASTIC(24", 120 MIL)	70 LF
T3	WHITE CROSSWALK LINE	THERMOPLASTIC(8", 120 MIL)	195 LF
UC	STRAIGHT ARROW	THERMOPLASTIC(90 MIL)	3 EA
T3	COMBINATION RIGHT/STRAIGHT ARROW	THERMOPLASTIC(90 MIL)	1 EA

SW CARY PARKWAY (SR 3977)
AND W CHATHAM STREET
CARY, WAKE COUNTY, NC
PAVEMENT MARKING /
SIGN PLACEMENT PLAN
DIVISION 05 WAKE COUNTY

REVISIONS	INIT.	DATE

N.C. DEPARTMENT of TRANSPORTATION
DIVISION of HIGHWAYS
DIVISION FIVE TRAFFIC ENGINEERING

DIVISION OF HIGHWAYS · STATE OF NORTH CAROLINA · DEPARTMENT OF TRANSPORTATION · TRAFFIC ENGINEERING

SCALE: 60' = 1" DATE: 11 MAR 2016
PREPARED BY: SJL
REVIEWED BY:
REVIEWED BY: