



PAT McCRORY
Governor

NICHOLAS J. TENNYSON
Secretary

April 12, 2016

SUBJECT: ADDENDUM 1 FOR DE00135, 17BP.5.R.52, Replacement of Bridge #93 on SR 1156 (Harper Renn Road) over Owen Creek in Granville County, WBS Element: 17BP.5.R.52

MEMORANDUM TO PROSPECTIVE BIDDERS

It has been brought to my attention that the bridge approach fill Line #0004 is incorrect on the bid sheet for the subject project. The pay item included was “*Bridge Approach Fill, Sub Regional Tier*” and should have been “*Reinforced Bridge Approach Fill*”. The plan sheet S-15 shows this correctly.

It has also been brought to my attention that 24” Thermoplastic was mistakenly included in the project and that 4”x90 mil Thermoplastic was omitted. The quantity for 24” has been removed and the quantity for 4”x90mil has been added to the project.

Since the bid opening was scheduled for Wednesday of this week, the bid opening will **DELAYED**. Bids for this project will now be opened on Wednesday, April 20th at 2:00pm. Please update the instructions to bidders with the following information:

11. The sealed bid must display the following statement on the front of the sealed envelope:

QUOTATION FOR DE00135– BRIDGE NO. 93 OVER OWEN CREEK, TO BE OPENED AT 2:00 PM ON, WEDNESDAY, APRIL 20, 2016.

If bids are being submitted on paper bids, a revised bid sheet has been attached for use.

If bids are being prepared electronically a **NEW** .EBS file for bid preparation has been provided.

This information will also be posted electronically on our website.

Please acknowledge receipt of this addendum in the proposal.



If you have any questions, feel free to call me at (919) 220-4600.

Sincerely,

DocuSigned by:



5CDD3BA8BDE94C1...
Michael J. Kneis, PE

Division Project Manager

cc: D. Jernigan
P. Townsend
L. Gilchrist
D. Pearson
C. Murray
Civil Rights Office

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (STATION 16+00.00 -L-)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA-TION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRUCTURES	7 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO-TEXTILE	20 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	28 LF		
0012	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	390 TON		
0015	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	330 TON		
0016	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	255 TON		
0017	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	49 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2		EA
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2		EA
0021	2556000000-E	846	SHOULDER BERM GUTTER	90		LF
0022	3030000000-E	862	STEEL BM GUARDRAIL	375		LF
0023	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0024	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0025	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
0026	3635000000-E	876	RIP RAP, CLASS II	100		TON
0027	3649000000-E	876	RIP RAP, CLASS B	2		TON
0028	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	302		SY
0029	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	526		SF
0030	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94		SF
0031	4445000000-E	1145	BARRICADES (TYPE III)	80		LF
0032	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,300		LF
0033	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,300		LF
0034	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	8		EA
0035	6000000000-E	1605	TEMPORARY SILT FENCE	1,615		LF
0036	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	609000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	40 TON		
0038	601200000-E	1610	SEDIMENT CONTROL STONE	60 TON		
0039	601500000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0040	601800000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0041	602100000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0042	602400000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0043	602900000-E	SP	SAFETY FENCE	400 LF		
0044	603000000-E	1630	SILT EXCAVATION	70 CY		
0045	603600000-E	1631	MATTING FOR EROSION CONTROL	6,295 SY		
0046	603700000-E	SP	COIR FIBER MAT	100 SY		
0047	604200000-E	1632	1/4" HARDWARE CLOTH	220 LF		
0048	607102000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0049	608400000-E	1660	SEEDING & MULCHING	3 ACR		
0050	608700000-E	1660	MOWING	0.5 ACR		
0051	609000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0052	609300000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0053	609600000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0054	610800000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0055	611450000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0056	611700000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6123000000-E	1670	REFORESTATION	0.1 ACR		
0058	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STATION 16+00.00 -L-)	Lump Sum	L.S.	
0059	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (STATION 16+00.00 -L-)	Lump Sum	L.S.	
0060	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	48.8 CY		
0061	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STATION 16+00.00 -L-)	Lump Sum	L.S.	
0062	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,860 LB		
0063	8364000000-E	450	HP12X53 STEEL PILES	175 LF		
0064	8391000000-N	450	STEEL PILE POINTS	10 EA		
0065	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	180 LF		
0066	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	230 TON		
0067	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	260 SY		
0068	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0069	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	900 LF		
0070	8860000000-N	SP	GENERIC STRUCTURE ITEM (ASBESTOS ASSESSMENT)	Lump Sum	L.S.	

1226/Apr12/Q23921.15/D318378520000/E70

Total Amount Of Bid For Entire Project :