



Transportation

PAT McCRORY
Governor

NICHOLAS J. TENNYSON
Secretary

April 11, 2016

SUBJECT: ADDENDUM 1 FOR DE00148, Replacement of Bridge #142 on SR 1547
(Parham Road) over Mayo Creek in Person County, WBS Element: 17BP.5.R.55

MEMORANDUM TO PROSPECTIVE BIDDERS

It has been brought to my attention that the supplemental description for Line #0068 is incorrect on the bid sheet for the subject project. The description is shown as “*Asbestos Abatement*” and should have been shown as “*Asbestos Assessment*”.

Since the bid opening was scheduled for Wednesday of this week, the bid opening will **DELAYED**. Bids for this project will now be opened on Wednesday, April 20th at 2:00pm. Please update the instructions to bidders with the following information:

11. The sealed bid must display the following statement on the front of the sealed envelope:

**QUOTATION FOR DE00148– BRIDGE NO. 148 OVER MAYO CREEK, TO BE
OPENED AT 2:00 PM ON, WEDNESDAY, APRIL 20, 2016.**

If bids are being submitted on paper bids, the bidder can strike through the description, make the change and initial or use the new revised bid sheet attached.

If bids are being prepared electronically an **NEW** .EBS file for bid preparation has been provided.

This information will also be posted electronically on our website.

Please acknowledge receipt of this addendum in the proposal.

If you have any questions, feel free to call me at (919) 220-4600.

Sincerely,

DocuSigned by:

5CDD3BA8BDE94C1...
Michael J. Kneis, PE
Division Project Manager

cc: D. Jernigan
A. Shapiro
L. Gilchrist
D. Pearson
C. Murray
Civil Rights Office



County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** STA. 15+64.00 -L-	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0194000000-E	SP	SELECT GRANULAR MATERIAL, CLASS III	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0010	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	20 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	36 LF		
0012	0335850000-E	305	*** DRAINAGE PIPE ELBOWS 15"	4 EA		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	260 TON		
0014	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	230 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	100 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	30 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	7 EA		
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2355000000-N	840	FRAME WITH GRATE, STD 840.29	2		EA
0020	2556000000-E	846	SHOULDER BERM GUTTER	25		LF
0021	3030000000-E	862	STEEL BM GUARDRAIL	50		LF
0022	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0023	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0024	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
0025	3635000000-E	876	RIP RAP, CLASS II	25		TON
0026	3649000000-E	876	RIP RAP, CLASS B	55		TON
0027	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	185		SY
0028	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	308		SF
0029	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	63		SF
0030	4445000000-E	1145	BARRICADES (TYPE III)	72		LF
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,500		LF
0032	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	5		EA
0033	6000000000-E	1605	TEMPORARY SILT FENCE	805		LF
0034	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON
0035	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	30		TON
0036	6012000000-E	1610	SEDIMENT CONTROL STONE	35		TON
0037	6015000000-E	1615	TEMPORARY MULCHING	0.5		ACR

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0039	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0040	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0041	6030000000-E	1630	SILT EXCAVATION	30 CY		
0042	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,625 SY		
0043	6042000000-E	1632	1/4" HARDWARE CLOTH	150 LF		
0044	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	145 SY		
0045	6071012000-E	SP	COIR FIBER WATTLE	60 LF		
0046	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0047	6087000000-E	1660	MOWING	0.5 ACR		
0048	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0049	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0050	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0051	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0052	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0053	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7 EA		
0054	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** STA. 15+64.00 -L-	Lump Sum	L.S.	
0055	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** STA. 15+64.00 -L-	Lump Sum	L.S.	
0056	8096000000-E	450	PILE EXCAVATION IN SOIL	97 LF		

County : Person

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	8097000000-E	450	PILE EXCAVATION NOT IN SOIL	43 LF		
0058	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** STA. 15+64.00 -L-	Lump Sum	L.S.	
0059	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	43.6 CY		
0060	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** STA. 15+64.00 -L-	Lump Sum	L.S.	
0061	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,272 LB		
0062	8364000000-E	450	HP12X53 STEEL PILES	140 LF		
0063	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140 LF		
0064	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	259 TON		
0065	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	325 SY		
0066	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0067	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	770 LF		
0068	8860000000-N	SP	GENERIC STRUCTURE ITEM ASBESTOS ASSESSMENT	Lump Sum	L.S.	

1129/Apr11/Q20077.1/D316166062000/E68

Total Amount Of Bid For Entire Project :