

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (14+66 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	980 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	700 SY		
0010	0223000000-E	275	ROCK PLATING	2,150 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0012	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	10 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0014	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0015	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0016	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	370 TON		
0017	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	425 TON		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	440 TON		
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	70 TON		
0020	2000000000-N	806	RIGHT-OF-WAY MARKERS	5 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	20 LF		
0024	3030000000-E	862	STEEL BEAM GUARDRAIL	550 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0028	3360000000-E	863	REMOVE EXISTING GUARDRAIL	540 LF		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	2,030 SY		
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	399 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0032	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0033	4430000000-N	1130	DRUMS	6 EA		
0034	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM WATERCRAFT SAFETY	Lump Sum	L.S.	
0036	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,800 LF		
0037	6000000000-E	1605	TEMPORARY SILT FENCE	1,415 LF		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	80 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	420 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6029000000-E	SP	SAFETY FENCE	200 LF		
0045	6030000000-E	1630	SILT EXCAVATION	120 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,030 SY		
0047	6037000000-E	SP	COIR FIBER MAT	100 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	300 LF		
0049	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	1,695 SY		
0050	6070000000-N	1639	SPECIAL STILLING BASINS	18 EA		
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0053	6087000000-E	1660	MOWING	0.5 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0058	6111000000-E	SP	IMPERVIOUS DIKE	50 LF		
0059	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
STRUCTURE ITEMS						
0061	0199000000-E	SP	TEMPORARY SHORING	8,000 SF		
0062	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+66.00 -L-)	Lump Sum	L.S.	
0063	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0064	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	153 LF		
0065	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	105 LF		
0066	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	216 LF		
0067	8113000000-N	411	SID INSPECTIONS	3 EA		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	8115000000-N	411	CSL TESTING	3 EA		
0069	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+66.00 -L-)	Lump Sum	L.S.	
0070	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	98.4 CY		
0071	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+66.00 -L-)	Lump Sum	L.S.	
0072	8217000000-E	425	REINFORCING STEEL (BRIDGE)	33,216 LB		
0073	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	4,782 LB		
0074	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12X53 PILES)	14 EA		
0075	8364000000-E	450	HP 12 X 53 STEEL PILES	350 LF		
0076	8475000000-E	460	TWO BAR METAL RAIL	385.75 LF		
0077	8517000000-E	460	1'***" X *****" CONCRETE PARAPET (1'-2" X 2'-9 1/2")	400.75 LF		
0078	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	840 TON		
0079	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	925 SY		
0080	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0081	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,400 LF		
0082	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** 10+50.00 -L-	Lump Sum	L.S.	