DocuSign Envelope ID: F371C4BD-3AA1-41FD-A4BE-7970851696EA

PROJECT REFERENCE NO.	SHEET NO.
W-5601EJ	2A-1

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 035663 MICHAEL B. LITTLEFIELD 3/28/2017

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Stantec

Stantec Consulting Services Inc.
801 Jones Franklin Road
Suite 300
Raleigh, NC 27606
Tel. (919) 851-6866
Fax. (919) 851-7024
www.stantec.com
License No. F-0672

PAVEMENT SCHEDULE

C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT TO EXCEED 2" IN DEPTH.
E1	PROP. APPROX. 8" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
R1	5" MONOLITHIC CONCRETE ISLAND (SURFACE MOUNTED)
R2	2'-6" CURB AND GUTTER
S	4" CONCRETE SIDEWALK
T	EARTH MATERIAL
U	EXISTING PAVEMENT
V	1.5" MILLING

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

TYPICAL SECTION 1

–L– STA. 12+90 TO 13+90
–L– STA. 15+53 TO 18+89 (SEE PLAN VIEW FOR LANE CONFIGURATION)
–L– STA. 20+31 TO 23+15

INSET A

–L– STA. 18+48 TO STA. 19+39

INSET B

–L– STA. 13+90 TO 15+09
–L– STA. 19+09 TO 20+11

INSET C

–L– STA. 15+09 TO 15+53
* –L– STA. 18+89 TO 19+09 (MIRROR)
–L– STA. 20+11 TO 20+31

TYPICAL SECTION 2

–L– STA. 25+54 TO 26+27

* DIMENSION VARIES
(SEE SHEET 2B–1 FOR DETAILS)

6/2/99

3/28/2017
J:\Roadway\Proj\W5601EJ_Rdy_typ.dgn
mlittlefield