

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001010000-N	200	SELECT TREE REMOVAL	9 EA		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	25 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	200 SY		
0010	0241000000-E	SP	GENERIC GRADING ITEM GEOTEXTILE FOR SUBGRADE STABILIZATION	600 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	180 TON		
0012	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	550 SY		
0013	0335200000-E	305	15" DRAINAGE PIPE	124 LF		
0014	0335300000-E	305	18" DRAINAGE PIPE	68 LF		
0015	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	600 LF		
0016	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	752 LF		
0017	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	92 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0995000000-E	340	PIPE REMOVAL	144 LF		
0019	1099500000-E	505	SHALLOW UNDERCUT	200 CY		
0020	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	400 TON		
0021	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5")	320 SY		
0022	1330000000-E	607	INCIDENTAL MILLING	400 SY		
0023	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,170 TON		
0024	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,250 TON		
0025	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,050 TON		
0026	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	240 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0028	1881000000-E	SP	GENERIC PAVING ITEM SINUSOIDAL MILLED RUMBLE STRIPS	620 LF		
0029	2000000000-N	806	RIGHT-OF-WAY MARKERS	15 EA		
0030	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0031	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	500 SY		
0032	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	84 CY		
0033	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0034	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2077000000-E	815	6" OUTLET PIPE	6 LF		
0036	2264000000-E	840	PIPE PLUGS	0.09 CY		
0037	2275000000-E	SP	FLOWABLE FILL	5 CY		
0038	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	25 EA		
0039	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2.8 LF		
0040	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	5 EA		
0041	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	4 EA		
0042	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	8 EA		
0043	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	7 EA		
0044	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,360 LF		
0045	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	100 LF		
0046	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	50 SY		
0047	3030000000-E	862	STEEL BEAM GUARDRAIL	437.5 LF		
0048	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	25 LF		
0049	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0050	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0051	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	3 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	3649000000-E	876	RIP RAP, CLASS B	40 TON		
0053	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	235 SY		
0054	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	172.5 LF		
0055	4102000000-N	904	SIGN ERECTION, TYPE E	18 EA		
0056	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	13 EA		
0057	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	128 SF		
0058	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0059	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	38 DAY		
0060	4430000000-N	1130	DRUMS	90 EA		
0061	4435000000-N	1135	CONES	25 EA		
0062	4455000000-N	1150	FLAGGER	400 DAY		
0063	4510000000-N	1190	LAW ENFORCEMENT	48 HR		
0064	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	12,115 LF		
0065	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	620 LF		
0066	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	365 LF		
0067	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	280 LF		
0068	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	134 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	32 EA		
0070	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,735 LF		
0071	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	365 LF		
0072	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	280 LF		
0073	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	134 LF		
0074	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	32 EA		
0075	6000000000-E	1605	TEMPORARY SILT FENCE	1,000 LF		
0076	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	180 TON		
0077	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,595 TON		
0078	6012000000-E	1610	SEDIMENT CONTROL STONE	575 TON		
0079	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0080	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0081	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0082	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0083	6029000000-E	SP	SAFETY FENCE	120 LF		
0084	6030000000-E	1630	SILT EXCAVATION	2,550 CY		
0085	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,750 SY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6042000000-E	1632	1/4" HARDWARE CLOTH	325 LF		
0087	6071002000-E	1642	FLOCCULANT	540 LB		
0088	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0089	6087000000-E	1660	MOWING	3 ACR		
0090	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0091	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0092	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0093	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0094	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0095	6114800000-N	SP	MANUAL LITTER REMOVAL	8 MHR		
0096	6114900000-E	SP	LITTER DISPOSAL	1 TON		
0097	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	25 EA		
0098	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0099	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION - (TYPE 2)	14 EA		
0100	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION CLEANOUT	42 EA		
0101	7060000000-E	1705	SIGNAL CABLE	2,400 LF		
0102	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	11 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	4 EA		
0104	7252000000-E	1710	MESSENGER CABLE (1/4")	80 LF		
0105	7264000000-E	1710	MESSENGER CABLE (3/8")	650 LF		
0106	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	25 LF		
0107	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	1,400 LF		
0108	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	14 EA		
0109	7360000000-N	1720	WOOD POLE	4 EA		
0110	7372000000-N	1721	GUY ASSEMBLY	9 EA		
0111	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0112	7420000000-E	1722	2" RISER WITH WEATHERHEAD	5 EA		
0113	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0114	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,100 LF		
0115	7456100000-E	1726	LEAD-IN CABLE (14-2)	3,610 LF		
0116	7481000000-N	SP	SITE SURVEY	1 EA		
0117	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	4 EA		
0118	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	4 EA		
0119	7541000000-N	1731	MODIFY SPLICE ENCLOSURE	1 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0120	7575170000-E	1738	BACK PULL FIBER OPTIC CABLE	150 LF		
0121	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0122	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0123	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (2070LX, BASE MTD)	1 EA		
0124	7744000000-N	1751	DETECTOR CARD (TYPE 170)	8 EA		
0125	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0126	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	1 EA		

1244/May08/Q61938.14/D529517882000/E126

Total Amount Of Bid For Entire Project :