DocuSign Envelope ID: B731FA39-534C-4860-BB04-D39CD6FBDA76

8/17/99

Dewberry
2610 WYCLIFF ROAD
SUITE 410
RALEIGH, NC 27607
PHONE: 919.881.9939
NCBELS #: F-0929

| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| R-4436EK | 3B-1 |

HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 12786 ENGINEER STEVEN M. BONDOR

DocuSigned by:
Steve Bondor 3/21/2017
5FD582964149489...

# TOTAL PROJECT SUMMARY

| SUMMARY TOTAL PROJECT | | | |
|---|---|---|---|
| **Section** | **Item** | **Quantity** | **Unit** |
| 800 | MOBILIZATION | 0.5 | LS |
| 801 | CONSTRUCTION SURVEYING | 0.5 | LS |
| 200 | CLEARING AND GRUBBING | 1 | LS |
| 226 | GRADING | 0.4 | LS |
| PSP-1 | FILTRATION MEDIA | 243 | CY |
| PSP-7 | FLOWABLE FILL | 7 | CY |
| 1003 | PIPE PLUGS | 2 | CY |
| 305 | 6" PERF SUBDRN PIPE | 70 | LF |
| 305 | 6" OUTLET PIPE | 40 | LF |
| 305 | 6" HDPE 45 DEGREE FITTING | 4 | EA |
| 305 | 6" HDPE WYE FITTING | 1 | EA |
| 858 | ADJUST CATCH BASIN | 1 | EA |
| 840 | 2 FRAME WITH GRATE STD 840.29 | 1 | EA |
| PSP-2 | CONCRETE CLEANOUT FLUSH MOUNT | 2 | EA |
| 846 | SHOULDER BERM GUTTER | 8 | LF |
| PSP-8 | MODIFIED CONCRETE FLUME WITH FUNNEL OUTLET | 2 | EA |
| 520 | AGGREGATE BASE COURSE (ABC) | 2 | TON |
| 864 | REMOVE & RESET GUARDRAIL | 20 | LF |
| 876 | RIP RAP CL. A | 49 | TON |
| 876 | RIP RAP CL. B | 47 | TON |
| PSP-9 | PREFORMED SCOUR HOLE WITH LEVEL SPREADER APRON | 1 | EA |
| PSP-3 | NO. 57 WASHED STONE | 78 | TON |
| PSP-4 | POLYPROPYLENE NONWOVEN GEOTEXTILE FABRIC | 618 | SY |
| PSP-5 | 3-D GEOTEXTILE PERMANENT SOIL REINFORCEMENT MAT | 16 | SY |
| PSP-6 | DRAINAGE STRUCTURE MARKERS | 2 | EA |
| 1664 | SODDING (BERMUDA) | 261 | SY |
| 1664 | WATER | 8 | 1000 GAL |
| 1660 | SEEDING & MULCHING | 0.2 | ACR |
| 1605 | TEMPORARY SILT FENCE | 400 | LF |
| 1610 | STONE FOR EROSION CONTROL STONE CLASS A | 20 | TON |
| 1610 | SEDIMENT CONTROL STONE | 20 | TON |
| 1105 | TEMPORARY TRAFFIC CONTROL | 0.5 | LS |

3/20/2017 2:08:13 PM
R-4436EK_SHEET_3B-1.dgn
USER: ccrouse