DocuSign Envelope ID: B731FA39-534C-4860-BB04-D39CD6FBDA76

8/17/99

Dewberry
2610 WYCLIFF ROAD
SUITE 410
RALEIGH, NC 27607
PHONE: 919.881.9939
NCBELS #: F-0929

| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| R-4436EK | 1A |

HYDRAULICS ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 12786 ENGINEER STEVEN M. BOUDOR

DocuSigned by:
Steve Boudor
5FD58296149489...

3/21/2017

# INDEX OF SHEETS

INDEX OF SHEETS

| SHEET NUMBER | SHEET |
|---|---|
| 1 | TITLE SHEET |
| 1A | INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS |
| 1B | CONVENTIONAL SYMBOLS |
| 1C–1 | SURVEY CONTROL SHEET |
| 2D–1 | DRAINAGE DETAILS |
| 3B–1 | SUMMARY OF QUANTITIES |
| 4 | SITE PLAN – MEDIA FILTER BASIN |
| 5 | PROFILE – MEDIA FILTER BASIN |
| TMP–1 | TRANSPORTATION MANAGEMENT PLAN |
| EC–1 | EROSION CONTROL PLAN |
| EC–2 | EROSION CONTROL DETAILS |

# STANDARD DRAWINGS

EFF. 01–17–2012
REV. 02–29–2016

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

| STD.NO. | TITLE |
|---|---|
| DIVISION 3 – | PIPE CULVERTS |
| 300.01 | METHOD OF PIPE INSTALLATION |
| DIVISION 8 – | INCIDENTALS |
| 816.04 | MARKERS FOR DRAINAGE STRUCTURE AND CONC PAD |
| 840.25 | ANCHORAGE FOR FRAMES |
| 840.27 | BRICK GRATED DROP INLET TYPE B DETAIL (APRON SUPPORT NOTCH) |
| 840.29 | FRAMES AND NARROW SLOT FLAT GRATES |
| 876.03 | DRAINAGE DITCHES WITH CLASS A RIP RAP |
| 876.04 | DRAINAGE DITCHES WITH CLASS B RIP RAP |

# GENERAL NOTES

1. SPECIFICATIONS: NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES (JANUARY 2012).
2. GRADING: THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATIONS OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY NCDOT IN ORDER TO SECURE A PROPER TIE–IN.
3. SUBSURFACE PLANS: NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHALL PREPARE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

3/20/2017 12:08:05 PM
R:\Proj\R4436_RDY_PSH_1A.dgn
USER: Dewberry