PROJECT NO.	SHEET NO.	TOTAL NO.
DE00124		

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	FINAL SURFACE TESTING REQUIRED	WARM MIX ASPHALT REQUIRED	LENGTH MI	WIDTH FT	1½" MILLING SY	SURFACE COURSE, S9.5B TONS	ASPHALT BINDER FOR PLANT MIX TON	POLYMER MODIFIED ASPHALT BINDER FOR PLANT MIX TON	OPEN-GRADED ASPHALT FRICTION COURSE, TYPE FC-1 MODIFIED TON	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE) LF	PORTABLE LIGHTING LS
DE00111	Durham	1	I-85 NB	NC147 OVERPASS BRG TO SR 1401 - COLE MILL RD BRG	1,2	2		NO	NO	0.654	40	1,533	129	8	47	777	6,895	1.00
TOTAL FOR MAP NO. 1										**0.654**		**1,533**	**129**	**8**	**47**	**777**	**6,895**	**1.00**
TOTAL FOR PROJ NO. DE00124										**0.654**		**1,533**	**129**	**8**	**47**	**777**	**6,895**	**1.00**
GRAND TOTAL										**0.654**		**1,533**	**129**	**8**	**47**	**777**	**6,895**	**1.00**

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	4413000000-E WORK ZONE ADVANCE/GENERAL WARNING SIGNING SF	4457000000-N TEMPORARY TRAFFIC CONTROL LS	4510000000-N LAW ENFORCEMENT HR	4688000000-E 6" X 90 MI YELLOW THERMO LF	4688000000-E 6" X 90 MI WHITE THERMO LF	4690000000-E 6" X 120 MI WHITE THERMO LF	4700000000-E 12" X 90 MI WHITE THERMO LF	4905000000-N SNOW PLOWABLE MARKERS EA
DE00111	Durham	1	I-85 NB	NC147 OVERPASS BRG TO SR 1401 - COLE MILL RD BRG	1,2	2		0.654	40	190	1	20	3,435	3,435	1,835	597	116
TOTAL FOR MAP NO. 1								**0.654**		**190**	**1**	**20**	**3,435**	**3,435**	**1,835**	**597**	**116**
TOTAL FOR PROJ NO. DE00124								**0.654**		**190**	**1**	**20**	**3,435**	**3,435**	**1,835**	**597**	**116**
													6,870				
GRAND TOTAL								**0.654**		**190**	**1**	**20**	**3,435**	**3,435**	**1,835**	**597**	**116**
													6,870				