PROPOSED ALIGNMENT CONTROL SHEET

PROJECT REFERENCE NO.	SHEET NO.
92-0135	RW02D-1

Location and Surveys

ETHERILL ENGINEERING
1223 Jones Franklin Rd.
Raleigh, N.C. 27606
License No. F-0377
Bus: 919 851 8077
Fax: 919 851 8107

TRANSPORTATION PLANNING/DESIGN • BRIDGE/STRUCTURE DESIGN
CIVIL/SITE DESIGN • SURVEYING • CONSTRUCTION OBSERVATION

L

TYPE	STATION	NORTH	EAST
POT	10+00.00	943317.3859	2256494.0893
PC	10+50.00	943340.5874	2256538.3803
PCC	11+33.32	943390.7246	2256604.4448
PT	12+03.92	943455.3264	2256627.6250
PC	12+67.81	943519.0762	2256623.4138
PRC	13+42.82	943588.8666	2256645.6987
PRC	14+25.59	943666.3781	2256667.1715
PT	17+17.83	943957.4898	2256643.9301
POT	17+17.83	943957.4898	2256643.9301

NOTES:

1. PROJECT CONTROL WAS ESTABLISHED USING GNSS, THE GLOBAL NAVIGATION SATELLITE SYSTEM.

2. THE PROPOSED ALIGNMENT CONTROL DATA FOR THIS PROJECT HAS BEEN COMPILED FROM VARIOUS SOURCES. IF FURTHER INFORMATINO REGARDING PROJECT CONTROL IS NEEDED, PLEASE CONTACT THE LOCATION AND SURVEYS UNIT.

REVISIONS

6/2/99

$$$$SYSTME$$$$
$$$$LINEWIDTH$$$$