PROJECT REFERENCE NO.	SHEET NO.
17BP.5.R.88	X-1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

'NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00	0	0
11+00.00	66	2
11+50.00	95	1
12+00.00	61	41
12+14.00	4	21
12+50.00	6	131
13+00.00	99	148
13+50.00	218	0
14+00.00	172	1
14+50.00	72	5
14+75.00	18	2

Approximate quantities only. Unclassified excavation, borrow excavation, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

REVISIONS

8/17/99

3/18/2019
ISF\Projects\
20135_RDY_XPL_X1A.dgn