DocuSign Envelope ID: FF1B6C95-E7AE-4694-B065-9829C5A07196

TIP PROJECT: SS-4905BM

CONTRACT:

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

DURHAM COUNTY

TIP NO.	SHEET NO.
SS-4905BM	PMP-1

APPROVED: DocuSigned by: Brandon W. Johnson 6A29A2BE0C9B45E...

DATE: 6/3/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 034371 ENGINEER BRANDON W. JOHNSON

LOCATION: INTERSECTION OF CARVER STREET (SR 1407), BROAD STREET, AND KENAN ROAD.

TYPE OF WORK: GRADING, DRAINAGE, PAVING & STRUCTURES.

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
-L-	THERMO	NONE
-Y1-	THERMO	NONE

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION
	THERMO (8″, 90 MIL)
TP	YELLOW DIAGONAL
TN	WHITE GORELINE
	THERMO (8″, 120 MIL)
T17	3 FT - 3 FT/SP WHITE MINI SKIP
	THERMO (4″, 90 MIL)
TA	WHITE EDGELINE
TB	YELLOW EDGELINE
	THERMO (4″, 120 MIL)
TI	YELLOW DOUBLE CENTER
	THERMO - PAVEMENT MARKING SYMBOLS (90 MIL)
UN	24″ YIELD LINE TRIANGLE

INTERSECTION PAVEMENT MARKINGS

SYMBOL	DESCRIPTION	QUANTITY
	THERMO (8″, 90 MIL)	
TP	YELLOW DIAGONAL	20 LF
TN	WHITE GORE LINE	110 LF
	THERMO (8″, 120 MIL)	
T17	3 FT - 3 FT/SP WHITE MINI SKIP	40 LF
	THERMO (4″, 90 MIL)	
TA	WHITE EDGELINE	700 LF
TB	YELLOW EDGELINE	260 LF
TI	YELLOW DOUBLE CENTER	820 LF
	THERMO (4″, 120 MIL)	
TI	YELLOW DOUBLE CENTER	820 LF
	THERMO - PAVEMENT MARKING SYMBOLS (90 MIL)	
UN	24″ YIELD LINE TRIANGLE	17 EA

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.06	PAVEMENT MARKINGS - LANE DROPS
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS

INDEX

PMP-1 PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET

PMP-2 PAVEMENT MARKING DETAIL SHEETS

Prepared in the Office of:
SUMMIT DESIGN AND ENGINEERING SERVICES
NC FIRM LICENSE No: P-0339
504 Meadowlands Drive
Hillsborough, NC 27278
(919) 732-3883
(919) 732-6676 (FAX)

TRACY N. PARROTT, PE — *PROJECT ENGINEER*

BRANDON W. JOHNSON, PE — *PROJECT DESIGN ENGINEER*

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

03-JUN-2015 08:55
RBT-HDY_PMP_01.dgn
Spencer_Merritt