DocuSign Envelope ID: 6AF55019-F730-45D0-ADF0-CC26DA050E81

TIP PROJECT: SS-4905BM

CONTRACT:

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

TIP NO.	SHEET NO.
SS-4905BM	SIGN-1

APPROVED: DocuSigned by: Brandon W. Johnson 6A29A2BE0C9845E...

DATE: 5/15/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 034371 ENGINEER BRANDON W. JOHNSON

SIGNING PLAN
DURHAM COUNTY

LOCATION: INTERSECTION OF CARVER STREET (SR 1407), BROAD STREET, AND KENAN ROAD.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
903.40	MEDIAN BARRIER SIGN SUPPORT AND ANCHORAGE
904.10	ORIENTATION OF GROUND SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' and 'F' SIGNS ON 'U' CHANNEL POSTS

PROJECT NOTES

1 DISPOSAL OF SIGN SYSTEM, U-CHANNEL

2 RELOCATE SIGN, TYPE "D", "E", or "F"

3 DISPOSAL OF SUPPORT, U-CHANNEL

4 DISPOSAL OF SIGN "E"

GENERAL NOTES

. ALL TYPE 'D' SIGNS BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREETS (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

SUMMARY OF QUANTITES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4078000000	903	SUPPORTS, 2 LB STEEL U-CHANNEL	16	EA.
4102000000	904	SIGN ERECTION, TYPE E	16	EA.
4116100000	904	SIGN ERECTION, RELOCATE SIGN, TYPE, "D", "E", OR "F"	2	EA.
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	2	EA.

Prepared in the Office of:
SUMMIT DESIGN AND ENGINEERING SERVICES
NC FIRM LICENSE No: P-0339
504 Meadowlands Drive
Hillsborough, NC 27278
(919) 732-3883
(919) 732-6676 (FAX)

TRACY N. PARROTT, PE — *PROJECT ENGINEER*

BRANDON W. JOHNSON, PE — *PROJECT DESIGN ENGINEER*

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

INDEX

SIGN-1 TITLE SHEET

SIGN-2 SIGN PLAN SHEET, SIGN DETAILS

29-APR-2015 15:07
R:\T_ROY_SIGN_01.dgn
brandon_johnson