

Contract Item Sheets For DE00290

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
STRUCTURE ITEMS						
0001	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	12 LF		
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH MILL ASP PVMY 1.5" DEPTH	2,410 SY		
0003	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	250 TON		
0004	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	13 TON		
0005	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0006	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	88 LF		
0007	2591000000-E	848	4" CONCRETE SIDEWALK	84 SY		
0008	2938000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE	1 EA		
0009	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	160 SF		
0010	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	200 SF		
0011	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	10 SF		
0012	4415000000-N	1115	FLASHING ARROW BOARD	4 EA		
0013	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0014	4430000000-N	1130	DRUMS	110 EA		
0015	4434000000-N	SP	SEQUENTIAL FLASHING WARNING LIGHTS	35 EA		
0016	4447000000-E	SP	PEDESTRIAN CHANNELIZING DE- VICES	18 LF		
0017	4480000000-N	1165	TMA	2 EA		
0018	4510000000-N	1190	LAW ENFORCEMENT	300 HR		
0019	4520000000-N	1266	TUBULAR MARKERS (FIXED)	20 EA		

Contract Item Sheets For DE00290

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0020	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	300 LF		
0021	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	200 LF		
0022	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	5 EA		
0023	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") 4" COLD APPL PLSTIC LINES, TYP E II	300 LF		
0024	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") 8" COLD APPL PLSTIC LINES, TYP E II	90 LF		
0025	4800000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING CHARACTER, TYPE ** COLD APPL PLAS CHAR, TYPE II	4 EA		
0026	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** COLD APPL PLASTIC SYM, TYPE II	7 EA		
0027	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,600 LF		
0028	4892000000-N	1205	GENERIC PAVEMENT MARKING ITEM THERMOPLASTIC PVMT MARKING CHARACTER 90 MILS	4 EA		
0029	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	50 EA		
0030	6000000000-E	1605	TEMPORARY SILT FENCE	25 LF		
0031	8161000000-E	420	GROOVING BRIDGE FLOORS	32,185 SF		
0032	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	143 CY		
0033	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	7,283 LB		
0034	8559000000-E	SP	CLASS II, SURFACE PREPARATION	2 SY		

Contract Item Sheets For DE00290

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0035	8860000000-N	SP	GENERIC STRUCTURE ITEM MOLDED RUBBER SEGMENTAL EXP JO INT	Lump Sum LS		
0036	8867000000-E	SP	GENERIC STRUCTURE ITEM SILICONE JOINT SEALANT	312 LF		
0037	8867000000-E	SP	GENERIC STRUCTURE ITEM TEMP STEEL COVER FOR EXP JT SE AL REPAIR	101 LF		
0038	8881000000-E	SP	GENERIC STRUCTURE ITEM PPC MATERIALS	129 CY		
0039	8892000000-E	SP	GENERIC STRUCTURE ITEM JOINT REPAIR	243 SF		
0040	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR FOR PPC O VERLAY	2 SY		
0041	8893000000-E	SP	GENERIC STRUCTURE ITEM PLACING AND FINISHING PPC OVER LAY	3,716 SY		
0042	8893000000-E	SP	GENERIC STRUCTURE ITEM SCARIFYING BRIDGE DECK	3,716 SY		
0043	8893000000-E	SP	GENERIC STRUCTURE ITEM SHOTBLASTING BRIDGE DECK	3,716 SY		
44	0000100000-N	800	MOBILIZATION	Lump Sum LS		
45	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM REMOVAL OF CONCRETE MEDIAN	155 SY		
TOTAL AMOUNT OF BID FOR ENTIRE PROJECT						\$0.00