

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (11+90)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	400 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	325 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	700 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	20 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	50 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	20 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	76 LF		
0014	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	52 LF		
0015	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0016	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	580 TON		
0019	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	625 TON		
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	510 TON		
0021	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	90 TON		
0022	2000000000-N	806	RIGHT-OF-WAY MARKERS	11 EA		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0024	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	65 LF		
0027	2591000000-E	848	4" CONCRETE SIDEWALK	25 SY		
0028	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0029	3030000000-E	862	STEEL BEAM GUARDRAIL	75 LF		
0030	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0031	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	4 EA		
0033	3628000000-E	876	RIP RAP, CLASS I	15 TON		
0034	3635000000-E	876	RIP RAP, CLASS II	280 TON		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	3649000000-E	876	RIP RAP, CLASS B	40 TON		
0036	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	700 SY		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	299 SF		
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	141 SF		
0039	4422000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)	56 DAY		
0040	4430000000-N	1130	DRUMS	12 EA		
0041	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0042	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,259 LF		
0043	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	55 LF		
0044	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2 EA		
0045	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM WHITE STOP BAR (24", 90 MIL)	44 LF		
0046	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
0047	5815500000-N	1530	REMOVE FIRE HYDRANT	1 EA		
0048	6000000000-E	1605	TEMPORARY SILT FENCE	1,350 LF		
0049	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	95 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0053	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0054	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0055	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0056	6029000000-E	SP	SAFETY FENCE	320 LF		
0057	6030000000-E	1630	SILT EXCAVATION	120 CY		
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,340 SY		
0059	6037000000-E	SP	COIR FIBER MAT	100 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	135 LF		
0061	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	170 SY		
0062	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0063	6071012000-E	SP	COIR FIBER WATTLE	350 LF		
0064	6071020000-E	SP	POLYACRYLAMIDE (PAM)	35 LB		
0065	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0066	6087000000-E	1660	MOWING	3 ACR		
0067	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0068	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0070	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0071	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7 EA		
0073	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0074	6123000000-E	1670	REFORESTATION	0.48 ACR		
0075	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (STA. 11+90.50)	Lump Sum	L.S.	
0076	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STA. 11+90.50)	Lump Sum	L.S.	
0077	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0078	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	80 LF		
0079	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	40 LF		
0080	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	98 LF		
0081	8113000000-N	411	SID INSPECTIONS	1 EA		
0082	8115000000-N	411	CSL TESTING	1 EA		
0083	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (STA. 11+90.50)	Lump Sum	L.S.	
0084	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	63.1 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STA. 11+90.50)	Lump Sum	L.S.	
0086	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,949 LB		
0087	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,451 LB		
0088	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12X53)	16 EA		
0089	8364000000-E	450	HP 12 X 53 STEEL PILES	460 LF		
0090	8391000000-N	450	STEEL PILE POINTS	16 EA		
0091	8475000000-E	460	TWO BAR METAL RAIL	155.25 LF		
0092	8517000000-E	460	1'*** X ***** CONCRETE PARAPET (1'-2" X 2'-9.5")	85.13 LF		
0093	8517000000-E	460	1'*** X ***** CONCRETE PARAPET (1'-2" X 3'-8")	85.13 LF		
0094	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	120 TON		
0095	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	130 SY		
0096	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0097	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,445 LF		
0098	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	27 CY		
0099	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	891 LB		