DocuSign Envelope ID: 48716AF9-1B10-47EE-B9CD-C629105D2DF8

4/11/2018 12:55:31 PM G:\Projects\2016\Division 5 (Mott Macdonald)\B-5682 Granville #129 (105 33BBU 2BMR)\Structures\Drawings\Final\401_B5682_SMU_LRFR.dgn

LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL		VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE											SERVICE III LIMIT STATE						COMMENT NUMBER
								MOMENT					SHEAR						MOMENT					
							LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING		HL-93(Inv)	N/A	1	1.126	--	1.75	0.267	1.49	A	EL	44.224	0.584	1.15	A	EL	8.845	0.80	0.267	**1.13**	A	EL	**44.224**	
		HL-93(Opr)	N/A	--	1.488	--	1.35	0.267	1.94	A	EL	44.224	0.584	1.49	A	EL	8.845	N/A	--	--	--	--	--	
		HS-20(Inv)	36.000	2	1.491	53.666	1.75	0.267	2.03	A	EL	44.224	0.584	**1.49**	A	EL	**8.845**	0.80	0.267	1.53	A	EL	44.224	
		HS-20(Opr)	36.000	--	1.932	69.567	1.35	0.267	2.63	A	EL	44.224	0.584	1.93	A	EL	8.845	N/A	--	--	--	--	--	
LEGAL LOAD RATING	SV	SNSH	13.500	--	3.573	48.237	1.4	0.267	5.92	A	EL	44.224	0.584	4.53	A	EL	8.845	0.80	0.267	3.57	A	EL	44.224	
		SNGARBS2	20.000	--	2.611	52.229	1.4	0.267	4.33	A	EL	44.224	0.584	3.19	A	EL	8.845	0.80	0.267	2.61	A	EL	44.224	
		SNAGRIS2	22.000	--	2.452	53.948	1.4	0.267	4.07	A	EL	44.224	0.584	2.95	A	EL	8.845	0.80	0.267	2.45	A	EL	44.224	
		SNCOTTS3	27.250	--	1.777	48.412	1.4	0.267	2.95	A	EL	44.224	0.584	2.26	A	EL	8.845	0.80	0.267	1.78	A	EL	44.224	
		SNAGGRS4	34.925	--	1.465	51.163	1.4	0.267	2.43	A	EL	44.224	0.584	1.85	A	EL	8.845	0.80	0.267	1.46	A	EL	44.224	
		SNS5A	35.550	--	1.434	50.974	1.4	0.267	2.38	A	EL	44.224	0.584	1.87	A	EL	8.845	0.80	0.267	1.43	A	EL	44.224	
		SNS6A	39.950	--	1.307	52.234	1.4	0.267	2.17	A	EL	44.224	0.584	1.69	A	EL	8.845	0.80	0.267	1.31	A	EL	44.224	
		SNS7B	42.000	--	1.245	52.283	1.4	0.267	2.06	A	EL	44.224	0.584	1.65	A	EL	8.845	0.80	0.267	1.24	A	EL	44.224	
	TTST	TNAGRIT3	33.000	--	1.592	52.537	1.4	0.267	2.64	A	EL	44.224	0.584	2.02	A	EL	8.845	0.80	0.267	1.59	A	EL	44.224	
		TNT4A	33.075	--	1.597	52.815	1.4	0.267	2.65	A	EL	44.224	0.584	1.98	A	EL	8.845	0.80	0.267	1.60	A	EL	44.224	
		TNT6A	41.600	--	1.298	53.997	1.4	0.267	2.15	A	EL	44.224	0.584	1.74	A	EL	8.845	0.80	0.267	1.30	A	EL	44.224	
		TNT7A	42.000	--	1.3	54.619	1.4	0.267	2.16	A	EL	44.224	0.584	1.71	A	EL	8.845	0.80	0.267	1.30	A	EL	44.224	
		TNT7B	42.000	--	1.335	56.09	1.4	0.267	2.21	A	EL	44.224	0.584	1.62	A	EL	8.845	0.80	0.267	1.34	A	EL	44.224	
		TNAGRIT4	43.000	--	1.278	54.943	1.4	0.267	2.12	A	EL	44.224	0.584	1.57	A	EL	8.845	0.80	0.267	1.28	A	EL	44.224	
		TNAGT5A	45.000	--	1.208	54.37	1.4	0.267	2	A	EL	44.224	0.584	1.55	A	EL	8.845	0.80	0.267	1.21	A	EL	44.224	
		TNAGT5B	45.000	3	1.197	53.852	1.4	0.267	1.98	A	EL	44.224	0.584	1.5	A	EL	8.845	0.80	0.267	**1.20**	A	EL	**44.224**	

LOAD FACTORS:

	LIMIT STATE	γ_{DC}	γ_{DW}
DESIGN LOAD RATING FACTORS	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.

ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

DISTANCE FROM LEFT END OF SPAN IS MEASURED FROM ℄ BEARING.

(#) CONTROLLING LOAD RATING

(1) DESIGN LOAD RATING (HL-93)

(2) DESIGN LOAD RATING (HS-20)

(3) LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER



LRFR SUMMARY

SPAN A

PROJECT NO. B-5682

GRANVILLE COUNTY

STATION: 14+55.00 -L-

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

LRFR SUMMARY FOR 90'-0" BOX BEAM UNIT 105° SKEW

(NON-INTERSTATE TRAFFIC)

PLANS PREPARED BY:

SIMPSON ENGINEERS & ASSOCIATES
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.simpsonengr.com
LICENSURE NO. C-2521

NORTH CAROLINA PROFESSIONAL SEAL 11268 ENGINEER BETSY S. COX

4/11/2018

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

REVISIONS						
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			
2			4			

SHEET NO. S-3

TOTAL SHEETS 19

DRAWN BY: S.D. COOPER DATE: 4-18
CHECKED BY: B.S. COX DATE: 4-18
DESIGN ENGINEER OF RECORD: B.S. COX DATE: 4-18