

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0008	0255000000-E	SP	GENERIC GRADING ITEM HAULING AND DISPOSAL OF CONTAMINATED SOIL	100 TON		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	190 TON		
0010	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	580 SY		
0011	0335200000-E	305	15" DRAINAGE PIPE	8 LF		
0012	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	1,116 LF		
0013	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	184 LF		
0014	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	416 LF		
0015	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	8 LF		
0016	0995000000-E	340	PIPE REMOVAL	305 LF		
0017	1099500000-E	505	SHALLOW UNDERCUT	100 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0019	1112000000-E	505	GEOTEXTILE FOR SUBGRADE STABILIZATION	300 SY		
0020	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1 1/2")	200 SY		
0021	1330000000-E	607	INCIDENTAL MILLING	650 SY		
0022	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	540 TON		
0023	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	430 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	770 TON		
0025	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	95 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	93 TON		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0028	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	500 SY		
0029	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	84 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0031	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0032	2077000000-E	815	6" OUTLET PIPE	6 LF		
0033	2264000000-E	840	PIPE PLUGS	0.045 CY		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	21 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.6 LF		
0036	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0037	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0038	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
0040	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	12 EA		
0041	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,830 LF		
0042	3628000000-E	876	RIP RAP, CLASS I	90 TON		
0043	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0044	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	983 SY		
0045	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	53 SF		
0046	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	86 LF		
0047	4102000000-N	904	SIGN ERECTION, TYPE E	14 EA		
0048	4116100000-N	904	SIGN ERECTION, RELOCATE TYPE **** (GROUND MOUNTED) (E)	2 EA		
0049	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	5 EA		
0050	4510000000-N	1190	LAW ENFORCEMENT	550 HR		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0051	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0052	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	7,114 LF		
0053	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	51 LF		
0054	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	208 LF		
0055	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	14 EA		
0056	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,114 LF		
0057	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	51 LF		
0058	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	208 LF		
0059	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	11 EA		
0060	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0061	5656100000-E	1515	RELOCATE *** RPZ BACKFLOW PREVENTION ASSEMBLY (1")	1 EA		
0062	5686500000-E	1515	WATER SERVICE LINE	12 LF		
0064	6000000000-E	1605	TEMPORARY SILT FENCE	1,665 LF		
0065	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	270 TON		
0066	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70 TON		
0067	6012000000-E	1610	SEDIMENT CONTROL STONE	235 TON		
0068	6015000000-E	1615	TEMPORARY MULCHING	0.8 ACR		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0070	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0071	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0072	6029000000-E	SP	SAFETY FENCE	1,120 LF		
0073	6030000000-E	1630	SILT EXCAVATION	150 CY		
0074	6036000000-E	1631	MATting FOR EROSION CONTROL	2,100 SY		
0075	6037000000-E	1629	COIR FIBER MAT	195 SY		
0076	6042000000-E	1632	1/4" HARDWARE CLOTH	770 LF		
0077	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0078	6071002000-E	1642	FLOCCULANT	110 LB		
0079	6071012000-E	1642	COIR FIBER WATTLE	390 LF		
0080	6084000000-E	1660	SEEDING & MULCHING	0.8 ACR		
0081	6087000000-E	1660	MOWING	0.4 ACR		
0082	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0083	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0084	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0085	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0087	6114800000-N	SP	MANUAL LITTER REMOVAL	8 MHR		
0088	6114900000-E	SP	LITTER DISPOSAL	1 TON		
0089	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	13 EA		
0090	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0091	6123000000-E	1670	REFORESTATION	0.1 ACR		
0092	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION CLEANOUT	54 EA		
0093	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FABRIC INSERT INLET PROTECTION, TYPE 1	18 EA		
0094	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	9 EA		
0095	7060000000-E	1705	SIGNAL CABLE	1,300 LF		
0096	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	7 EA		
0097	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0098	7252000000-E	1710	MESSENGER CABLE (1/4")	360 LF		
0099	7264000000-E	1710	MESSENGER CABLE (3/8")	350 LF		
0100	7288000000-E	1715	PAVED TRENCHING (***** (1, 2"))	25 LF		
0101	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2"))	550 LF		
0102	7300000000-E	1715	UNPAVED TRENCHING (***** (2, 2"))	25 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	7 EA		
0104	7360000000-N	1720	WOOD POLE	2 EA		
0105	7372000000-N	1721	GUY ASSEMBLY	8 EA		
0106	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1 EA		
0107	7420000000-E	1722	2" RISER WITH WEATHERHEAD	4 EA		
0108	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0109	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	700 LF		
0110	7456100000-E	1726	LEAD-IN CABLE (14-2)	2,200 LF		
0111	7481000000-N	SP	SITE SURVEY	1 EA		
0112	7481200000-N	SP	LUMINAIRE ARM FOR VIDEO SYSTEM	2 EA		
0114	7481260000-N	SP	EXTERNAL LOOP EMULATOR PROCESSING UNIT	1 EA		
0115	7528000000-E	1730	DROP CABLE	510 LF		
0116	7540000000-N	1731	SPLICE ENCLOSURE	1 EA		
0117	7552000000-N	1731	INTERCONNECT CENTER	1 EA		
0118	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	100 LF		
0119	7575170000-E	1738	BACK PULL FIBER OPTIC CABLE	310 LF		
0120	7636000000-N	1745	SIGN FOR SIGNALS	1 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0121	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0122	7696000000-N	1751	CONTROLLERS WITH CABINET (*****) (2070LX, BASE MTD)	1 EA		
0123	7744000000-N	1751	DETECTOR CARD (TYPE 170)	7 EA		
0124	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0125	7980000000-N	SP	GENERIC SIGNAL ITEM ETHERNET EDGE SWITCH	1 EA		
0136	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 2" AIR RELEASE VALVE	1 EA		
0137	7481240000-N	SP	CAMERA WITHOUT INTERNAL LOOP EMULATOR PROCESSING UNIT	2 EA		
ROADWAY ITEMS - NPAR (CITY OF RALEIGH)						
0138	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT PLANT MIX, PAVEMENT REPAIR	101 TON		
0139	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT BINDER FOR PLANT MIX	5 TON		
0140	5882000000-N	SP	GENERIC UTILITY ITEM ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0141	5888000000-E	SP	GENERIC UTILITY ITEM 12" WATER LINE	329 LF		
0142	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FITTINGS	3,000 LB		
0143	5882000000-N	SP	GENERIC UTILITY ITEM 6" VALVE	1 EA		
0144	5882000000-N	SP	GENERIC UTILITY ITEM 12" VALVE	1 EA		
0145	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE WATER METER	1 EA		
0146	5882000000-N	SP	GENERIC UTILITY ITEM FIRE HYDRANT	1 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0147	5888000000-E	SP	GENERIC UTILITY ITEM FIRE HYDRANT LEG	8 LF		
0148	5888000000-E	SP	GENERIC UTILITY ITEM WATER SERVICE LINE	38 LF		

1628/Aug06/Q44402.995/D629031844000/E136

Total Amount Of Bid For Entire Project :