

PROJECT SPECIAL PROVISIONS**ROADWAY****BURNING RESTRICTIONS:**

(7-1-95)

200, 210, 215

SP2 R05

Open burning is not permitted on any portion of the right-of-way limits established for this project. Do not burn the clearing, grubbing or demolition debris designated for disposal and generated from the project at locations within the project limits, off the project limits or at any waste or borrow sites in this county. Dispose of the clearing, grubbing and demolition debris by means other than burning, according to state or local rules and regulations.

CONES:

(3-19-24)

1135

SP11 R35

Revise the *Standard Specifications* as follows:

Page 11-11, Article 1135-3 CONSTRUCTION METHODS, lines 19-20, delete the third sentence of the first paragraph, "Do not use cones in the upstream taper of lane or shoulder closures for multi-lane roadways."

PREEMPTION UNITS:

All Preemption Units shown on these plans are to be purchased, installed, maintained, and operated under a separate contract. The Town of Holly Springs will be responsible for engaging in a contract with NCDOT Division 5 Traffic Services for the Town to provide contracting services separately from this contract to procure, install, and maintain these units. All preemption work is unrelated to this contract. There is no operational impact to installing signals as indicated in the plans without installing the preemption equipment.