

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	300 SY		
0006	0248000000-N	SP	GENERIC GRADING ITEM TYPE I APPROACH FILL, STATION -L- 14+23.50	Lump Sum	L.S.	
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	15 TON		
0008	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	50 SY		
0009	0335200000-E	305	15" DRAINAGE PIPE	16 LF		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	16 LF		
0011	0546000000-E	310	*** CAA PIPE CULVERTS, ***** THICK (60", 0.105" THICK (12 GAUGE CONTRACTOR DESIGNED))	100 LF		
0012	0995000000-E	340	PIPE REMOVAL	73 LF		
0013	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0014	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0015	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0016	1330000000-E	607	INCIDENTAL MILLING	235 SY		
0017	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	470 TON		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	470 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	395 TON		
0020	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	70 TON		
0021	2000000000-N	806	RIGHT-OF-WAY MARKERS	8 EA		
0022	2253000000-E	840	PIPE COLLARS	0.45 CY		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0025	2473000000-N	SP	GENERIC DRAINAGE ITEM ALUMINUM STRUCTURAL PLATE HEADWALL FOR 60" CAAP 0.15" THICK CONTRACTOR DESIGNED	1 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	30 LF		
0027	3030000000-E	862	STEEL BEAM GUARDRAIL	62.5 LF		
0028	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0030	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	4 EA		
0031	3628000000-E	876	RIP RAP, CLASS I	50 TON		
0032	3635000000-E	876	RIP RAP, CLASS II	280 TON		
0033	3649000000-E	876	RIP RAP, CLASS B	167 TON		
0034	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,172 SY		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	341 SF		
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0037	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0038	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,200 LF		
0039	6000000000-E	1605	TEMPORARY SILT FENCE	1,360 LF		
0040	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	90 TON		
0041	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0042	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0043	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0044	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0045	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0046	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0047	6029000000-E	SP	SAFETY FENCE	320 LF		
0048	6030000000-E	1630	SILT EXCAVATION	290 CY		
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,320 SY		
0050	6037000000-E	1629	COIR FIBER MAT	100 SY		
0051	6042000000-E	1632	1/4" HARDWARE CLOTH	175 LF		

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6070000000-N	1639	SPECIAL STILLING BASINS	1 EA		
0053	6071002000-E	1642	FLOCCULANT	45 LB		
0054	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0055	6087000000-E	1660	MOWING	3 ACR		
0056	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0058	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0059	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0060	6111000000-E	SP	IMPERVIOUS DIKE	239 LF		
0061	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0062	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	13 EA		
0063	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0064	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0065	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+23.50 -L-)	Lump Sum	L.S.	
0066	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (14+23.50 -L-)	Lump Sum	L.S.	

County: GRANVILLE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	51.2 CY		
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+23.50 -L-)	Lump Sum	L.S.	
0070	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,058 LB		
0071	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12 X 53)	14 EA		
0072	8364000000-E	450	HP 12 X 53 STEEL PILES	245 LF		
0073	8391000000-N	450	STEEL PILE POINTS	14 EA		
0074	8392500000-E	450	PREDRILLING FOR PILES	35 LF		
0075	8394000000-N	450	DYNAMIC PILE TESTING	1 EA		
0076	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	170 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	220 TON		
0078	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	245 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0080	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	935 LF		

1341/Aug08/Q26941/D364779702000/E80

Total Amount Of Bid For Entire Project :