

DF18405.2073011

TIP NO

0.100 MILES

FED AID NO DF18405.2073011  
EMERGENCY PIPE REPLACEMENT  
SR 1305 MILL HILLRD AT RICHLAND CREEK

				JYMCO CONSTRUCTION COMPANY INC  SMITHFIELD, NC		FSC II LLC DBA FRED SMITH COMPANY  RALEIGH, NC		RALPH HODGE CONSTRUCTION COMPANY DBA RALPH HODGE CONSTRUCTIO WILSON, NC			
<b>ROADWAY ITEMS</b>											
0001	0000100000-N	800	MOBILIZATION	Lump Sum		35,000.00		37,000.00		27,000.00	
0003	0043000000-N	226	GRADING (226)	Lump Sum		100,000.00		103,000.00		91,000.00	
0004	0314000000-E	SP	SELECT MATERIAL CLASS ** V OR VI	961 TON	52.00	49,972.00	42.00	40,362.00	71.00	68,231.00	
0005	0318000000-E	300	FND CONDIT MATL MINOR STRS	118 TON	52.00	6,136.00	42.00	4,956.00	71.00	8,378.00	
0006	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	182 SY	6.00	1,092.00	6.50	1,183.00	8.30	1,510.60	
0007	1121000000-E	520	AGGREGATE BASE COURSE	1,711 TON	46.00	78,706.00	50.00	85,550.00	47.40	81,101.40	
0008	1220000000-E	545	INCIDENTAL STONE BASE	5 TON	100.00	500.00	50.00	250.00	47.40	237.00	
0009	1297000000-E	607	MILL ASP PVMT ***** DTH 1.5"	212 SY	25.00	5,300.00	20.00	4,240.00	17.80	3,773.60	
0010	1491000000-E	610	ASP CONC BASE CRS B25.0C	26 TON	290.00	7,540.00	325.00	8,450.00	296.00	7,696.00	
0011	1519000000-E	610	ASP CONC SURF CRS S9.5B	42 TON	290.00	12,180.00	320.00	13,440.00	296.00	12,432.00	
0012	1575000000-E	620	ASP FOR PLANT MIX	5 TON	800.00	4,000.00	675.00	3,375.00	753.00	3,765.00	
0013	2484000000-E	SP	GENERIC DRAINAGE ITEM (LF) TWIN 13'-1" SPAN X 8'-4" RISE .200" THICK ALUM STRUCTURAL PLATE PIPE ARCH W/ HEA	144 LF	2,144.00	308,736.00	2,850.00	410,400.00	2,770.00	398,880.00	
0014	3635000000-E	876	RIP RAP, CLASS II	100 TON	83.00	8,300.00	92.00	9,200.00	110.00	11,000.00	
0015	3649000000-E	876	RIP RAP, CLASS B	125 TON	76.00	9,500.00	75.00	9,375.00	114.00	14,250.00	
0016	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	240 SY	7.00	1,680.00	6.50	1,560.00	8.30	1,992.00	
0017	4810000000-E	1205	PAINT PVMT MARKINGS 4"	271 LF	19.00	5,149.00	18.00	4,878.00	7.10	1,924.10	
0018	6000000000-E	1605	TEMPORARY SILT FENCE	750 LF	7.00	5,250.00	3.00	2,250.00	5.90	4,425.00	
0019	6006000000-E	1610	EROS CONTRL STONE CL A	50 TON	78.00	3,900.00	40.00	2,000.00	59.20	2,960.00	
0020	6012000000-E	1610	SEDIMENT CONTROL STONE	25 TON	100.00	2,500.00	70.00	1,750.00	53.30	1,332.50	
0021	6018000000-E	1620	SEED FOR TEMP SEEDING	50 LB	20.00	1,000.00	3.50	175.00	5.90	295.00	
0022	6021000000-E	1620	FERT FOR TEMP SEEDING	1 TON	500.00	500.00	100.00	100.00	947.00	947.00	
0023	6030000000-E	1630	SILT EXCAVATION	25 CY	30.00	750.00	50.00	1,250.00	17.80	445.00	
0024	6036000000-E	1631	MATTING FOR EROS CONTROL	300 SY	6.00	1,800.00	2.25	675.00	8.30	2,490.00	
0025	6037000000-E	1629	COIR FIBER MAT	400 SY	9.00	3,600.00	6.00	2,400.00	9.50	3,800.00	
0026	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF	2.00	120.00	7.00	420.00	5.90	354.00	
0027	6070000000-N	1639	SPECIAL STILLING BASINS	4 EA	6,000.00	24,000.00	250.00	1,000.00	888.00	3,552.00	
0028	6071010000-E	1642	WATTLE	200 LF	20.00	4,000.00	8.00	1,600.00	23.70	4,740.00	
0029	6084000000-E	1660	SEEDING AND MULCHING	1 ACR	6,000.00	6,000.00	761.00	761.00	3,550.00	3,550.00	
0030	6111000000-E	SP	IMPERVIOUS DIKE	80 LF	350.00	28,000.00	150.00	12,000.00	237.00	18,960.00	
0031	6144000000-E	SP	GENERIC EROSION CONTROL ITEM (LB) POLYACRYLAMIDE	20 LB	20.00	400.00	5.00	100.00	23.70	474.00	
CONTRACT TOTAL						TOTAL	715,611.00	TOTAL	763,700.00	TOTAL	781,495.20
ROADWAY ITEMS						SUB-TOTAL	715,611.00	SUB-TOTAL	763,700.00	SUB-TOTAL	781,495.20

DF18405.2073011

TIP NO

0.100 MILES

FED AID NO DF18405.2073011

EMERGENCY PIPE REPLACEMENT

SR 1305 MILL HILLRD AT RICHLAND CREEK

---

**BIDDERS IN ORDER**

**CONTRACT TOTAL**

JYMCO CONSTRUCTION COMPANY INC	1	715,611.00
FSC II LLC DBA FRED SMITH COMPANY	2	763,700.00
RALPH HODGE CONSTRUCTION COMPANY DBA RALPH HODGE CONSTRUCTIO	3	781,495.20