

5/26/20

DIVISION OF HIGHWAYS  
STATE OF NORTH CAROLINA

SUMMARY OF MILLING

IN SQUARE YARDS

SURVEY LINE	STATION	STATION	LOCATION LT/RT/CL	PLAN. AREA SQ. FT.	WIDTH FT.	SQ. YDS.
-Y-	11+31.00	-Y- 13+07.00	CL	9160	VARIES	1020
			TOTAL:			1020
			SAY:			1050

SUMMARY OF EARTHWORK

IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + %	BORROW EXCAVATION	WASTE
-Y- 11+37.00 CL TO -Y- 13+07.00 CL	80	0	80	80
				0
SUBTOTALS No. 1	80	0	80	80
SUBTOTALS No. 2	0	0	0	0
PROJECT SUBTOTALS	80	0	80	80
WASTE IN LIEU OF BORROW				
PROJECT TOTALS	80	0	80	80
REPLACE TOP SOIL BORROW PITS				
GRAND TOTALS	80		80	
SAY	90		100	

SHALLOW UNDERCUT: 100 CY  
CLASS IV STABILIZATION: 200 TONS  
GEOTEXTILE FOR SUBGRADE STABILIZATION: 300 SY

Note: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, Breaking of Existing Pavement, and Removal of Existing Pavement will be paid for at the contract lump sum price for "Grading."