

ADA SUMMARY OF QUANTITIES - KINGPOST DR FROM SR 4701 TO SR 5093

Municipality:

Outside Municipality

WBS

2026CPT.05.10.20921.1,2026CPT.05.10.20922.1

Number:

County:

Wake

Sheet No.

37

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	Improvement Type
26362	1	SR-4702 (Kingpost Dr)	SR-5093 (Greenbreeze Ln)	4			1	Type 1 Modified - 848.06
26363	1	SR-4702 (Kingpost Dr)	SR-5093 (Greenbreeze Ln)	4			1	Type 1 Modified - 848.06
26364	2	SR-4702 (Kingpost Dr)	SR-4703 (Basal Creek Ln)				1	Type 1C - 848.06
26365**	2	SR-4702 (Kingpost Dr)	SR-4703 (Basal Creek Ln)	4			1	Type 1 Modified - 848.06
26367	3	SR-4702 (Kingpost Dr)	SR-4701 (Cypress Ford Dr)	15		6	1	Type 4B - 848D0610
26368	3	SR-4702 (Kingpost Dr)	SR-4701 (Cypress Ford Dr)	4			1	Type 1 Modified - 848.06
26369	4	SR-4702 (Kingpost Dr)	SR-4701 (Cypress Ford Dr)	4			1	Type 1 Modified - 848.06
26370	4	SR-4702 (Kingpost Dr)	SR-4701 (Cypress Ford Dr)	4			1	Type 1 Modified - 848.06
-	-	-	-	-	4*	-	-	
Sub-Total for Kingpost Dr From SR 4701 To SR 5093				39	4	6	8	

*Contingency line item amount provided for adjustments outside of curb ramp pay limits.

**While ramp is compliant upon initial inspection, it is to be improved in order to create a more resilient curb ramp.

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted.