

ADA SUMMARY OF QUANTITIES - SHADY GREENS DR FROM SR 1393 TO CUL-DE-SAC

Municipality:

Fuquay-Varina

WBS

2026CPT.05.10.20921.1,2026CPT.05.10.20922.1

Number:

County:

Wake

Sheet No.

41

Ramp ID	Inset Map Number	Route 1	Route 2	0156000000-E (SY) Removal of Existing Asphalt Pavement	2752000000-E (LF) Remove And Replace 2'-6" Concrete Curb & Gutter	2591000000-E (SY) 4" Concrete Sidewalk	2612500000-N (EA) Remove and Replace Concrete Curb Ramps	Improvement Type
26371	1	SR-4771 (Shady Greens Dr)	Greenway Crossing Near Hilltop Needmore Rd	12			1	Type 1 Modified - 848.06
26372	1	SR-4771 (Shady Greens Dr)	Greenway Crossing Near Hilltop Needmore Rd	12			1	Type 1 Modified - 848.06
26373	2	SR-4771 (Shady Greens Dr)	Greenway Crossing near Greensflag Ln	12			1	Type 1 Modified - 848.06
26374	2	SR-4771 (Shady Greens Dr)	Greenway Crossing near Greensflag Ln	12			1	Type 1 Modified - 848.06
26375	3	SR-4771 (Shady Greens Dr)	Greenway Crossing Near 4628 Shady Greens Dr	12			1	Type 1 Modified - 848.06
26376	3	SR-4771 (Shady Greens Dr)	Greenway Crossing Near 4628 Shady Greens Dr	12			1	Type 1 Modified - 848.06
-	-	-	-	-	8*	-	-	
Sub-Total for Shady Greens Dr From SR 1393 To Cul-de-sac				72	8	0	6	

Notes: (1) ADA quantity totals are provided on the project 'ADA SUMMARY OF QUANTITIES - TOTALS' page. (2) Construct in accordance with Section 848. Detectable warnings shall be of one of the following materials: engineered plastics, rubber, or composite tile. Additionally, warnings shall be applied directly to the curb ramps by incorporating into the concrete of the curb ramps unless otherwise approved by the Engineer. Surface mounted rubber mats, brick, steel and stamped concrete pavers will not be accepted.