

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0028000000-N	SP	TYPE I STANDARD APPROACH FILL STATION ***** (STA. 18+40.76)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	475 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	50 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	400 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	110 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	520 SY		
0012	0335200000-E	305	15" DRAINAGE PIPE	112 LF		
0013	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	2 EA		
0014	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	28 LF		
0015	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	120 LF		
0016	0992000000-E	SP	GENERIC PIPE ITEM TEMPORARY STEEL PLATE COVER	1 EA		
0017	0995000000-E	340	PIPE REMOVAL	101 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1099500000-E	505	SHALLOW UNDERCUT	100 CY		
0019	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	200 TON		
0020	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0021	1330000000-E	607	INCIDENTAL MILLING	560 SY		
0022	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,170 TON		
0023	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,010 TON		
0024	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	920 TON		
0025	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	165 TON		
0026	2000000000-N	806	RIGHT-OF-WAY MARKERS	20 EA		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0028	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	1 EA		
0029	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1 EA		
0030	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	1 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0033	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	660 LF		
0034	2556000000-E	846	SHOULDER BERM GUTTER	25 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2612000000-E	848	6" CONCRETE DRIVEWAY	142 SY		
0036	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
0037	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	1 EA		
0038	3030000000-E	862	STEEL BEAM GUARDRAIL	75 LF		
0039	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	37.5 LF		
0040	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0041	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0042	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0043	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	3 EA		
0044	3649000000-E	876	RIP RAP, CLASS B	45 TON		
0045	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	300 SY		
0046	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	72 SF		
0047	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	160 SF		
0048	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	108 SF		
0049	4430000000-N	1130	DRUMS	33 EA		
0050	4435000000-N	1135	CONES	20 EA		
0051	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4455000000-N	1150	FLAGGER	22 DAY		
0053	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,276 LF		
0054	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	592 LF		
0055	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,820 LF		
0056	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	114 LF		
0057	4891000000-E	1205	GENERIC PAVEMENT MARKING ITEM THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	57 LF		
0058	5326200000-E	1510	12" WATER LINE	426 LF		
0059	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	920 LB		
0060	5540000000-E	1515	6" VALVE	1 EA		
0061	5558000000-E	1515	12" VALVE	1 EA		
0063	5606000000-E	1515	2" BLOW OFF	1 EA		
0064	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0065	5666000000-N	1515	FIRE HYDRANT	1 EA		
0066	5673000000-E	1515	FIRE HYDRANT LEG	14 LF		
0067	5686500000-E	1515	WATER SERVICE LINE	90 LF		
0068	5804000000-E	1530	ABANDON 12" UTILITY PIPE	410 LF		
0069	5835900000-E	1540	20" ENCASMENT PIPE	49 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0070	6000000000-E	1605	TEMPORARY SILT FENCE	2,610 LF		
0071	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0072	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	205 TON		
0073	6012000000-E	1610	SEDIMENT CONTROL STONE	140 TON		
0074	6015000000-E	1615	TEMPORARY MULCHING	5.5 ACR		
0075	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	500 LB		
0076	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5 TON		
0077	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0078	6030000000-E	1630	SILT EXCAVATION	230 CY		
0079	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,000 SY		
0080	6042000000-E	1632	1/4" HARDWARE CLOTH	395 LF		
0081	6071012000-E	SP	COIR FIBER WATTLE	120 LF		
0082	6071014000-E	SP	COIR FIBER WATTLE BARRIER	50 LF		
0083	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0084	6071030000-E	1640	COIR FIBER BAFFLE	80 LF		
0085	6084000000-E	1660	SEEDING & MULCHING	9 ACR		
0086	6087000000-E	1660	MOWING	6 ACR		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0087	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0088	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0089	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	175 LB		
0090	6108000000-E	1665	FERTILIZER TOPDRESSING	4.75 TON		
0091	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0092	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7 EA		
0093	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0109	5689000000-E	1515	GENERIC UTILITY ITEM 12" INSERTION VALVE	1 EA		
0110	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM RAILROAD CONTRACTOR PROTECTIVE SERVICES	120 DAY		
STRUCTURE ITEMS						
0094	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (910405)	Lump Sum	L.S.	
0095	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0096	8112730000-N	450	PDA TESTING	1 EA		
0097	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (18+40.76 -L-)	Lump Sum	L.S.	
0098	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,850 SF		
0099	8161000000-E	420	GROOVING BRIDGE FLOORS	4,924 SF		
0100	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	110.3 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0101	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+40.76 -L-)	Lump Sum	L.S.	
0102	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,874 LB		
0103	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	197,100 LS		
0104	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP12X53)	14 EA		
0105	8364000000-E	450	HP 12 X 53 STEEL PILES	490 LF		
0106	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	291.7 LF		
0107	8531000000-E	462	4" SLOPE PROTECTION	190 SY		
0108	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

0848/Oct10/Q256237.5/D467813856000/E109

Total Amount Of Bid For Entire Project :