LOAD AND RESISTANCE FACTOR RATING (LRFD) SUMMARY FOR PRESTRESSED CONCRETE GIRDERS

LEVEL		VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING	MINIMUM RATING FACTORS (RF)	TONS = W X RF	STRENGTH I LIMIT STATE											SERVICE III LIMIT STATE						COMMENT NUMBER
								MOMENT					SHEAR						MOMENT					
							LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	LIVELOAD FACTORS	DISTRIBUTION FACTORS (DF)	RATING FACTOR	SPAN	GIRDER LOCATION	DISTANCE FROM LEFT END OF SPAN (ft)	
DESIGN LOAD RATING		HL-93(Inv)	N/A	1	2.42	--	1.75	0.370	2.42	25'	EL	12.5	0.400	2.98	25'	EL	22.2	0.80	0.370	3.30	25'	EL	12.5	
		HL-93(Opr)	N/A	--	3.14	--	1.35	0.370	3.14	25'	EL	12.5	0.400	3.86	25'	EL	22.2	N/A	--	--	--	--	--	
		HS-20(Inv)	36.000	2	3.62	130.32	1.75	0.370	3.62	25'	EL	9.5	0.400	3.44	25'	EL	22.2	0.80	0.370	4.94	25'	EL	9.5	
		HS-20(Opr)	36.000	--	4.70	169.20	1.35	0.370	4.70	25'	EL	9.5	0.400	4.46	25'	EL	22.2	N/A	--	--	--	--	--	
LEGAL LOAD RATING	SV	SNSH	13.500	--	6.69	90.31	1.4	0.370	6.69	25'	EL	12.5	0.400	7.94	25'	EL	22.2	0.80	0.370	7.29	25'	EL	9.5	
		SNGARBS2	20.000	--	6.26	125.20	1.4	0.370	6.26	25'	EL	12.5	0.400	6.38	25'	EL	22.2	0.80	0.370	6.82	25'	EL	12.5	
		SNAGRIS2	22.000	--	6.59	131.80	1.4	0.370	6.59	25'	EL	9.5	0.400	6.25	25'	EL	22.2	0.80	0.370	7.19	25'	EL	9.5	
		SNCOTTS3	27.250	--	3.43	93.47	1.4	0.370	3.43	25'	EL	12.5	0.400	4.01	25'	EL	22.2	0.80	0.370	3.74	25'	EL	12.5	
		SNAGGRS4	34.925	--	3.43	119.79	1.4	0.370	3.43	25'	EL	12.5	0.400	3.89	25'	EL	22.2	0.80	0.370	3.73	25'	EL	12.5	
		SNS5A	35.550	--	3.29	116.96	1.4	0.370	3.29	25'	EL	12.5	0.400	4.06	25'	EL	22.2	0.80	0.370	3.59	25'	EL	12.5	
		SNS6A	39.950	--	3.09	123.44	1.4	0.370	3.09	25'	EL	12.5	0.400	3.90	25'	EL	22.2	0.80	0.370	3.37	25'	EL	12.5	
		SNS7B	42.000	3	3.05	128.10	1.4	0.370	3.05	25'	EL	12.5	0.400	3.93	25'	EL	22.2	0.80	0.370	3.33	25'	EL	12.5	
	TTST	TNAGRIT3	33.000	--	4.30	141.90	1.4	0.370	4.30	25'	EL	12.5	0.400	4.79	25'	EL	22.2	0.80	0.370	4.68	25'	EL	12.5	
		TNT4A	33.075	--	3.78	125.02	1.4	0.370	3.78	25'	EL	12.5	0.400	4.35	25'	EL	22.2	0.80	0.370	4.12	25'	EL	12.5	
		TNT6A	41.600	--	3.55	147.68	1.4	0.370	3.55	25'	EL	12.5	0.400	4.08	25'	EL	22.2	0.80	0.370	3.86	25'	EL	12.5	
		TNT7A	42.000	--	3.66	153.72	1.4	0.370	3.66	25'	EL	12.5	0.400	4.07	25'	EL	22.2	0.80	0.370	3.99	25'	EL	12.5	
		TNT7B	42.000	--	3.32	139.44	1.4	0.370	3.32	25'	EL	9.5	0.400	3.92	25'	EL	22.2	0.80	0.370	3.62	25'	EL	12.5	
		TNAGRIT4	43.000	--	3.53	151.79	1.4	0.370	3.53	25'	EL	12.5	0.400	3.94	25'	EL	22.2	0.80	0.370	3.85	25'	EL	12.5	
		TNAGT5A	45.000	--	3.53	158.85	1.4	0.370	3.53	25'	EL	12.5	0.400	3.99	25'	EL	22.2	0.80	0.370	3.85	25'	EL	12.5	
		TNAGT5B	45.000	--	3.43	154.35	1.4	0.370	3.43	25'	EL	9.5	0.400	3.63	25'	EL	22.2	0.80	0.370	3.75	25'	EL	9.5	

LOAD FACTORS:

	LIMIT STATE	γ_{DC}	γ_{DW}
DESIGN LOAD RATING FACTORS	STRENGTH I	1.25	1.50
	SERVICE III	1.00	1.00

NOTES:

MINIMUM RATING FACTORS ARE BASED ON THE STRENGTH I AND SERVICE III LIMIT STATES.

ALLOWABLE STRESSES FOR SERVICE III LIMIT STATE ARE AS REQUIRED FOR DESIGN.

CONTROLLING LOAD RATING

(1) DESIGN LOAD RATING (HL-93)

(2) DESIGN LOAD RATING (HS-20)

(3) LEGAL LOAD RATING **

** SEE CHART FOR VEHICLE TYPE

GIRDER LOCATION

I - INTERIOR GIRDER
EL - EXTERIOR LEFT GIRDER
ER - EXTERIOR RIGHT GIRDER

LRFR SUMMARY

FOR SPAN 'C'

PROJECT NO. 17BP.5.R.77

WARREN COUNTY

STATION: 15+02.50 -L-

SHEET 2 OF 2

DocuSigned by: David Ruggles C46276B0F412422... 7/17/2018

NORTH CAROLINA PROFESSIONAL SEAL 11725 ENGINEER DAVID R. RUGGLES

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

Firm License No. C-1051
421 Fayetteville St,
Suite 400
Raleigh, NC 27601
T 919.380.8750
www.stewartinc.com

STEWART

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

LRFR SUMMARY FOR 25' CORED SLAB UNIT 90° SKEW

(NON-INTERSTATE TRAFFIC)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	S-5
1			3			TOTAL SHEETS
2			4			22

DRAWN BY:	E. PHELPS	DATE :	2/18
CHECKED BY:	J. LOFTUS	DATE :	2/18
DESIGN ENGINEER OF RECORD:	J. LOFTUS	DATE :	2/18

WARREN 77
6/29/2018
...\400_005_920077_SMU_LRFR02.dgn
USER:ephelps