be measured vertically to the nearest 0.1 foot. Such payment includes, but is not limited to, excavation, backfilling, fabrication and welding associated with the extra depth.

Payment will be made under:

Pay ItemPay UnitExtra Length Guardrail Posts (8' Steel)Each

Extra Length Guardran 1 0sts (6 Steet)

ATTACH STEEL BEAM GUARDRAIL TO EXISTING

Where guardrail is required to be mounted to an existing structure, the Contractor shall install said guardrail according to the attached special drawings and in accordance with Section 862 of the Standard Specifications.

Payment for this item will include providing the plates (front, and or, back plate), attaching the guardrail to the anchor plate, anchoring the plate to the structure and providing any necessary hardware.

Payment will be made under:

Pay Item Pay Unit

Generic Guardrail Item: Attach Steel Beam Guardrail to Existing Each

TEMPORARY TRAFFIC CONTROL DEVICES:

(1-17-12) 1105 SP11 R05

Revise the 2018 Standard Specifications as follows:

Page 11-5, Article 1105-6 Measurement and Payment, add the following paragraph after line 27:

Partial payments will be made on each payment estimate based on the following: 50% of the contract lump sum price bid will be paid on the first monthly estimate and the remaining 50% of the contract lump sum price bid will be paid on each subsequent estimate based on the percent of the project completed.

WORK ZONE INSTALLER:

(7-20-21) 1101, 1150 SP11 R04

Provide the service of at least one qualified work zone installer during the setup, installation, and removal of temporary traffic control within the highway right of way. The qualified work zone installer shall serve as crew leader and shall be on site and directing the installation and removal of temporary traffic control. If multiple temporary traffic control installations or removals are occurring simultaneously, then each shall have a qualified work zone installer.

The work zone installer shall be qualified by an NCDOT approved training agency in the safe and competent set up of temporary traffic control. For a complete listing of approved training agencies,