County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
			ROADWAY ITEMS			
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	280 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	200 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	1,055 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	33 TON		
0011	0321000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	90 SY		
0012	0448000000-E	310	****" RC PIPE CULVERTS, CLASS IV (48")	60 LF		
0013	0448000000-E	310	****" RC PIPE CULVERTS, CLASS IV (54")	80 LF		
0014	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	24 LF		
0015	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	36 LF		
0016	0636000000-E	310	**" CS PIPE ELBOWS, *****" THICK (15", 0.064")	4 EA		
0017	1099500000-E	505	SHALLOW UNDERCUT	200 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	400 TON		
0019	1112000000-E	505	GEOTEXTILE FOR SUBGRADE STABILIZATION	600 SY		
0020	1220000000-E	545	INCIDENTAL STONE BASE	108 TON		
0021	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.3 SMI		
0022	1260000000-E	SP	AGGREGATE SHOULDER BORROW	305 TON		
0023	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***" DEPTH (1.5")	14,804 SY		
0024	1330000000-E	607	INCIDENTAL MILLING	1,812 SY		
0025	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	690 TON		
0026	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	670 TON		
0027	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3,724 TON		
0028	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	289 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0030	1704000000-E	SP	PATCHING EXISTING PAVEMENT	50 TON		
0031	2000000000-N	806	RIGHT-OF-WAY MARKERS	4 EA		
0032	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0033	2026000000-E	815	GEOTEXTILE FOR SUBSURFACE DRAINS	100 SY		
0034	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	16.8 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0036	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0037	2077000000-E	815	6" OUTLET PIPE	6 LF		
0038	2220000000-E	838	REINFORCED ENDWALLS	19.8 CY		
0039	2253000000-E	840	PIPE COLLARS	0.893 CY		
0040	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0041	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	27.4 CY		
0042	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	2 EA		
0043	2556000000-E	846	SHOULDER BERM GUTTER	230 LF		
0044	3030000000-E	862	STEEL BEAM GUARDRAIL	812.5 LF		
0045	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	37.5 LF		
0046	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0047	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0048	3287000000-N	862	GUARDRAIL END UNITS, TYPE TL-3	3 EA		
0049	3380000000-E	862	TEMPORARY STEEL BEAM GUARDRAIL	125 LF		
0050	3382000000-E	862	TEMPORARY STEEL BEAM GUARDRAIL, SHOP CURVED	37.5 LF		
0051	3389150000-N	862	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (AT-1)	1 EA		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	3389150000-N	862	TEMPORARY GUARDRAIL END UNITS, TYPE ***** (TL-3)	1 EA		
0053	3389160000-N	862	TEMPORARY ADDITIONAL GUARDRAIL POSTS	5 EA		
0054	3628000000-E	876	RIP RAP, CLASS I	150 TON		
0055	3635000000-E	876	RIP RAP, CLASS II	80 TON		
0056	3649000000-E	876	RIP RAP, CLASS B	50 TON		
0057	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,075 SY		
0058	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	68.5 LF		
0059	4102000000-N	904	SIGN ERECTION, TYPE E	5 EA		
0060	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4 EA		
0061	4413000000-E	SP	WORK ZONE ADVANCE/GENERAL WARNING SIGNING	117 SF		
0062	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0063	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0064	4485000000-E	1170	PORTABLE CONCRETE BARRIER	440 LF		
0065	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	6,733 LF		
0066	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	58,615 LF		
0067	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	1,209 LF		
0068	4709000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	144 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	22 EA		
0070	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,389 LF		
0071	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,800 LF		
0072	4865000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (12")	65 LF		
0073	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM POLYCARBONATE H-SHAPED MARKERS	164 EA		
0074	5325800000-E	1510	8" WATER LINE	60 LF		
0075	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	700 LB		
0076	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0077	5686500000-E	1515	WATER SERVICE LINE	28 LF		
0078	5801000000-E	1530	ABANDON 8" UTILITY PIPE	50 LF		
0079	6000000000-E	1605	TEMPORARY SILT FENCE	2,230 LF		
0080	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		
0081	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	380 TON		
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	305 TON		
0083	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0084	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0085	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2 TON		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0087	6029000000-E	SP	SAFETY FENCE	1,520 LF		
0088	6030000000-E	1630	SILT EXCAVATION	1,140 CY		
0089	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400 SY		
0090	6037000000-E	1629	COIR FIBER MAT	100 SY		
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	310 LF		
0092	6043000000-E	1644	LOW PERMEABILITY GEOTEXTILE	100 SY		
0093	6045000000-E	SP	**" TEMPORARY PIPE (18")	210 LF		
0094	6070000000-N	1639	SPECIAL STILLING BASINS	6 EA		
0095	6071002000-E	1642	FLOCCULANT	115 LB		
0096	6071030000-E	1640	COIR FIBER BAFFLE	205 LF		
0097	6071050000-E	1644	**" SKIMMER (1.5")	3 EA		
0098	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0099	6087000000-E	1660	MOWING	3 ACR		
0100	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0101	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0102	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0104	6111000000-E	SP	IMPERVIOUS DIKE	105 LF		
0105	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0106	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	25 EA		
0107	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0108	6123000000-E	1670	REFORESTATION	0.1 ACR		
0109	6132000000-N	SP	GENERIC EROSION CONTROL ITEM PREFABRICATED CONCRETE WASHOUT	3 EA		
0110	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	792 LF		

0748/Oct22/Q116061.193/D394875042000/E110 **Total Amount Of Bid For Entire Project :**