2027CPT.05.01.10921, 49367.3.10

TIP NO HL-0008O 2.497 MILES

FED AID NO STATE FUNDED
PAVING, GRADING, DRAINAGE
NC 42 AT SR 2735 (JOHNSTON RD)

							S T WOOTEN CORPORATION WILSON, NC		FSC II LLC DBA FRED SMITH COMPANY RALEIGH, NC		CARDINAL CIVIL CONTRACTING LLC RALEIGH, NC
			ROADWAY ITEMS								
0001	0000100000-N	800	MOBILIZATION	Lump Sum			65,750.00		150,000.00		255,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			23,569.55		22,305.00		32,000.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1	ACR	8,500.00	8,500.00	1.00	1.00	1.00	1.00
0004	0043000000-N	226	GRADING (226)	Lump Sum			317,000.39		830,000.00		840,000.00
0005	0057000000-E	226	UNDERCUT EXCAVATION	200	CY	24.00	4,800.00	40.00	8,000.00	78.73	15,746.00
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	280	CY	15.00	4,200.00	28.00	7,840.00	53.00	14,840.00
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200	CY	22.00	4,400.00	32.00	6,400.00	89.38	17,876.00
0008	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	200	SY	6.00	1,200.00	4.00	800.00	4.55	910.00
0009	0199000000-E	SP	TEMPORARY SHORING	1,055	SF	75.00	79,125.00	40.00	42,200.00	116.00	122,380.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	33	TON	65.00	2,145.00	100.00	3,300.00	57.00	1,881.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	90	SY	50.00	4,500.00	10.00	900.00	15.40	1,386.00
0012	0448000000-E	310	***" RCP CULV CLASS IV (48")	60	LF	415.00	24,900.00	390.00	23,400.00	460.00	27,600.00
0013	0448000000-E	310	***" RCP CULV CLASS IV (54")	80	LF	765.00	61,200.00	670.00	53,600.00	480.00	38,400.00
0014	0448300000-E	310	18" RCP CULV CLASS IV	24	LF	3,540.00	84,960.00	198.00	4,752.00	212.00	5,088.00
0015	0582000000-E	310	15" CS PIPE CULV 0.064"	36	LF	250.00	9,000.00	127.00	4,572.00	261.00	9,396.00
0016	0636000000-E	310	**" CS ELBOW *****" THICK (15", 0.064")	4	EA	1,000.00	4,000.00	300.00	1,200.00	1,900.00	7,600.00
0017	1099500000-E	505	SHALLOW UNDERCUT	200	CY	25.50	5,100.00	44.00	8,800.00	96.55	19,310.00
0018	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	400	TON	30.00	12,000.00	50.00	20,000.00	54.66	21,864.00
0019	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	600	SY	6.00	3,600.00	4.00	2,400.00	3.75	2,250.00
0020	1220000000-E	545	INCIDENTAL STONE BASE	108	TON	50.00	5,400.00	82.00	8,856.00	93.00	10,044.00
0021	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.3	SMI	6,725.00	22,192.50	5,100.00	16,830.00	10,000.00	33,000.00
0022	1260000000-E	SP	AGGREGATE SHOULDER BORROW	305	TON	32.45	9,897.25	55.00	16,775.00	76.00	23,180.00
0023	1297000000-E	607	MILL ASP PVMT *****" DTH (1.5")	14,804	SY	1.20	17,764.80	2.25	33,309.00	4.50	66,618.00
0024	1330000000-E	607	INCIDENTAL MILLING	1,812	SY	4.95	8,969.40	11.50	20,838.00	8.75	15,855.00
0025	1491000000-E	610	ASP CONC BASE CRS B25.0C	690	TON	109.25	75,382.50	140.00	96,600.00	144.00	99,360.00
0026	1503000000-E	610	ASP CONC INTR CRS I19.0C	670	TON	110.25	73,867.50	140.00	93,800.00	133.00	89,110.00
0027	1523000000-E	610	ASP CONC SURF CRS S9.5C	3,724	TON	87.00	323,988.00	88.00	327,712.00	71.00	264,404.00
0028	1575000000-E	620	ASP FOR PLANT MIX	289	TON	865.00	249,985.00	850.00	245,650.00	825.00	238,425.00
0029	1693000000-E	654	ASPH PLT MIX PVMT REPAIR	25	TON	174.00	4,350.00	185.00	4,625.00	259.20	6,480.00
0030	1704000000-E	SP	PATCHING EXIST PAVEMENT	50	TON	174.00	8,700.00	400.00	20,000.00	259.20	12,960.00
0031	2000000000-N	806	RIGHT-OF-WAY MARKERS	4	EA	318.39	1,273.56	650.00	2,600.00	330.00	1,320.00
0032	2022000000-E	815	SUBDRAIN EXCAVATION	22.4	CY	35.00	784.00	40.00	896.00	62.50	1,400.00
0033	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	100	SY	10.00	1,000.00	5.00	500.00	8.59	859.00
0034	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	16.8	CY	75.00	1,260.00	60.00	1,008.00	160.00	2,688.00
0035	2044000000-E	815	6" PERF SUBDRN PIPE	100	LF	16.00	1,600.00	8.00	800.00	25.93	2,593.00
0036	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	400.00	400.00	650.00	650.00	565.00	565.00
0037	2077000000-E	815	6" OUTLET PIPE	6	LF	35.00	210.00	45.00	270.00	87.00	522.00
0038	2220000000-E	838	REINFORCED ENDWALLS	19.8	CY	2,500.00	49,500.00	4,650.00	92,070.00	1,595.00	31,581.00

						S T WOOTEN CORPORATION WILSON, NC		FSC II LLC DBA FRED SMITH COMPANY RALEIGH, NC		CARDINAL CIVIL CONTRACTING LLC RALEIGH, NC	
0039	2253000000-E	840	PIPE COLLARS	0.893	CY	5,581.19	4,984.00	4,000.00	3,572.00	3,807.39	3,400.00
0040	2286000000-N	840	MASNRY DRAINAGE STRUCT	2	EA	5,000.00	10,000.00	5,000.00	10,000.00	3,225.00	6,450.00
0041	2297000000-E	840	MASNRY DRAINAGE STRUCT	27.4	CY	2,609.48	71,499.75	5,500.00	150,700.00	1,800.00	49,320.00
0042	2364200000-N	840	FRAME W/2GRTS 840.20 STD	2	EA	1,168.18	2,336.36	1,750.00	3,500.00	2,300.00	4,600.00
0043	2556000000-E	846	SHOULDER BERM GUTTER	230	LF	59.25	13,627.50	60.00	13,800.00	46.00	10,580.00
0044	3030000000-E	862	STL BEAM GUARDRAIL	812.5	LF	28.00	22,750.00	28.00	22,750.00	29.00	23,562.50
0045	3045000000-E	862	SBGR SHOP CURVED	37.5	LF	30.00	1,125.00	30.00	1,125.00	31.00	1,162.50
0046	3150000000-N	862	ADDIT GUARDRAIL POSTS	10	EA	11.00	110.00	11.00	110.00	11.50	115.00
0047	3195000000-N	862	GR END TYPE AT-1	1	EA	1,100.00	1,100.00	1,100.00	1,100.00	1,150.00	1,150.00
0048	3287000000-N	862	GR END TYPE TL-3	3	EA	3,300.00	9,900.00	3,300.00	9,900.00	3,400.00	10,200.00
0049	3380000000-E	862	TEMP STL BM GUARDRAIL	125	LF	10.00	1,250.00	10.00	1,250.00	10.20	1,275.00
0050	3382000000-E	862	TEMP STL BM GDRAIL, SHP CURV	37.5	LF	15.00	562.50	15.00	562.50	16.00	600.00
0051	3389150000-N	862	TEMP GDRL END UNITS ***** (AT-1)	1	EA	500.00	500.00	500.00	500.00	515.00	515.00
0052	3389150000-N	862	TEMP GDRL END UNITS ***** (TL-3)	1	EA	1,800.00	1,800.00	1,800.00	1,800.00	1,855.00	1,855.00
0053	3389160000-N	862	TEMP ADDIT GDRL POST	5	EA	1.00	5.00	1.00	5.00	2.00	10.00
0054	3628000000-E	876	RIP RAP, CLASS I	150	TON	56.00	8,400.00	135.00	20,250.00	106.00	15,900.00
0055	3635000000-E	876	RIP RAP, CLASS II	80	TON	60.00	4,800.00	135.00	10,800.00	117.00	9,360.00
0056	3649000000-E	876	RIP RAP, CLASS B	50	TON	52.00	2,600.00	135.00	6,750.00	126.00	6,300.00
0057	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,075	SY	6.00	6,450.00	2.00	2,150.00	6.40	6,880.00
0058	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	68.5	LF	9.00	616.50	8.00	548.00	8.00	548.00
0059	4102000000-N	904	SIGN ERECTION, TYPE E	5	EA	295.00	1,475.00	325.00	1,625.00	567.00	2,835.00
0060	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	4	EA	10.00	40.00	10.00	40.00	6.00	24.00
0061	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	117	SF	21.00	2,457.00	20.00	2,340.00	13.00	1,521.00
0062	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum			212,000.00		288,100.00		385,000.00
0063	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	4,500.00	9,000.00	11,500.00	23,000.00	4,600.00	9,200.00
0064	4485000000-E	1170	PORT CONC BARRIER	440	LF	35.00	15,400.00	70.00	30,800.00	36.00	15,840.00
0065	4685000000-E	1205	THERMO PVT MKG LINES 4"90	6,733	LF	0.70	4,713.10	0.70	4,713.10	0.70	4,713.10
0066	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	58,615	LF	0.76	44,547.40	0.76	44,547.40	0.80	46,892.00
0067	4700000000-E	1205	12"WIDE THERMO 90 MILS	1,209	LF	3.00	3,627.00	3.00	3,627.00	3.00	3,627.00
0068	4709000000-E	1205	24"WIDE THERMO 90 MILS	144	LF	14.00	2,016.00	14.00	2,016.00	14.00	2,016.00
0069	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	22	EA	115.00	2,530.00	115.00	2,530.00	115.00	2,530.00
0070	4810000000-E	1205	PAINT PVMT MARKINGS 4"	6,389	LF	0.60	3,833.40	0.60	3,833.40	0.60	3,833.40
0071	4850000000-E	1205	LINE REMOVAL 4" WIDE	1,800	LF	2.50	4,500.00	2.50	4,500.00	2.60	4,680.00
0072	4865000000-E	1205	LINE REMOVAL 12" WIDE	65	LF	6.00	390.00	6.00	390.00	6.50	422.50
0073	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM (EA) POLYCARBONATE H-SHAPED MARKERS	164	EA	72.00	11,808.00	72.00	11,808.00	75.00	12,300.00
0074	5325800000-E	1510	8" WATER LINE	60	LF	150.00	9,000.00	275.00	16,500.00	116.05	6,963.00
0075	5329000000-E	1510	DI H2O PIPE FITTINGS	700	LB	8.00	5,600.00	20.00	14,000.00	17.43	12,201.00
0076	5648000000-N	1515	RELOCATE WATER METER	1	EA	1,500.00	1,500.00	3,300.00	3,300.00	3,130.00	3,130.00
0077	5686500000-E	1515	WATER SERVICE LINE (<2")	28	LF	82.38	2,306.64	64.00	1,792.00	94.00	2,632.00

2027CPT.05.01.10921, 49367.3.10

TIP NO HL-0008O 2.497 MILES

FED AID NO STATE FUNDED
PAVING, GRADING, DRAINAGE
NC 42 AT SR 2735 (JOHNSTON RD)

						S T WOOTEN CORPORATION WILSON, NC		FSC II LLC DBA FRED SMITH COMPANY RALEIGH, NC		CARDINAL CIVIL CONTRACTING LLC RALEIGH, NC	
0078	5801000000-E	1530	ABANDON 8" UTILITY PIPE	50	LF	30.00	1,500.00	40.00	2,000.00	150.00	7,500.00
0079	6000000000-E	1605	TEMPORARY SILT FENCE	2,230	LF	2.80	6,244.00	2.50	5,575.00	2.70	6,021.00
0080	6006000000-E	1610	EROS CONTRL STONE CL A	105	TON	50.00	5,250.00	25.00	2,625.00	61.20	6,426.00
0081	6009000000-E	1610	EROS CONTRL STONE CL B	380	TON	52.00	19,760.00	14.00	5,320.00	63.00	23,940.00
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	305	TON	43.00	13,115.00	13.00	3,965.00	53.00	16,165.00
0083	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	2,100.00	4,200.00	450.00	900.00	2,000.00	4,000.00
0084	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	2.00	400.00	2.00	400.00	2.00	400.00
0085	6021000000-E	1620	FERT FOR TEMP SEEDING	2	TON	400.00	800.00	395.00	790.00	1,100.00	2,200.00
0086	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	18.00	3,600.00	1.00	200.00	32.08	6,416.00
0087	6029000000-E	SP	SAFETY FENCE	1,520	LF	1.90	2,888.00	1.85	2,812.00	3.00	4,560.00
0088	6030000000-E	1630	SILT EXCAVATION	1,140	CY	23.11	26,345.40	1.00	1,140.00	39.50	45,030.00
0089	6036000000-E	1631	MATTING FOR EROS CONTROL	2,400	SY	1.85	4,440.00	2.50	6,000.00	2.15	5,160.00
0090	6037000000-E	1629	COIR FIBER MAT	100	SY	5.75	575.00	5.00	500.00	4.71	471.00
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	310	LF	6.00	1,860.00	3.50	1,085.00	4.00	1,240.00
0092	6043000000-E	1644	LOW PERMEABILITY GEOTEXTILE	100	SY	6.00	600.00	20.00	2,000.00	17.80	1,780.00
0093	6045000000-E	SP	**" TEMPORARY PIPE (18")	210	LF	50.00	10,500.00	150.00	31,500.00	81.00	17,010.00
0094	6070000000-N	1639	SPECIAL STILLING BASINS	6	EA	1,500.00	9,000.00	400.00	2,400.00	15,000.00	90,000.00
0095	6071002000-E	1642	FLOCCULANT	115	LB	12.00	1,380.00	4.00	460.00	25.00	2,875.00
0096	6071030000-E	1640	COIR FIBER BAFFLE	205	LF	6.50	1,332.50	4.00	820.00	9.00	1,845.00
0097	6071050000-E	1644	**" SKIMMER (1.5")	3	EA	3,950.00	11,850.00	3,000.00	9,000.00	3,055.00	9,165.00
0098	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	3,000.00	9,000.00	1,500.00	4,500.00	5,100.00	15,300.00
0099	6087000000-E	1660	MOWING	3	ACR	175.00	525.00	150.00	450.00	295.00	885.00
0100	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	5.00	250.00	6.00	300.00	5.00	250.00
0101	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	600.00	150.00	1,000.00	250.00	1,100.00	275.00
0102	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	5.00	250.00	6.00	300.00	5.50	275.00
0103	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	600.00	750.00	1,000.00	1,250.00	1,160.00	1,450.00
0104	6111000000-E	SP	IMPERVIOUS DIKE	105	LF	80.00	8,400.00	150.00	15,750.00	120.80	12,684.00
0105	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	60.00	600.00	125.00	1,250.00	78.00	780.00
0106	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	350.00	8,750.00	10.00	250.00	103.00	2,575.00
0107	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,300.00	1,300.00	1,500.00	1,500.00	1,335.00	1,335.00
0108	6123000000-E	1670	REFORESTATION	0.1	ACR	5,700.00	570.00	15,500.00	1,550.00	2,000.00	200.00
0109	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	3	EA	1,300.00	3,900.00	1,250.00	3,750.00	270.00	810.00
0110	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	792	LF	15.00	11,880.00	15.50	12,276.00	15.50	12,276.00
			CONTRACT TOTAL			TOTAL	2,249,599.50	TOTAL	3,017,761.40	TOTAL	3,309,934.00
			ROADWAY ITEMS			SUB-TOTAL	2,249,599.50	SUB-TOTAL	3,017,761.40	SUB-TOTAL	3,309,934.00

2027CPT.05.01.10921, 49367.3.10

TIP NO HL-0008O 2.497 MILES

FED AID NO STATE FUNDED
PAVING, GRADING, DRAINAGE
NC 42 AT SR 2735 (JOHNSTON RD)

PRECISION PIPELINE LLC
EAU CLAIRE, WI

			ROADWAY ITEMS				
0001	0000100000-N	800	MOBILIZATION	Lump Sum			100,000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum			25,000.00
0003	0008000000-E	200	SUPP CLEARING & GRUBBING	1	ACR	15,000.00	15,000.00
0004	0043000000-N	226	GRADING (226)	Lump Sum			247,928.05
0005	0057000000-E	226	UNDERCUT EXCAVATION	200	CY	65.00	13,000.00
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	280	CY	80.00	22,400.00
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200	CY	90.00	18,000.00
0008	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	200	SY	6.00	1,200.00
0009	0199000000-E	SP	TEMPORARY SHORING	1,055	SF	125.00	131,875.00
0010	0318000000-E	300	FND CONDIT MATL MINOR STRS	33	TON	90.00	2,970.00
0011	0321000000-E	300	FND CONDIT GEOTEXTILE (4A)	90	SY	6.00	540.00
0012	0448000000-E	310	***" RCP CULV CLASS IV (48")	60	LF	700.00	42,000.00
0013	0448000000-E	310	***" RCP CULV CLASS IV (54")	80	LF	700.00	56,000.00
0014	0448300000-E	310	18" RCP CULV CLASS IV	24	LF	250.00	6,000.00
0015	0582000000-E	310	15" CS PIPE CULV 0.064"	36	LF	175.00	6,300.00
0016	0636000000-E	310	**" CS ELBOW *****" THICK (15", 0.064")	4	EA	500.00	2,000.00
0017	1099500000-E	505	SHALLOW UNDERCUT	200	CY	65.00	13,000.00
0018	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	400	TON	90.00	36,000.00
0019	1112000000-E	505	GEOTEXTILE SUBGRADE STAB	600	SY	6.00	3,600.00
0020	1220000000-E	545	INCIDENTAL STONE BASE	108	TON	90.00	9,720.00
0021	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.3	SMI	6,500.00	21,450.00
0022	1260000000-E	SP	AGGREGATE SHOULDER BORROW	305	TON	90.00	27,450.00
0023	1297000000-E	607	MILL ASP PVMT *****" DTH (1.5")	14,804	SY	3.00	44,412.00
0024	1330000000-E	607	INCIDENTAL MILLING	1,812	SY	9.00	16,308.00
0025	1491000000-E	610	ASP CONC BASE CRS B25.0C	690	TON	225.00	155,250.00
0026	1503000000-E	610	ASP CONC INTR CRS I19.0C	670	TON	225.00	150,750.00
0027	1523000000-E	610	ASP CONC SURF CRS S9.5C	3,724	TON	280.00	1,042,720.00
0028	1575000000-E	620	ASP FOR PLANT MIX	289	TON	1,200.00	346,800.00
0029	1693000000-E	654	ASPH PLT MIX PVMT REPAIR	25	TON	175.00	4,375.00
0030	1704000000-E	SP	PATCHING EXIST PAVEMENT	50	TON	175.00	8,750.00
0031	2000000000-N	806	RIGHT-OF-WAY MARKERS	4	EA	250.00	1,000.00
0032	2022000000-E	815	SUBDRAIN EXCAVATION	22.4	CY	65.00	1,456.00
0033	2026000000-E	815	GEOTEXTILE FOR SUBSURF DRNS	100	SY	6.00	600.00
0034	2036000000-E	815	SUBDRAIN COARSE AGGREGATE	16.8	CY	90.00	1,512.00
0035	2044000000-E	815	6" PERF SUBDRN PIPE	100	LF	80.00	8,000.00
0036	2070000000-N	815	SUBDRN PIPE OUTLET	1	EA	250.00	250.00
0037	2077000000-E	815	6" OUTLET PIPE	6	LF	20.00	120.00
0038	2220000000-E	838	REINFORCED ENDWALLS	19.8	CY	3,000.00	59,400.00
0039	2253000000-E	840	PIPE COLLARS	0.893	CY	1,500.00	1,339.50

2027CPT.05.01.10921, 49367.3.10

TIP NO HL-0008O 2.497 MILES

FED AID NO STATE FUNDED
PAVING, GRADING, DRAINAGE
NC 42 AT SR 2735 (JOHNSTON RD)

PRECISION PIPELINE LLC
EAU CLAIRE, WI

0040	2286000000-N	840	MASNRY DRAINAGE STRUCT	2	EA	6,000.00	12,000.00
0041	2297000000-E	840	MASNRY DRAINAGE STRUCT	27.4	CY	3,000.00	82,200.00
0042	2364200000-N	840	FRAME W/2GRTS 840.20 STD	2	EA	3,500.00	7,000.00
0043	2556000000-E	846	SHOULDER BERM GUTTER	230	LF	90.00	20,700.00
0044	3030000000-E	862	STL BEAM GUARDRAIL	812.5	LF	45.00	36,562.50
0045	3045000000-E	862	SBGR SHOP CURVED	37.5	LF	85.00	3,187.50
0046	3150000000-N	862	ADDIT GUARDRAIL POSTS	10	EA	90.00	900.00
0047	3195000000-N	862	GR END TYPE AT-1	1	EA	3,000.00	3,000.00
0048	3287000000-N	862	GR END TYPE TL-3	3	EA	15,000.00	45,000.00
0049	3380000000-E	862	TEMP STL BM GUARDRAIL	125	LF	30.00	3,750.00
0050	3382000000-E	862	TEMP STL BM GDRAIL, SHP CURV	37.5	LF	75.00	2,812.50
0051	3389150000-N	862	TEMP GDRL END UNITS ***** (AT-1)	1	EA	2,000.00	2,000.00
0052	3389150000-N	862	TEMP GDRL END UNITS ***** (TL-3)	1	EA	12,000.00	12,000.00
0053	3389160000-N	862	TEMP ADDIT GDRL POST	5	EA	70.00	350.00
0054	3628000000-E	876	RIP RAP, CLASS I	150	TON	90.00	13,500.00
0055	3635000000-E	876	RIP RAP, CLASS II	80	TON	90.00	7,200.00
0056	3649000000-E	876	RIP RAP, CLASS B	50	TON	90.00	4,500.00
0057	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	1,075	SY	6.00	6,450.00
0058	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	68.5	LF	20.00	1,370.00
0059	4102000000-N	904	SIGN ERECTION, TYPE E	5	EA	150.00	750.00
0060	4155000000-N	907	DISPOSE SIGN SYST U-CHAN	4	EA	50.00	200.00
0061	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	117	SF	15.00	1,755.00
0062	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum			35,000.00
0063	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	10,000.00	20,000.00
0064	4485000000-E	1170	PORT CONC BARRIER	440	LF	150.00	66,000.00
0065	4685000000-E	1205	THERMO PVT MKG LINES 4"90	6,733	LF	2.50	16,832.50
0066	4688000000-E	1205	THERMO PVT MKG LINES,6"90 MILS	58,615	LF	1.50	87,922.50
0067	4700000000-E	1205	12"WIDE THERMO 90 MILS	1,209	LF	5.00	6,045.00
0068	4709000000-E	1205	24"WIDE THERMO 90 MILS	144	LF	25.00	3,600.00
0069	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	22	EA	250.00	5,500.00
0070	4810000000-E	1205	PAINT PVMT MARKINGS 4"	6,389	LF	1.50	9,583.50
0071	4850000000-E	1205	LINE REMOVAL 4" WIDE	1,800	LF	4.00	7,200.00
0072	4865000000-E	1205	LINE REMOVAL 12" WIDE	65	LF	10.00	650.00
0073	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM (EA) POLYCARBONATE H-SHAPED MARKERS	164	EA	125.00	20,500.00
0074	5325800000-E	1510	8" WATER LINE	60	LF	350.00	21,000.00
0075	5329000000-E	1510	DI H2O PIPE FITTINGS	700	LB	8.00	5,600.00
0076	5648000000-N	1515	RELOCATE WATER METER	1	EA	5,000.00	5,000.00
0077	5686500000-E	1515	WATER SERVICE LINE (<2")	28	LF	500.00	14,000.00
0078	5801000000-E	1530	ABANDON 8" UTILITY PIPE	50	LF	125.00	6,250.00
0079	6000000000-E	1605	TEMPORARY SILT FENCE	2,230	LF	9.00	20,070.00

2027CPT.05.01.10921, 49367.3.10

TIP NO HL-0008O 2.497 MILES

FED AID NO STATE FUNDED
PAVING, GRADING, DRAINAGE
NC 42 AT SR 2735 (JOHNSTON RD)

PRECISION PIPELINE LLC
EAU CLAIRE, WI

0080	6006000000-E	1610	EROS CONTRL STONE CL A	105	TON	90.00	9,450.00
0081	6009000000-E	1610	EROS CONTRL STONE CL B	380	TON	90.00	34,200.00
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	305	TON	90.00	27,450.00
0083	6015000000-E	1615	TEMPORARY MULCHING	2	ACR	4,000.00	8,000.00
0084	6018000000-E	1620	SEED FOR TEMP SEEDING	200	LB	3.00	600.00
0085	6021000000-E	1620	FERT FOR TEMP SEEDING	2	TON	1,200.00	2,400.00
0086	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	65.00	13,000.00
0087	6029000000-E	SP	SAFETY FENCE	1,520	LF	9.00	13,680.00
0088	6030000000-E	1630	SILT EXCAVATION	1,140	CY	15.00	17,100.00
0089	6036000000-E	1631	MATTING FOR EROS CONTROL	2,400	SY	6.00	14,400.00
0090	6037000000-E	1629	COIR FIBER MAT	100	SY	25.00	2,500.00
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	310	LF	6.00	1,860.00
0092	6043000000-E	1644	LOW PERMEABILITY GEOTEXTILE	100	SY	9.00	900.00
0093	6045000000-E	SP	**" TEMPORARY PIPE (18")	210	LF	45.00	9,450.00
0094	6070000000-N	1639	SPECIAL STILLING BASINS	6	EA	1,500.00	9,000.00
0095	6071002000-E	1642	FLOCCULANT	115	LB	15.00	1,725.00
0096	6071030000-E	1640	COIR FIBER BAFFLE	205	LF	9.00	1,845.00
0097	6071050000-E	1644	**" SKIMMER (1.5")	3	EA	1,500.00	4,500.00
0098	6084000000-E	1660	SEEDING AND MULCHING	3	ACR	4,500.00	13,500.00
0099	6087000000-E	1660	MOWING	3	ACR	150.00	450.00
0100	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	4.00	200.00
0101	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.25	TON	1,200.00	300.00
0102	6096000000-E	1662	SEED FOR SUPP SEEDING	50	LB	4.00	200.00
0103	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	1,200.00	1,500.00
0104	6111000000-E	SP	IMPERVIOUS DIKE	105	LF	150.00	15,750.00
0105	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	150.00	1,500.00
0106	6117000000-N	1675	RESPONSE FOR EROS CONTROL	25	EA	150.00	3,750.00
0107	6117500000-N	SP	CONC WASHOUT STRUCTURE	1	EA	1,500.00	1,500.00
0108	6123000000-E	1670	REFORESTATION	0.1	ACR	5,000.00	500.00
0109	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) PREFABRICATED CONCRETE WASHOUT	3	EA	1,500.00	4,500.00
0110	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	792	LF	30.00	23,760.00

CONTRACT TOTAL TOTAL 3,501,886.55

ROADWAY ITEMS SUB-TOTAL 3,501,886.55

2027CPT.05.01.10921, 49367.3.10

TIP NO HL-0008O 2.497 MILES

FED AID NO STATE FUNDED
PAVING, GRADING, DRAINAGE
NC 42 AT SR 2735 (JOHNSTON RD)

BIDDERS IN ORDER		CONTRACT TOTAL
S T WOOTEN CORPORATION	1	2,249,599.50
FSC II LLC DBA FRED SMITH COMPANY	2	3,017,761.40
CARDINAL CIVIL CONTRACTING LLC	3	3,309,934.00
PRECISION PIPELINE LLC	4	3,501,886.55