

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	200 CY		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	100 SY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	239 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	1,104 SY		
0009	0335400000-E	305	24" DRAINAGE PIPE	108 LF		
0010	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (72")	96 LF		
0011	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	72 LF		
0012	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	160 LF		
0013	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	192 LF		
0014	0448600000-E	310	36" RC PIPE CULVERTS, CLASS IV	36 LF		
0015	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (30", 0.375")	52 LF		
0016	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (36", 0.375")	92 LF		
0017	0973100000-E	330	*** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (72", 0.375")	64 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0995000000-E	340	PIPE REMOVAL	178 LF		
0019	1099500000-E	505	SHALLOW UNDERCUT	150 CY		
0020	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	300 TON		
0021	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0022	1260000000-E	SP	AGGREGATE SHOULDER BORROW	48 TON		
0023	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1.5)	1,810 SY		
0024	1330000000-E	607	INCIDENTAL MILLING	280 SY		
0025	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,155 TON		
0026	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	480 TON		
0027	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,870 TON		
0028	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	290 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0030	2209000000-E	838	ENDWALLS	3.4 CY		
0031	2220000000-E	838	REINFORCED ENDWALLS	7.1 CY		
0032	2253000000-E	840	PIPE COLLARS	6.26 CY		
0033	2275000000-E	SP	FLOWABLE FILL	66 CY		
0034	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	9.8 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	2612000000-E	848	6" CONCRETE DRIVEWAY	40 SY		
0036	3030000000-E	862	STEEL BEAM GUARDRAIL	887.5 LF		
0037	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	50 LF		
0038	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0039	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0040	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	3 EA		
0041	3628000000-E	876	RIP RAP, CLASS I	410 TON		
0042	3635000000-E	876	RIP RAP, CLASS II	187 TON		
0043	3649000000-E	876	RIP RAP, CLASS B	703 TON		
0044	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	4,690 SY		
0045	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	296 SF		
0046	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	416 SF		
0047	4430000000-N	1130	DRUMS	171 EA		
0048	4455000000-N	1150	FLAGGER	330 DAY		
0049	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	50 EA		
0050	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	15,115 LF		
0051	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	325 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	150 LF		
0053	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	11 EA		
0054	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,105 LF		
0055	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	118 EA		
0056	5325600000-E	1510	6" WATER LINE	27 LF		
0057	5326600000-E	1510	16" WATER LINE	1,238 LF		
0058	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	8,350 LB		
0059	5558600000-E	1515	16" VALVE	4 EA		
0060	5571600000-E	1515	6" TAPPING SLEEVE & VALVE	1 EA		
0061	5648000000-N	1515	RELOCATE WATER METER	2 EA		
0062	5672000000-N	1515	RELOCATE FIRE HYDRANT	4 EA		
0063	5673000000-E	1515	FIRE HYDRANT LEG	56 LF		
0064	5679200000-E	1515	16" LINE STOP	2 EA		
0065	5686500000-E	1515	WATER SERVICE LINE	21 LF		
0066	5800000000-E	1530	ABANDON 6" UTILITY PIPE	43 LF		
0067	5810000000-E	1530	ABANDON 16" UTILITY PIPE	2,416 LF		
0068	5872600000-E	1550	DIRECTIONAL DRILLING OF *** (16" WATER LINE)	491 LF		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0069	6000000000-E	1605	TEMPORARY SILT FENCE	3,750 LF		
0070	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	195 TON		
0071	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,045 TON		
0072	6012000000-E	1610	SEDIMENT CONTROL STONE	345 TON		
0073	6015000000-E	1615	TEMPORARY MULCHING	8.5 ACR		
0074	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	700 LB		
0075	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	3.5 TON		
0076	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400 LF		
0077	6029000000-E	SP	SAFETY FENCE	1,240 LF		
0078	6030000000-E	1630	SILT EXCAVATION	490 CY		
0079	6036000000-E	1631	MATTING FOR EROSION CONTROL	17,515 SY		
0080	6037000000-E	SP	COIR FIBER MAT	100 SY		
0081	6042000000-E	1632	1/4" HARDWARE CLOTH	250 LF		
0082	6069000000-E	1638	STILLING BASINS	188 CY		
0083	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0084	6071010000-E	SP	WATTLE	370 LF		
0085	6071020000-E	SP	POLYACRYLAMIDE (PAM)	345 LB		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0086	6071030000-E	1640	COIR FIBER BAFFLE	95 LF		
0087	6084000000-E	1660	SEEDING & MULCHING	9 ACR		
0088	6087000000-E	1660	MOWING	9 ACR		
0089	6090000000-E	1661	SEED FOR REPAIR SEEDING	150 LB		
0090	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0091	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0092	6108000000-E	1665	FERTILIZER TOPDRESSING	5.75 TON		
0093	6111000000-E	SP	IMPERVIOUS DIKE	323 LF		
0094	6114500000-N	1667	SPECIALIZED HAND MOWING	20 MHR		
0095	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	38 EA		
0096	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	4 EA		
0097	6120000000-E	SP	CULVERT DIVERSION CHANNEL	18 CY		
0098	6123000000-E	1670	REFORESTATION	0.1 ACR		
0099	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0100	8126000000-N	414	CULVERT EXCAVATION, STA ***** 14+28.00	Lump Sum	L.S.	
0101	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	252 TON		
0102	8196000000-E	420	CLASS A CONCRETE (CULVERT)	161.5 CY		

County: WAKE

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0103	8245000000-E	425	REINFORCING STEEL (CULVERT)	21,045 LB		

1447/Oct31/Q103301.91/D413249960000/E103

Total Amount Of Bid For Entire Project :
